




- LEGEND:
- 01 Flemish bond London stock brick re-pointed in hydraulic lime mortar
 - 01a Exploratory works to establish the extent and properties of movement and deformation. External facing brickwork where the delamination is identified to be carefully demounted. Salvageable materials to be cleaned and stored for re-use.
 - 01b Location of debonding; Flemish bond London stock brick, salvaged or reclaimed, pointed in hydraulic lime mortar
 - 01c Areas of retained brickwork above and below the rebuilt area to be fitted with ties to the structural engineer's specification
 - 02 Stucco with rusticated relief detailing
 - 03 Flat gauged brick arch. Red brick
 - 03a Damaged flat gauge brick arches replaced with new using lime putty to match existing
 - 04 Reinstated Flemish bond London stock string course
 - 05 Coping
 - 06 Painted door case
 - 07 Painted render reveals to windows to be reinstated
 - 08 Existing window cills WS_01, 02, 03 carefully demounted, cleaned stored and reused
 - 09 Windows WS_01, 02, 03 and internal shutters to be removed and stored. Reinstated post remedial works
 - 10 Existing second floor metal window railings WS_01, 02, 03 demounted cleaned and stored for reinstatement post remedial works

Note: hatching not to scale or indicative of brick bond.



Dimensions must not be scaled from this drawing. This drawing is copyright and must not be reproduced.

Revisions Rev A 05.03.2020 Additional notes added

Proposed Elevation

4 John Street, London
for

Mr J Moores

Trevor Hewett RIBA

The Architecture Studio, 135 Corve Street, Ludlow, SY8 2PG
Tel: 01584 877992 Email: info@trevorhewett.co.uk
www.trevorhewett.co.uk

Proposed Elevations

Date: 25.02.2020

Status: Preliminary

Scale: 1:50 @ A1 - 1:100 @ A3

Drg. No: Jcsm.15 - 200b