

<u>Legend</u>

Balustrade

Composit Decking

Porcelain Paving

Hardwood Bench

GRP Planters

Soft Landscaping

Green Wall

Green Roof

Coping Stone

Proposed Levels +100.00

Top of Wall + TOW

Top of Green Wall + TOGW

Top of Pergola + TOP

General Notes

- 1. Stairwell access pop-up to be boxed off and hold hold, finished with a Green Biodiverse Roof
- 2. Paving: 600x600mm mid-dark grey porcelain paving:
- 3. Decking: 150x20mm solid composite decking boards.
- 4. Planters: Bespoke fabricated lightweight planters.
- 5. Balustrade: Bespoke fabricated balustrade and coping stone,
- 6. Bar Island: A freestanding timber structure, natural stone worktop with small storage drawers.
- 7. Pergola: Sliding frame with a retracable canvas awning. Frame to be clad in wood.
- 8. Green 'Biodiverse' Roof
- 9. Green 'Biodiverse' Wall
- 10. In-built wooden benches.

Please Note:

This detail is to be referred to only as a guide; the responsibility for the integrity and safety of the construction remains with the appointed sub-contractor.

It shall be their reponsibility to ensure all methods and materials are fit for purpose and that all proposed levels against buildings do not breach the damp proof course.

Any issues with this drawing should be raised with Aralia before construction work commences.

All drawings and details remain the property of Aralia unless agreed in writing prior to document issue. No changes are permitted without consultation and consent in writing by Aralia.



Drawing Title: General Arrangement Plan: Proposed

Drawing Ref: AR-WILL001-D-201 Planning-R01

| Client Contact: Henry Goodfellow | | Email: Henry@aralia.org.uk |
|----------------------------------|---------------------|----------------------------|
| Site: | 3 Willoughby Street | Client: Rob Stephens |
| Drawn By: | H.Goodfellow | Date: 08.04.2020 |
| Revision: | R1 | Scale: 1-50 @ A3 |