

---

# GROUND MOVEMENT ASSESSMENT REPORT

---


10 Glenmore Road  
London  
NW3 4DB

Client: Mr B and Mrs L Walford





Engineer: Structure Workshop

J20026

March 2020



## Document Control

|                                     |  |   |                    |   |
|-------------------------------------|--|---|--------------------|---|
| <b>Project title</b>                | 10 Glenmore Road, London NW3 4DB   |   | <b>Project ref</b> | J20026  |
| <b>Report prepared by</b>           |  |   |                    |   |
|                                     | Matthew Legg BEng FGS<br>Senior Geotechnical Engineer                              |   |                    |   |
| <b>Report checked by</b>            |   |   |                    |   |
|                                     | Matthew Penfold MSci MSc DIC CGeol FGS<br>Principal Geotechnical Engineer          |   |                    |   |
| <b>Report approved for issue by</b> |   |   |                    |   |
|                                     | Steve Branch BSc MSc CGeol FGS FRGS<br>Managing Director                           |   |                    |   |
| <b>Issue No</b>                     | <b>Status</b>  | <b>Amendment Details</b>                            | <b>Date</b>        | <b>Approved for Issue</b>   |
| 1                                   | Final  |   | 17 February 2020   |   |
| 2                                   | Final  | Amended to include assessment of Thames Water sewer | 6 March 2020       |   |
| 3                                   | Final  | Amended to address comments by Campbell Reith       | 23 March 2020      |  |

This report has been issued by the GEA office indicated below. Any enquiries regarding the report should be directed to the project engineer at the office indicated below or to Steve Branch in our main Herts office.

|   |                        |                   |
|---|------------------------|-------------------|
| ✓ | <b>Hertfordshire</b>   | tel 01727 824666  |
|   | <b>Nottinghamshire</b> | tel 01509 674888  |
|   | <b>Manchester</b>      | tel 0161 209 3032 |

Geotechnical & Environmental Associates Limited (GEA) disclaims any responsibility to the Client and others in respect of any matters outside the scope of this work. This report has been prepared with reasonable skill, care and diligence within the terms of the contract with the Client and taking account of the manpower, resources, investigation and testing devoted to it in agreement with the Client. This report is confidential to the Client and GEA accepts no responsibility of whatsoever nature to third parties to whom this report or any part thereof is made known, unless formally agreed beforehand. Any such party relies upon the report at their own risk. This report may provide advice based on an interpretation of legislation, guidance notes and codes of practice. GEA does not however provide legal advice and if specific legal advice is required a lawyer should be consulted.

© Geotechnical & Environmental Associates Limited 2020.

## CONTENTS

### Part 1: INVESTIGATION REPORT

|     |                                     |   |
|-----|-------------------------------------|---|
| 1.0 | INTRODUCTION                        | 1 |
| 1.1 | Proposed Development                | 1 |
| 1.2 | Purpose of Work                     | 1 |
| 1.3 | Limitations                         | 1 |
| 2.0 | THE SITE                            | 1 |
| 2.1 | Site Description                    | 1 |
| 2.2 | Geology                             | 2 |
| 2.3 | Hydrogeology                        | 2 |
| 3.0 | GROUND MOVEMENT ASSESSMENT          | 2 |
| 3.1 | Basis of Ground Movement Assessment | 3 |
| 3.2 | Construction Sequence               | 3 |
| 4.0 | GROUND MOVEMENTS                    | 4 |
| 4.1 | Model Used                          | 4 |
| 4.2 | Results                             | 5 |
| 5.0 | BUILDING DAMAGE ASSESSMENT          | 6 |
| 5.1 | Damage to Neighbouring Structures   | 6 |
| 5.2 | Movements along Thames Water Sewer  | 6 |
| 5.3 | Monitoring of Ground Movements      | 6 |
| 6.0 | CONCLUSIONS                         | 7 |

### APPENDIX

## 1.0 INTRODUCTION

Geotechnical and Environmental Associates (GEA) has been commissioned by Mr and Mrs Walford, to carry out a Ground Movement Analysis (GMA) of the proposed basement structure at 10 Glenmore Road, London NW3 4DB. Structure Workshop are the structural engineers for the project.

The site has been the subject of a ground investigation by Connaughts Site Investigation Ltd (report ref: 0762, dated August 2019), which is referred to where appropriate within this report.

### 1.1 Proposed Development

It is understood that it is proposed to extend and deepen the existing single level basement below the footprint of the existing house. Formation level for the basement is understood to be 62.70 m AOD, which will require an excavation of 1.50 m and 2.71 m, with the basement retaining walls being constructed through the conventional underpinning of existing foundations. The levels of the existing foundations are as such that the depth of underpinning will vary between 0.40 m and 1.00 m, such that the scale of the work is considered to be very minimal.

This report is specific to the proposed development and the advice herein should be reviewed if the development proposals are amended.

### 1.2 Purpose of Work

The principal technical objectives of the work carried out were as follows:

- to review and assess the ground conditions and hydrogeological regime; and
- to assess the possible impact of the proposed development on the surrounding structures.

### 1.3 Limitations

The conclusions and recommendations made in this report are limited to those that can be made on the basis of the investigation. The results of the work should be viewed in the context of the range of data sources consulted, the number of locations where the ground was sampled and the number of soil, gas or groundwater samples tested; no liability can be accepted for information in other data sources or conditions not revealed by the sampling or testing. Any comments made on the basis of information obtained from the client or other third parties are given in good faith on the assumption that the information is accurate; no independent validation of such information has been made by GEA.

## 2.0 THE SITE

### 2.1 Site Description

The site is located in the area of Hampstead within the London Borough of Camden, northwest London, approximately 320 m southwest of Belsize Park London Underground station. It may be additionally located by National Grid Reference (NGR) 527199,184911.

The site forms a rectangular shaped area with maximum dimensions of approximately 20 m east-west by 6 m north-south and is occupied by a three-storey terraced property with a partial basement below the front third of the building footprint and a small courtyard garden in the west of the site. It is bordered to the north and south by Nos 8 and 12 Glenmore Road respectively, which are of similar construction to the house occupying the site and it is understood that both include similar basements. The site is bordered to the west by private gardens of properties fronting Glenloch Road.

## 2.2 Geology

The Geological Survey map of the area (sheet 256) indicates that the site is directly underlain by the London Clay Formation.

The Connaughts investigation comprised a number of manually excavated trial pits adjacent to existing elevations, to determine the configuration of existing foundations, and a single window sample borehole advanced to a depth of 5.1 m within the rear garden. The borehole encountered made ground to a depth of 1.6 m, whereupon London Clay was encountered and was described as comprising firm becoming stiff medium strength brown with some light grey veining. The borehole was terminated at 5.1 m on a claystone.

GEA has previously carried out a number of investigations close to the site, which confirmed the expected ground conditions and the findings of the Connaughts investigation, in that below a generally moderate thickness of made ground, the London Clay was encountered and extended to the maximum depth investigated, of 25.0 m.

## 2.3 Hydrogeology

The London Clay Formation is classified as an Unproductive Stratum and non-aquifer with negligible significance for water supply or river base flow. This means that a continuous groundwater table will not exist below the site.

Groundwater was not encountered during the previous investigation and although a groundwater monitoring standpipe was installed, it is understood that no monitoring has been undertaken to date.

## 3.0 GROUND MOVEMENT ANALYSIS

The sides of a basement excavation will move to some extent regardless of how they are supported. The movement will typically be both horizontal and vertical and will be influenced by the engineering properties of the ground, groundwater level and flow, the efficiency of the various support systems employed during underpinning and the efficiency or stiffness of any support structures used.

An analysis has been carried out of the likely movements arising from the proposed basement excavation and the results of this analysis have been used to predict the effect of these movements on surrounding structures.

### 3.1 Basis of Ground Movement Assessment

#### 3.1.1 Nearby Sensitive Structures

Sensitive structures relevant to this assessment are the neighbouring Nos 8 and 12 Glenmore Road to the north and south respectively. Based on the proposed size and depth of excavation, all other surrounding buildings and structures are considered to be outside of the zone of influence of the proposed basement.

A plan showing the locations of the site and neighbouring buildings is included in the appendix, which also indicates the individual elevations assessed for associated building damage and the referencing used within the analysis.

The founding levels of the party walls with the two neighbouring properties were determined in part by the previous investigation and provided by Structure Workshop within their Basement Impact Assessment (BIA) document (ref: 19029.R01.P2, dated November 2019). Therefore, it is understood that No 8 Glenmore is bearing at a level of 63.71 m AOD, whilst No 12 is bearing at a level of 63.09 m AOD and these levels have been adopted for the analysis. Survey drawings for the existing house indicates varying eave levels due to the shape of the roof. Therefore, a conservative worst-case building height (foundation to top of eaves) of 9m has been adopted for each of the neighbouring elevations.

In addition to the neighbouring properties, a combined sewer is indicated by Thames Water as being present below Glenmore Road at a depth of approximately 2.90m and it has been estimated to be approximately 6.00m from the front elevation of the site. The Thames Water asset drawing is included in the appendix.

The following drawings have been referred to, where relevant, to model the sensitive structures and proposed excavation.

| Drawing Reference                                 | Drawing Title                  |
|---|--------------------------------|
| 19029.SK02 (undated)                              | Foundation Loads               |
| 18495 – 10 Glenmore Road – G, dated November 2018 | Measured Survey – Ground Floor |
| 18495 – 10 Glenmore Road – B, dated November 2018 | Measured Survey – Basement     |
| 18495 – 10 Glenmore Road – S, dated December 2018 | Measured Survey – Sections     |

### 3.2 Construction Sequence

The following sequence of operations is detailed in Structure Workshop BIA document:

1. Install sacrificial sheet piles to support existing lightwell;
2. Underpin front elevation;
3. Install RC retaining wall against sheet piles for lightwell;
4. Prop existing ground floor structure;
5. Underpin party walls and rear elevation using a ‘hit and miss’ method of panel widths no more than 1 m;

6. Excavate rear area of extended basement;
7. Remove rear retaining wall of existing basement;
8. Excavate whole basement to new founding level;
9. Install new drainage runs followed by basement slab;
10. Install new load bearing walls in basement and box frames; and
11. Remove temporary propping.

The underpins will be adequately laterally propped and sufficiently dowelled together, and the concrete will be cast and adequately cured prior to excavation of the basement and removal of the formwork and supports. It is assumed that the corners of the excavation will be locally stiffened by cross-bracing or similar and that the new retaining walls will not be cantilevered at any stage during the construction process. It is assumed that adequate temporary propping of the new retaining walls, particularly at the top level, will occur at all times prior to the construction of permanent concrete floor slabs.

#### 4.0 GROUND MOVEMENTS

An assessment of ground movements within and surrounding the excavation has been undertaken using the P-Disp Version 20.0 – Build 12 and X-Disp Version 20.0 software packages licensed from the OASYS suite of geotechnical modelling software from Arup. This program is commonly used within the ground engineering industry and is considered to be an appropriate tool for this analysis. The use of the P-Disp program is based on the assumption that the soils behave elastically, which provides a reasonable approximation of soil behaviour at small strains.

For the purpose of these analyses, the corners have been defined by x and y coordinates, with the x-direction orientated approximately northeast-southwest, whilst the y-direction is orientated approximately northwest-southeast. Vertical movement is in the z-direction. Wall lengths of less than 10 m have been modelled as 1 m long structural elements, while walls greater than 10 m in length have been modelled as 2 m elements to reflect their greater stiffness.

It is assumed that suitable propping will be provided during the construction of the basement and in the permanent condition, such that the walls can be considered to be stiff for the purpose of the ground movement modelling.

The full outputs of all the analyses can be provided on request but samples of the output movement contour plots and the tables of movements are included within the appendix.

#### 4.1 Model Used

Vertical movement, in the form of heave, will arise from the unloading of the London Clay due to the reduction of vertical stress, at least in the short-term. Undrained soil parameters have been used to estimate the potential short-term movements, which include the “immediate” or elastic movements as a result of the basement excavation. Drained parameters have been used to provide an estimate of the total movement, which includes long term swelling or creep that will continue for a number of years.

The elastic analysis requires values of soil stiffness at various levels to calculate displacements. Values of stiffness for the soils at this site are readily available from published data and we have used a well-established method to provide our estimates. Published data<sup>1</sup> indicates stiffness values of  $750 \times C_u$  for the London Clay and a ratio of  $E'$  to  $E_u$  of 0.75, and it is considered that this provides a sensible approach. The profile of the underlying ground conditions used in the analysis has been interpolated from the results of aforementioned nearby GEA site investigations, with a design line of  $C_u = 5z + 45 \text{ kN/m}^2$  adopted for the London Clay.

The soil parameters used in this analysis are tabulated below, which have been estimated from the information contained within the Connaughts Site Investigation Ltd report and assumed parameters interpreted from archive boreholes on the GEA database.

| Stratum     | Level range (m AOD) | $E_u$ (MPa)  | $E'$ (MPa)  |
|-------------|---------------------|--------------|-------------|
| Made Ground | 65.4 to 63.8        | 15           | 11.2        |
| London Clay | 63.8 to 25.4        | 33.75 to 201 | 25.2 to 150 |

A rigid boundary for the analysis has been set at 25.4 m AOD, which equates to 40 m below ground level. Below this depth the London Clay is not considered to be affected by the scale of the development and the soils are considered to be essentially incompressible.

The existing basement that will be lowered will result in unloading of approximately  $30 \text{ kN/m}^2$ , whilst the proposed single level basement extension will comprise a maximum excavation depth of approximately 2.70 m below the existing ground floor level, which will result in a net unloading of about  $50 \text{ kN/m}^2$ .

Proposed line loads have been provided by Structure Workshop, with foundation pressures equating to 57 kPa and 116 kPa, whilst a slab loading of 7.2 kPa will also exist across the area of the basement extension, as indicated by the appended foundation load mark-up. These loads have been taken into account in analysing the vertical movements.

## 4.2 Results

The full predicted movements are summarised in the contour plots and tables within appendix; the results are presented to the degree of accuracy required to allow predicted variations in ground movements around the structure(s) to be illustrated, but may not reflect the anticipated accuracy of the predictions.

The P-Disp analysis indicates that less 5mm of heave can be expected at the centre of the proposed basement excavation, whilst along a number of the underpinned elevations, settlements of less than 5mm can be expected to occur due to the proposed loadings.

If a compressible material is used beneath the slab, it will need to be designed to be able to resist the potential uplift forces generated by the ground movements. In this respect, potential heave pressures are typically taken to equate to around 40% of the total unloading pressure.

1 Burland JB, Standing, JR, and Jardine, FM (2001) *Building response to tunnelling, case studies from construction of the Jubilee Line Extension* CIRIA Special Publication 200



## 5.0 BUILDING DAMAGE ASSESSMENT

Published data for ground movements associated with underpinned retaining walls and the subsequent excavation of a new basement is limited compared to other types of retaining wall. It is possible to use the well-documented predictions and movement curves for embedded retaining walls contained within CIRIA C760<sup>2</sup>, although this approach is considered to be conservative. However, in order to model potential movements associated with the installation of the underpins, the movement curves for ‘installation of planar diaphragm wall in stiff clay’ has been adopted.

For the excavation phase following the underpinning, as the existing building will be in place during the construction of the proposed basement extension, the walls being underpinned, in addition to the use of temporary propping, will provide a level of restraint to the underpins, which would generally be expected to result in negligible movement. The magnitude of the any movement will also be controlled to a large extent by the quality of workmanship. For the horizontal movements, a ground movement curve assuming that horizontal settlement behind the wall will be equivalent to 0.15% of the retained height, with movement that diminishes with distance from the wall according to the trend line set by a wall within clay (see Fig 6.15a of CIRIA C760), has been adopted. These movements have been combined the vertical movements derived from the P-Disp model. For the purpose of this analysis, the total vertical movements derived from the P-Disp model have been adopted as the most critical case in terms of potential damage to the neighbouring properties.

In order to address the potential impact of the proposed underpinning, the movements from both the installation and excavation phases have been combined to enable a damage assessment to be undertaken of all the potential movements.

### 5.1 Damage to Neighbouring Structures

The Camden Planning Guidance for Basements and Lightwells (CPG Basements; March 2018) states that “applicant must demonstrate in the Basement Impact Assessment that the basement scheme has a risk of damage to neighbouring properties no higher than Burland Scale 1 ‘very slight.’”

As a result of the limited movements expected to arise from the relatively small-scale excavation, the assessment has indicated that the predicted damage to all of the neighbouring elevations will fall within Category 0 and Negligible building damage and is therefore within allowable limits.

### 5.2 Movements along Thames Water Sewer

The ground movement assessment has indicated that negligible movements are expected to arise from the proposed basement excavation, with movements of less than 5mm occurring outside of the basement footprint. Given the depth and distance of the sewer from the basement excavation, the proposed development is not considered likely to have an impact on the asset, such that a detailed assessment is not required.

### 5.3 Monitoring of Ground Movements

The predictions of ground movement based on the ground movement analysis should be checked by monitoring of adjacent properties and structures. The structures to be monitored

<sup>2</sup> Gaba, A, Hardy, S, Powrie, W, Doughty, L and Selemetas, D (2017) *Embedded retaining walls – guidance for economic design* CIRIA Report C760.

during the construction stages should include all of the sensitive structures included within the assessment.

The precise monitoring strategy will be developed at a later stage and it will be subject to discussions and agreements with the owners of the adjacent properties and structures. Contingency measures will be implemented if movements of the adjacent structures exceed predefined trigger levels. Both contingency measures and trigger levels will need to be developed within a future monitoring specification for the works.

## 6.0 CONCLUSIONS

The analysis has concluded that the predicted damage to the neighbouring properties from the construction of the underpins and excavations would be 'Negligible' or less and therefore the damage that would occur would fall within the acceptable limits.

Whilst it is recommended that movement monitoring is carried out on all structures prior to and during the proposed excavation and construction, it is unlikely that specification of these works will be required as part of the planning conditions, but may be required in order to satisfy party wall awards.

## **APPENDIX**

Proposed Foundation Loads

Plan of proposed basement and sensitive structures

Thames Water Asset Drawing

### **P-DISP ANALYSIS:**

Input Data

Short Term Movement Plot

Total Movement Plot

### **X-DISP ANALYSIS**

Input Data


Contour Plots of Combined Vertical Movements

Contour Plots of Combined Horizontal Movements


**BUILDING DAMAGE ASSESSMENT – RESULTS TABLE**

**NOTES:**  
 This drawing is to be read in conjunction with all other Architects and Engineers drawings, details and specifications.  
 Any discrepancies in the arrangement and details discovered on site, or otherwise, are to be reported to the Architect or Engineer immediately.  
 All dimensions in mm.  
 Do not scale from this drawing. Setting out to Architect's details.

- KEY:**
- 1. GFL party walls
  - 2. GFL rear wall
  - 3. BFL underpin (incl. spine wall weight)
  - 4. BFL retaining wall
  - 5. BFL front wall



Ex: DL = 140 kN/m LL = 18 kN/m



INCREASED DEAD LOAD  
 DUE TO ADDITION OF  
 BASEMENT SLAB = 7.2 kN/m<sup>2</sup>

Ex DL = 140 kN/m LL 18 kN/m

| Wall Type | EXISTING (U.M.O)             |         | PROPOSED                        |         |
|-----------|------------------------------|---------|---------------------------------|---------|
|           | DL                           | LL      | DL                              | LL      |
| 1.        | 70 kN/m                      | 5 kN/m  | 70 kN/m                         | 5 kN/m  |
| 2.        | 40 kN/m                      | 11 kN/m | 40 kN/m                         | 11 kN/m |
| 3.        | 145 kN/m                     | 28 kN/m | 155 kN/m                        | 28 kN/m |
| 4.        | <del>5 kN/m</del><br>64 kN/m | 19 kN/m | <del>67 kN/m</del><br>79.2 kN/m | 19 kN/m |
| 5.        | 100 kN/m                     | 13 kN/m | 110 kN/m                        | 13 kN/m |

ALL LOADS PROVIDED ARE UNFACTORED

PRELIMINARY

STRUCTURE WORKSHOP  
 Engineering & Technical Design  
 4 Bliffa Yard  
 London SE17 3BA  
 020 7761 2616  
 www.structureworkshop.co.uk

| No. | Description | Date |
|-----|-------------|------|
|     |             |      |



project  
**Glenmore Road**  
 title  
**Foundation Loads**

scale  
 1:50 @ A1  
 drawn  
 WW  
 app.  
 SR  
 No.  
 19029.SK02  
 rev.  
 P1

© RESERVED

|               |           |         |
|---------------|-----------|---------|
| Job No.       | Sheet No. | Rev.    |
| J20026        |           |         |
| Drg. Ref.     |           |         |
| Made by<br>ML | Date      | Checked |

Legend



# Asset location search



## Property Searches

Genever & Partners  
Keyes House Keyes House

LONDON  
SW1V 3NA

**Search address supplied** 10  
Glenmore Road  
London  
NW3 4DB

**Your reference** 5022

**Our reference** ALS/ALS Standard/2019\_4001196

**Search date** 13 May 2019

### Keeping you up-to-date

#### Notification of Price Changes

From 1 September 2018 Thames Water Property Searches will be increasing the price of its Asset Location Search in line with RPI at 3.23%.

For further details on the price increase please visit our website: [www.thameswater-propertysearches.co.uk](http://www.thameswater-propertysearches.co.uk)  
Please note that any orders received with a higher payment prior to the 1 September 2018 will be non-refundable.



Thames Water Utilities Ltd  
Property Searches, PO Box 3189, Slough SL1 4WW  
DX 151280 Slough 13



[searches@thameswater.co.uk](mailto:searches@thameswater.co.uk)  
[www.thameswater-propertysearches.co.uk](http://www.thameswater-propertysearches.co.uk)



0845 070 9148



**Search address supplied:** 10, Glenmore Road, London, NW3 4DB

Dear Sir / Madam

**An Asset Location Search is recommended when undertaking a site development.** It is essential to obtain information on the size and location of clean water and sewerage assets to safeguard against expensive damage and allow cost-effective service design.

The following records were searched in compiling this report: - the map of public sewers & the map of waterworks. Thames Water Utilities Ltd (TWUL) holds all of these.

This search provides maps showing the position, size of Thames Water assets close to the proposed development and also manhole cover and invert levels, where available.

Please note that none of the charges made for this report relate to the provision of Ordnance Survey mapping information. The replies contained in this letter are given following inspection of the public service records available to this company. No responsibility can be accepted for any error or omission in the replies.

You should be aware that the information contained on these plans is current only on the day that the plans are issued. The plans should only be used for the duration of the work that is being carried out at the present time. Under no circumstances should this data be copied or transmitted to parties other than those for whom the current work is being carried out.

Thames Water do update these service plans on a regular basis and failure to observe the above conditions could lead to damage arising to new or diverted services at a later date.

## Contact Us

If you have any further queries regarding this enquiry please feel free to contact a member of the team on 0845 070 9148, or use the address below:

Thames Water Utilities Ltd  
Property Searches  
PO Box 3189  
Slough  
SL1 4WW

Email: [searches@thameswater.co.uk](mailto:searches@thameswater.co.uk)

Web: [www.thameswater-propertysearches.co.uk](http://www.thameswater-propertysearches.co.uk)

## Waste Water Services

**Please provide a copy extract from the public sewer map.**

Enclosed is a map showing the approximate lines of our sewers. Our plans do not show sewer connections from individual properties or any sewers not owned by Thames Water unless specifically annotated otherwise. Records such as "private" pipework are in some cases available from the Building Control Department of the relevant Local Authority.

Where the Local Authority does not hold such plans it might be advisable to consult the property deeds for the site or contact neighbouring landowners.

This report relates only to sewerage apparatus of Thames Water Utilities Ltd, it does not disclose details of cables and or communications equipment that may be running through or around such apparatus.

The sewer level information contained in this response represents all of the level data available in our existing records. Should you require any further Information, please refer to the relevant section within the 'Further Contacts' page found later in this document.

For your guidance:

- The Company is not generally responsible for rivers, watercourses, ponds, culverts or highway drains. If any of these are shown on the copy extract they are shown for information only.
- Any private sewers or lateral drains which are indicated on the extract of the public sewer map as being subject to an agreement under Section 104 of the Water Industry Act 1991 are not an 'as constructed' record. It is recommended these details be checked with the developer.

## Clean Water Services

**Please provide a copy extract from the public water main map.**

Enclosed is a map showing the approximate positions of our water mains and associated apparatus. Please note that records are not kept of the positions of individual domestic supplies.

For your information, there will be a pressure of at least 10m head at the outside stop valve. If you would like to know the static pressure, please contact our Customer Centre on 0800 316 9800. The Customer Centre can also arrange for a full flow and pressure test to be carried out for a fee.



# Asset location search



## Property Searches

For your guidance:

- Assets other than vested water mains may be shown on the plan, for information only.
- If an extract of the public water main record is enclosed, this will show known public water mains in the vicinity of the property. It should be possible to estimate the likely length and route of any private water supply pipe connecting the property to the public water network.

### **Payment for this Search**

A charge will be added to your suppliers account.

## Further contacts:

### Waste Water queries

Should you require verification of the invert levels of public sewers, by site measurement, you will need to approach the relevant Thames Water Area Network Office for permission to lift the appropriate covers. This permission will usually involve you completing a TWOSA form. For further information please contact our Customer Centre on Tel: 0845 920 0800. Alternatively, a survey can be arranged, for a fee, through our Customer Centre on the above number.

If you have any questions regarding sewer connections, budget estimates, diversions, building over issues or any other questions regarding operational issues please direct them to our service desk. Which can be contacted by writing to:

Developer Services (Waste Water)  
Thames Water  
Clearwater Court  
Vastern Road  
Reading  
RG1 8DB


Tel: 0800 009 3921  
Email: [developer.services@thameswater.co.uk](mailto:developer.services@thameswater.co.uk)

### Clean Water queries

Should you require any advice concerning clean water operational issues or clean water connections, please contact:

Developer Services (Clean Water)  
Thames Water  
Clearwater Court  
Vastern Road  
Reading  
RG1 8DB

Tel: 0800 009 3921  
Email: [developer.services@thameswater.co.uk](mailto:developer.services@thameswater.co.uk)



The width of the displayed area is 200 m and the centre of the map is located at OS coordinates 527212,184932

The position of the apparatus shown on this plan is given without obligation and warranty, and the accuracy cannot be guaranteed. Service pipes are not shown but their presence should be anticipated. No liability of any kind whatsoever is accepted by Thames Water for any error or omission. The actual position of mains and services must be verified and established on site before any works are undertaken.

Based on the Ordnance Survey Map with the Sanction of the controller of H.M. Stationery Office, License no. 100019345 Crown Copyright Reserved.

NB. Levels quoted in metres Ordnance Newlyn Datum. The value -9999.00 indicates that no survey information is available



















| Manhole Reference | Manhole Cover Level | Manhole Invert Level |
|-------------------|---------------------|----------------------|
| 181A              | n/a                 | n/a                  |
| 1903              | 64.43               | 60.02                |
| 181B              | n/a                 | n/a                  |
| 181C              | n/a                 | n/a                  |
| 1801              | n/a                 | n/a                  |
| 2904              | 67.6                | 62.19                |
| 291A              | n/a                 | n/a                  |
| 2905              | 64.04               | 59.84                |
| 291B              | n/a                 | n/a                  |
| 2903              | 67.27               | 62.74                |
| 2802              | 64.04               | 58.75                |
| 2902              | 66.47               | 62.08                |
| 291C              | n/a                 | n/a                  |
| 10AB              | n/a                 | n/a                  |
| 1901              | 61.97               | 57.88                |
| 1802              | 61.84               | 57.63                |

The position of the apparatus shown on this plan is given without obligation and warranty, and the accuracy cannot be guaranteed. Service pipes are not shown but their presence should be anticipated. No liability of any kind whatsoever is accepted by Thames Water for any error or omission. The actual position of mains and services must be verified and established on site before any works are undertaken.








# ALS Sewer Map Key

## Public Sewer Types (Operated & Maintained by Thames Water)

-  **Foul:** A sewer designed to convey waste water from domestic and industrial sources to a treatment works.
-  **Surface Water:** A sewer designed to convey surface water (e.g. rain water from roofs, yards and car parks) to rivers or watercourses.
-  **Combined:** A sewer designed to convey both waste water and surface water from domestic and industrial sources to a treatment works.
-  Trunk Surface Water
-  Trunk Foul
-  Storm Relief
-  Trunk Combined
-  Vent Pipe
-  Bio-solids (Sludge)
-  Proposed Thames Surface Water Sewer
-  Proposed Thames Water Foul Sewer
-  Gallery
-  Foul Rising Main
-  Surface Water Rising Main
-  Combined Rising Main
-  Sludge Rising Main
-  Proposed Thames Water Rising Main
-  Vacuum





## Sewer Fittings

A feature in a sewer that does not affect the flow in the pipe. Example: a vent is a fitting as the function of a vent is to release excess gas.

-  Air Valve
-  Dam Chase
-  Fitting
-  Meter
-  Vent Column




## Operational Controls

A feature in a sewer that changes or diverts the flow in the sewer. Example: A hydrobrake limits the flow passing downstream.

-  Control Valve
-  Drop Pipe
-  Ancillary
-  Weir






## End Items

End symbols appear at the start or end of a sewer pipe. Examples: an Undefined End at the start of a sewer indicates that Thames Water has no knowledge of the position of the sewer upstream of that symbol, Outfall on a surface water sewer indicates that the pipe discharges into a stream or river.

-  Outfall
-  Undefined End
-  Inlet






## Other Symbols

Symbols used on maps which do not fall under other general categories








-  /  Public/Private Pumping Station
-  Change of characteristic indicator (C.O.C.I.)
-  Invert Level
-  Summit

## Areas

Lines denoting areas of underground surveys, etc.


-  Agreement
-  Operational Site
-  Chamber
-  Tunnel
-  Conduit Bridge

## Other Sewer Types (Not Operated or Maintained by Thames Water)

-  Foul Sewer
-  Surface Water Sewer
-  Combined Sewer
-  Gully
-  Culverted Watercourse
-  Proposed
-  Abandoned Sewer

### Notes:

- 1) All levels associated with the plans are to Ordnance Datum Newlyn.
- 2) All measurements on the plans are metric.
- 3) Arrows (on gravity fed sewers) or flecks (on rising mains) indicate direction of flow.
- 4) Most private pipes are not shown on our plans, as in the past, this information has not been recorded.
- 5) 'na' or '0' on a manhole level indicates that data is unavailable.
- 6) The text appearing alongside a sewer line indicates the internal diameter of the pipe in millimetres. Text next to a manhole indicates the manhole reference number and should not be taken as a measurement. If you are unsure about any text or symbology present on the plan, please contact a member of Property Insight on 0845 070 9148.



The width of the displayed area is 200 m and the centre of the map is located at OS coordinates 527212, 184932.








The position of the apparatus shown on this plan is given without obligation and warranty, and the accuracy cannot be guaranteed. Service pipes are not shown but their presence should be anticipated. No liability of any kind whatsoever is accepted by Thames Water for any error or omission. The actual position of mains and services must be verified and established on site before any works are undertaken.

Based on the Ordnance Survey Map with the Sanction of the controller of H.M. Stationery Office, License no. 100019345 Crown Copyright Reserved.







# ALS Water Map Key

## Water Pipes (Operated & Maintained by Thames Water)


- 
**Distribution Main:** The most common pipe shown on water maps. With few exceptions, domestic connections are only made to distribution mains.
- 
**Trunk Main:** A main carrying water from a source of supply to a treatment plant or reservoir, or from one treatment plant or reservoir to another. Also a main transferring water in bulk to smaller water mains used for supplying individual customers.
- 
**Supply Main:** A supply main indicates that the water main is used as a supply for a single property or group of properties.
- 
**Fire Main:** Where a pipe is used as a fire supply, the word FIRE will be displayed along the pipe.
- 
**Metered Pipe:** A metered main indicates that the pipe in question supplies water for a single property or group of properties and that quantity of water passing through the pipe is metered even though there may be no meter symbol shown.
- 
**Transmission Tunnel:** A very large diameter water pipe. Most tunnels are buried very deep underground. These pipes are not expected to affect the structural integrity of buildings shown on the map provided.
- 
**Proposed Main:** A main that is still in the planning stages or in the process of being laid. More details of the proposed main and its reference number are generally included near the main.

| PIPE DIAMETER               | DEPTH BELOW GROUND |
|-----------------------------|--------------------|
| Up to 300mm (12")           | 900mm (3')         |
| 300mm - 600mm (12" - 24")   | 1100mm (3' 8")     |
| 600mm and bigger (24" plus) | 1200mm (4')        |

## Valves

-  General Purpose Valve
-  Air Valve
-  Pressure Control Valve
-  Customer Valve

## Hydrants








-  Single Hydrant

## Meters










-  Meter

## End Items

Symbol indicating what happens at the end of a water main.

-  Blank Flange
-  Capped End
-  Emptying Pit
-  Undefined End
-  Manifold
-  Customer Supply
-  Fire Supply



## Operational Sites

-  Booster Station
-  Other
-  Other (Proposed)
-  Pumping Station
-  Service Reservoir
-  Shaft Inspection
-  Treatment Works
-  Unknown
-  Water Tower

## Other Symbols

-  Data Logger

## Other Water Pipes (Not Operated or Maintained by Thames Water)

-  **Other Water Company Main:** Occasionally other water company water pipes may overlap the border of our clean water coverage area. These mains are denoted in purple and in most cases have the owner of the pipe displayed along them.
-  **Private Main:** Indicates that the water main in question is not owned by Thames Water. These mains normally have text associated with them indicating the diameter and owner of the pipe.

## Terms and Conditions

All sales are made in accordance with Thames Water Utilities Limited (TWUL) standard terms and conditions unless previously agreed in writing.

1. All goods remain in the property of Thames Water Utilities Ltd until full payment is received.
2. Provision of service will be in accordance with all legal requirements and published TWUL policies.
3. All invoices are strictly due for payment 14 days from due date of the invoice. Any other terms must be accepted/agreed in writing prior to provision of goods or service, or will be held to be invalid.
4. Thames Water does not accept post-dated cheques-any cheques received will be processed for payment on date of receipt.
5. In case of dispute TWUL's terms and conditions shall apply.
6. Penalty interest may be invoked by TWUL in the event of unjustifiable payment delay. Interest charges will be in line with UK Statute Law 'The Late Payment of Commercial Debts (Interest) Act 1998'.
7. Interest will be charged in line with current Court Interest Charges, if legal action is taken.
8. A charge may be made at the discretion of the company for increased administration costs.

A copy of Thames Water's standard terms and conditions are available from the Commercial Billing Team (cashoperations@thameswater.co.uk).

We publish several Codes of Practice including a guaranteed standards scheme. You can obtain copies of these leaflets by calling us on 0800 316 9800

If you are unhappy with our service you can speak to your original goods or customer service provider. If you are not satisfied with the response, your complaint will be reviewed by the Customer Services Director. You can write to her at: Thames Water Utilities Ltd. PO Box 492, Swindon, SN38 8TU.

If the Goods or Services covered by this invoice falls under the regulation of the 1991 Water Industry Act, and you remain dissatisfied you can refer your complaint to Consumer Council for Water on 0121 345 1000 or write to them at Consumer Council for Water, 1st Floor, Victoria Square House, Victoria Square, Birmingham, B2 4AJ.

### Ways to pay your bill

| Credit Card  | BACS Payment  | Telephone Banking   | Cheque  |
|--|---|---|---|
| <p>Call <b>0845 070 9148</b> quoting your invoice number starting CBA or ADS / OSS</p> | <p>Account number <b>90478703</b><br/>Sort code <b>60-00-01</b><br/>A remittance advice must be sent to:<br/><b>Thames Water Utilities Ltd., PO Box 3189, Slough SL1 4WW.</b><br/>or email <a href="mailto:ps.billing@thameswater.co.uk">ps.billing@thameswater.co.uk</a></p> | <p>By calling your bank and quoting:<br/>Account number <b>90478703</b><br/>Sort code <b>60-00-01</b> and your invoice number</p> | <p>Made payable to '<b>Thames Water Utilities Ltd</b>'<br/>Write your Thames Water account number on the back.<br/>Send to:<br/><b>Thames Water Utilities Ltd., PO Box 3189, Slough SL1 4WW</b><br/>or by DX to <b>151280 Slough 13</b></p> |

Thames Water Utilities Ltd Registered in England & Wales No. 2366661 Registered Office Clearwater Court, Vastern Rd, Reading, Berks, RG1 8DB.



## Terms and Conditions

### Search Code



#### **IMPORTANT CONSUMER PROTECTION INFORMATION**

This search has been produced by Thames Water Property Searches, Clearwater Court, Vastern Road, Reading RG1 8DB, which is registered with the Property Codes Compliance Board (PCCB) as a subscriber to the Search Code. The PCCB independently monitors how registered search firms maintain compliance with the Code.

#### **The Search Code:**

- provides protection for homebuyers, sellers, estate agents, conveyancers and mortgage lenders who rely on the information included in property search reports undertaken by subscribers on residential and commercial property within the United Kingdom
- sets out minimum standards which firms compiling and selling search reports have to meet
- promotes the best practise and quality standards within the industry for the benefit of consumers and property professionals
- enables consumers and property professionals to have confidence in firms which subscribe to the code, their products and services.

By giving you this information, the search firm is confirming that they keep to the principles of the Code. This provides important protection for you.

#### **The Code's core principles**

Firms which subscribe to the Search Code will:

- display the Search Code logo prominently on their search reports
- act with integrity and carry out work with due skill, care and diligence
- at all times maintain adequate and appropriate insurance to protect consumers
- conduct business in an honest, fair and professional manner
- handle complaints speedily and fairly
- ensure that products and services comply with industry registration rules and standards and relevant laws
- monitor their compliance with the Code

#### **Complaints**

If you have a query or complaint about your search, you should raise it directly with the search firm, and if appropriate ask for any complaint to be considered under their formal internal complaints procedure. If you remain dissatisfied with the firm's final response, after your complaint has been formally considered, or if the firm has exceeded the response timescales, you may refer your complaint for consideration under The Property Ombudsman scheme (TPOs). The Ombudsman can award compensation of up to £5,000 to you if the Ombudsman finds that you have suffered actual loss and/or aggravation, distress or inconvenience as a result of your search provider failing to keep to the code.

**Please note that all queries or complaints regarding your search should be directed to your search provider in the first instance, not to TPOs or to the PCCB.**

#### **TPOs Contact Details**

The Property Ombudsman scheme  
Milford House  
43-55 Milford Street  
Salisbury  
Wiltshire SP1 2BP  
Tel: 01722 333306  
Fax: 01722 332296  
Web site: [www.tpos.co.uk](http://www.tpos.co.uk)  
Email: [admin@tpos.co.uk](mailto:admin@tpos.co.uk)

You can get more information about the PCCB from [www.propertycodes.org.uk](http://www.propertycodes.org.uk)

**PLEASE ASK YOUR SEARCH PROVIDER IF YOU WOULD LIKE A COPY OF THE SEARCH CODE**



10 Glenmore Road, London NW3 4DB

Vertical Movements from Basement Excavation

Drained Total Condition

Job No. Sheet No. Rev.

J20026

Drg. Ref.

Made by Date Checked ML

Titles

Job No.: J20026
Job Title: 10 Glenmore Road, London NW3 4DB
Sub-title: Vertical Movements from Basement Excavation
Calculation Heading: Drained Total Condition
Initials: ML
Checker:
Date Saved:
Date Checked:
Notes:
File Name: J20026 Total Vertical Movements.pdd
File Path: G:\CURRENT\20-\J20026 - 10 Glenmore Road\APPENDIX

History

Table with columns: Date, Time, By, Notes. History entries include 14-Feb-2020, 16-Feb-2020, 17-Feb-2020.

Analysis Options

General

Global Poisson's ratio: 0.20
Maximum allowable ratio between values of E: 1.5
Horizontal rigid boundary level: 25.40 [m OD]
Displacements at load centroids: Yes
GSA piled raft data: No

Elastic

Elastic: Yes
Analysis: Boussinesq
Stiffness for horizontal displacement calculations: Weighted average
Using legacy heave correction factor: No

Consolidation

Consolidation: No

Soil Profiles Short-term

Table with columns: Layer ref., Name, Level at top, Number of intermediate displacement levels, Youngs Modulus, Poissons ratio, Non-linear curve. Lists soil layers 1-8.

Soil Profiles Total

Table with columns: Layer ref., Name, Level at top, Number of intermediate displacement levels, Youngs Modulus, Poissons ratio, Non-linear curve. Lists soil layers 1-8.

Soil Zones

Table with columns: Zone, Name, X min, X max, Y min, Y max, Profile. Shows Soil Zone 1.

Polygonal Load Data

Table with columns: Load ref., Name, Position: Level, Polygon: Coords., Position: Polygon Rectangles, No. of Rectangles, Value: Normal (local z). Lists excavation and elevation loads.

Polygonal Loads' Rectangles

Table with columns: No., Centre: x, y, Angle of local x from global X [Degrees], Width, Depth, y. Lists excavation loads.



10 Glenmore Road, London NW3 4DB  
 Vertical Movements from Basement Excavation  
 Drained Total Condition

|               |           |         |
|---------------|-----------|---------|
| Job No.       | Sheet No. | Rev.    |
| J20026        |           |         |
| Drg. Ref.     |           |         |
| Made by<br>ML | Date      | Checked |

| No.                               | Centre x | Centre y | Angle of local x from global X | Width x | Depth y |
|-----------------------------------|----------|----------|--------------------------------|---------|---------|
| (Edge 2 optimal)                  |          |          |                                |         |         |
| 1                                 | 16.83000 | 14.60000 | 0.0                            | 2.0000  | 3.8000  |
| 2                                 | 18.83000 | 13.25000 | 0.0                            | 2.0000  | 6.5000  |
| <b>Load 3 : No. 8 party wall</b>  |          |          |                                |         |         |
| (Edge 2 optimal)                  |          |          |                                |         |         |
| 1                                 | 14.91500 | 10.70000 | 90.000                         | 1.4000  | 9.8300  |
| <b>Load 4 : No. 12 party wall</b> |          |          |                                |         |         |
| (Edge 2 optimal)                  |          |          |                                |         |         |
| 1                                 | 15.38000 | 15.80000 | 90.000                         | 1.4000  | 8.9000  |
| <b>Load 5 : Rear elevation</b>    |          |          |                                |         |         |
| (Edge 2 optimal)                  |          |          |                                |         |         |
| 1                                 | 19.43000 | 13.25000 | 90.000                         | 3.7000  | 0.80000 |
| <b>Load 6 : Front elevation</b>   |          |          |                                |         |         |
| (Edge 2 optimal)                  |          |          |                                |         |         |
| 1                                 | 10.70000 | 13.25000 | 90.000                         | 3.7000  | 1.4000  |

**Displacement Lines**

| Name | X1 [m]   | Y1 [m]   | Z1 [m]   | X2 [m]   | Y2 [m]   | Z2 [m]   | Intervals [No.] | Calculate | Detailed Results |
|------|----------|----------|----------|----------|----------|----------|-----------------|-----------|------------------|
| 8A   | 10.00000 | 10.00000 | 63.71000 | 10.00000 | 4.70000  | 63.71000 | 5               | Yes       | Yes              |
| 8B   | 10.00000 | 4.70000  | 63.71000 | 10.93000 | 4.70000  | 63.71000 | 2               | Yes       | Yes              |
| 8C   | 10.93000 | 4.70000  | 63.71000 | 10.93000 | 3.50000  | 63.71000 | 2               | Yes       | Yes              |
| 8D   | 10.93000 | 3.50000  | 63.71000 | 19.83000 | 3.50000  | 63.71000 | 9               | Yes       | Yes              |
| 8E   | 19.83000 | 3.50000  | 63.71000 | 19.83000 | 10.00000 | 63.71000 | 6               | Yes       | Yes              |
| 12A  | 10.93000 | 16.50000 | 63.09000 | 10.93000 | 17.70000 | 63.09000 | 2               | Yes       | Yes              |
| 12B  | 10.93000 | 17.70000 | 63.09000 | 10.00000 | 17.70000 | 63.09000 | 2               | Yes       | Yes              |
| 12C  | 10.00000 | 17.70000 | 63.09000 | 10.00000 | 23.00000 | 63.09000 | 5               | Yes       | Yes              |
| 12D  | 10.00000 | 23.00000 | 63.09000 | 19.83000 | 23.00000 | 63.09000 | 9               | Yes       | Yes              |
| 12E  | 19.83000 | 23.00000 | 63.09000 | 19.83000 | 16.50000 | 63.09000 | 9               | Yes       | Yes              |


**Displacement Grids**

| Name                | Extrusion: Direction | X1 [m]  | Y1 [m]  | Z1 [m]   | X2 [m] | Y2 [m]   | Z2 [m]   | Intervals Along Line [No.] | Extrusion: Distance [m] | Extrusion: Intervals Along [No.] | Calculate | Detailed Results |
|---------------------|----------------------|---------|---------|----------|--------|----------|----------|----------------------------|-------------------------|----------------------------------|-----------|------------------|
| Displacement Grid 1 | Global X             | 5.00000 | 0.00000 | 62.70000 | -      | 28.00000 | 62.70000 | 10                         | 20.00000                | 10                               | Yes       | Yes              |

10 Glenmore Road, London NW3 4DB  
Vertical Movements from Basement Excavation  
Undrained Short-term Condition


|               |           |         |
|---------------|-----------|---------|
| Job No.       | Sheet No. | Rev.    |
| <b>J20026</b> |           |         |
| Drg. Ref.     |           |         |
| Made by<br>ML | Date      | Checked |

Settlement Contours : Grid 1 at 62.7000m



|               |           |         |
|---------------|-----------|---------|
| Job No.       | Sheet No. | Rev.    |
| <b>J20026</b> |           |         |
| Drg. Ref.     |           |         |
| Made by<br>ML | Date      | Checked |

Settlement Contours : Grid 1 at 62.7000m





**10 Glenmore Road, London NW3 4DB**  
**Vertical and Horizontal Movements from Underpinning**  
**Combined P-Disp and X-Disp Models**

|               |           |         |
|---------------|-----------|---------|
| Job No.       | Sheet No. | Rev.    |
| <b>J20026</b> |           |         |
| Drg. Ref.     |           |         |
| Made by<br>ML | Date      | Checked |

**Titles**

Job No.: J20026  
 Job Title: 10 Glenmore Road, London NW3 4DB  
 Sub-title: Vertical and Horizontal Movements from Underpinning  
 Calculation Heading: Combined P-Disp and X-Disp Models  
 Initials: ML  
 Checker:  
 Date Saved:  
 Date Checked:  
 Notes:  
 File Name: J20026 Building Damage - incl installation.xdd  
 File Path: C:\Users\Matt Legg\Desktop

**History**

| Date        | Time  | By        | Notes |
|-------------|-------|-----------|-------|
| 14-Feb-2020 | 14:51 | Matt Legg | New   |
| 14-Feb-2020 | 15:16 | Matt Legg |       |
| 16-Feb-2020 | 21:11 | Matt Legg |       |
| 23-Mar-2020 | 17:16 | Matt Legg |       |

**Displacement Lines**

| Ref. | Name | x1       | y1       | z1       | x2       | y2       | z2       | Intervals | Calculate | Surface type for tunnels |
|------|------|----------|----------|----------|----------|----------|----------|-----------|-----------|--------------------------|
|      |      | [m]      | [m]      | [m]      | [m]      | [m]      | [m]      | [No.]     |           |                          |
| 1    | 8A   | 10.00000 | 10.00000 | 63.71000 | 10.00000 | 4.70000  | 63.71000 | 5         | Surface   | Yes                      |
| 2    | 8B   | 10.00000 | 4.70000  | 63.71000 | 10.93000 | 4.70000  | 63.71000 | 2         | Surface   | Yes                      |
| 3    | 8C   | 10.93000 | 4.70000  | 63.71000 | 10.93000 | 3.50000  | 63.71000 | 2         | Surface   | Yes                      |
| 4    | 8D   | 10.93000 | 3.50000  | 63.71000 | 19.83000 | 3.50000  | 63.71000 | 9         | Surface   | Yes                      |
| 5    | 8E   | 19.83000 | 3.50000  | 63.71000 | 19.83000 | 10.00000 | 63.71000 | 6         | Surface   | Yes                      |
| 6    | 12A  | 10.93000 | 16.50000 | 63.09000 | 10.93000 | 17.70000 | 63.09000 | 2         | Surface   | Yes                      |
| 7    | 12B  | 10.93000 | 17.70000 | 63.09000 | 10.00000 | 17.70000 | 63.09000 | 2         | Surface   | Yes                      |
| 8    | 12C  | 10.00000 | 17.70000 | 63.09000 | 10.00000 | 23.00000 | 63.09000 | 5         | Surface   | Yes                      |
| 9    | 12D  | 10.00000 | 23.00000 | 63.09000 | 19.83000 | 23.00000 | 63.09000 | 9         | Surface   | Yes                      |
| 10   | 12E  | 19.83000 | 23.00000 | 63.09000 | 19.83000 | 16.50000 | 63.09000 | 9         | Surface   | Yes                      |
| 11   | 8A   | 10.00000 | 10.00000 | 63.71000 | 10.00000 | 4.70000  | 63.71000 | 5         | Surface   | Yes                      |
| 12   | 8B   | 10.00000 | 4.70000  | 63.71000 | 10.93000 | 4.70000  | 63.71000 | 2         | Surface   | Yes                      |
| 13   | 8C   | 10.93000 | 4.70000  | 63.71000 | 10.93000 | 3.50000  | 63.71000 | 2         | Surface   | Yes                      |
| 14   | 8D   | 10.93000 | 3.50000  | 63.71000 | 19.83000 | 3.50000  | 63.71000 | 9         | Surface   | Yes                      |
| 15   | 8E   | 19.83000 | 3.50000  | 63.71000 | 19.83000 | 10.00000 | 63.71000 | 6         | Surface   | Yes                      |
| 16   | 12A  | 10.93000 | 16.50000 | 63.09000 | 10.93000 | 17.70000 | 63.09000 | 2         | Surface   | Yes                      |
| 17   | 12B  | 10.93000 | 17.70000 | 63.09000 | 10.00000 | 17.70000 | 63.09000 | 2         | Surface   | Yes                      |
| 18   | 12C  | 10.00000 | 17.70000 | 63.09000 | 10.00000 | 23.00000 | 63.09000 | 5         | Surface   | Yes                      |
| 19   | 12D  | 10.00000 | 23.00000 | 63.09000 | 19.83000 | 23.00000 | 63.09000 | 9         | Surface   | Yes                      |
| 20   | 12E  | 19.83000 | 23.00000 | 63.09000 | 19.83000 | 16.50000 | 63.09000 | 9         | Surface   | Yes                      |

**Displacement Grids**

| Ref. | Name                | Extrusion Direction | Base line start: X [m] | Base line start: Y [m] | Base line start: Z (level) [m] | Base line end: X [m] | Base line end: Y [m] | Base line end: Z (level) [m] | Intervals [No.] | Extrusion Distance [m] | Extrusion Intervals [No.] | Surface type for tunnels | Calculate |
|------|---------------------|---------------------|------------------------|------------------------|--------------------------------|----------------------|----------------------|------------------------------|-----------------|------------------------|---------------------------|--------------------------|-----------|
| 1    | Displacement Grid 1 | Global X            | 5.00000                | 0.00000                | 62.70000                       | -                    | 28.00000             | 62.70000                     | 20              | 20.00000               | 20                        | Surface                  | Yes       |
| 2    | Displacement Grid 2 | Global X            | 5.00000                | 0.00000                | 63.71000                       | -                    | 28.00000             | 63.71000                     | 20              | 20.00000               | 20                        | Surface                  | Yes       |
| 3    | Displacement Grid 1 | Global X            | 5.00000                | 0.00000                | 62.70000                       | -                    | 28.00000             | 62.70000                     | 10              | 20.00000               | 10                        | Surface                  | Yes       |

**Imported Displacements**

The following data points and displacements were found in the import file .

| Ref. | Coordinates: x [m] | Coordinates: y [m] | Coordinates: z [m] | Displacements: x [mm] | Displacements: y [mm] | Displacements: z [mm] |
|------|--------------------|--------------------|--------------------|-----------------------|-----------------------|-----------------------|
| 1    | 10.0000            | 10.0000            | 63.710             | 0.0                   | 0.0                   | 0.88754 1,2,6         |
| 2    | 10.0000            | 8.9400             | 63.710             | 0.0                   | 0.0                   | 0.36127 1,2,6         |
| 3    | 10.0000            | 7.8800             | 63.710             | 0.0                   | 0.0                   | 0.20564 1,2,6         |
| 4    | 10.0000            | 6.8200             | 63.710             | 0.0                   | 0.0                   | 0.13156 1,2,6         |
| 5    | 10.0000            | 5.7600             | 63.710             | 0.0                   | 0.0                   | 0.089331 1,2,6        |
| 6    | 10.0000            | 4.7000             | 63.710             | 0.0                   | 0.0                   | 0.063611 1,2,6        |
| 7    | 10.0000            | 4.7000             | 63.710             | 0.0                   | 0.0                   | 0.063611 1,2,6        |
| 8    | 10.465             | 4.7000             | 63.710             | 0.0                   | 0.0                   | 0.063681 1,2,6        |
| 9    | 10.930             | 4.7000             | 63.710             | 0.0                   | 0.0                   | 0.063124 1,2,6        |
| 10   | 10.930             | 4.7000             | 63.710             | 0.0                   | 0.0                   | 0.063124 1,2,6        |
| 11   | 10.930             | 4.1000             | 63.710             | 0.0                   | 0.0                   | 0.052722 1,2,6        |
| 12   | 10.930             | 3.5000             | 63.710             | 0.0                   | 0.0                   | 0.044531 1,2,6        |
| 13   | 10.930             | 3.5000             | 63.710             | 0.0                   | 0.0                   | 0.044531 1,2,6        |
| 14   | 11.919             | 3.5000             | 63.710             | 0.0                   | 0.0                   | 0.042273 1,2,6        |
| 15   | 12.908             | 3.5000             | 63.710             | 0.0                   | 0.0                   | 0.038664 1,2,6        |
| 16   | 13.897             | 3.5000             | 63.710             | 0.0                   | 0.0                   | 0.034117 1,2,6        |
| 17   | 14.886             | 3.5000             | 63.710             | 0.0                   | 0.0                   | 0.029137 1,2,6        |
| 18   | 15.874             | 3.5000             | 63.710             | 0.0                   | 0.0                   | 0.024200 1,2,6        |
| 19   | 16.863             | 3.5000             | 63.710             | 0.0                   | 0.0                   | 0.019660 1,2,6        |
| 20   | 17.852             | 3.5000             | 63.710             | 0.0                   | 0.0                   | 0.015719 1,2,6        |
| 21   | 18.841             | 3.5000             | 63.710             | 0.0                   | 0.0                   | 0.012438 1,2,6        |
| 22   | 19.830             | 3.5000             | 63.710             | 0.0                   | 0.0                   | 0.009781 1,2,6        |
| 23   | 19.830             | 3.5000             | 63.710             | 0.0                   | 0.0                   | 0.009781 1,2,6        |
| 24   | 19.830             | 4.5833             | 63.710             | 0.0                   | 0.0                   | 0.011271 1,2,6        |
| 25   | 19.830             | 5.6667             | 63.710             | 0.0                   | 0.0                   | 0.013561 1,2,6        |
| 26   | 19.830             | 6.7500             | 63.710             | 0.0                   | 0.0                   | 0.017885 1,2,6        |
| 27   | 19.830             | 7.8333             | 63.710             | 0.0                   | 0.0                   | 0.023931 1,2,6        |
| 28   | 19.830             | 8.9167             | 63.710             | 0.0                   | 0.0                   | 0.032055 1,2,6        |
| 29   | 19.830             | 10.0000            | 63.710             | 0.0                   | 0.0                   | 0.042181 1,2,6        |
| 30   | 10.930             | 16.5000            | 63.090             | 0.0                   | 0.0                   | 0.75837 1,2,6         |
| 31   | 10.930             | 17.1000            | 63.090             | 0.0                   | 0.0                   | 0.38739 1,2,6         |
| 32   | 10.930             | 17.7000            | 63.090             | 0.0                   | 0.0                   | 0.25360 1,2,6         |
| 33   | 10.930             | 17.7000            | 63.090             | 0.0                   | 0.0                   | 0.25360 1,2,6         |
| 34   | 10.465             | 17.7000            | 63.090             | 0.0                   | 0.0                   | 0.23834 1,2,6         |
| 35   | 10.0000            | 17.7000            | 63.090             | 0.0                   | 0.0                   | 0.21978 1,2,6         |
| 36   | 10.0000            | 17.7000            | 63.090             | 0.0                   | 0.0                   | 0.21978 1,2,6         |
| 37   | 10.0000            | 18.7600            | 63.090             | 0.0                   | 0.0                   | 0.13283 1,2,6         |
| 38   | 10.0000            | 19.8200            | 63.090             | 0.0                   | 0.0                   | 0.085092 1,2,6        |
| 39   | 10.0000            | 20.8800            | 63.090             | 0.0                   | 0.0                   | 0.057263 1,2,6        |
| 40   | 10.0000            | 21.9400            | 63.090             | 0.0                   | 0.0                   | 0.040159 1,2,6        |
| 41   | 10.0000            | 23.0000            | 63.090             | 0.0                   | 0.0                   | 0.029161 1,2,6        |
| 42   | 10.0000            | 23.0000            | 63.090             | 0.0                   | 0.0                   | 0.029161 1,2,6        |
| 43   | 11.092             | 23.0000            | 63.090             | 0.0                   | 0.0                   | 0.026741 1,2,6        |
| 44   | 12.184             | 23.0000            | 63.090             | 0.0                   | 0.0                   | 0.022765 1,2,6        |
| 45   | 13.277             | 23.0000            | 63.090             | 0.0                   | 0.0                   | 0.017561 1,2,6        |
| 46   | 14.369             | 23.0000            | 63.090             | 0.0                   | 0.0                   | 0.011756 1,2,6        |
| 47   | 15.461             | 23.0000            | 63.090             | 0.0                   | 0.0                   | 0.0061242 1,2,6       |
| 48   | 16.553             | 23.0000            | 63.090             | 0.0                   | 0.0                   | 0.0013634 1,2,6       |
| 49   | 17.646             | 23.0000            | 63.090             | 0.0                   | 0.0                   | -0.0020985 1,2,6      |
| 50   | 18.738             | 23.0000            | 63.090             | 0.0                   | 0.0                   | -0.0041906 1,2,6      |
| 51   | 19.830             | 23.0000            | 63.090             | 0.0                   | 0.0                   | -0.0051371 1,2,6      |
| 52   | 19.830             | 23.0000            | 63.090             | 0.0                   | 0.0                   | -0.0051371 1,2,6      |
| 53   | 19.830             | 22.278             | 63.090             | 0.0                   | 0.0                   | -0.0068742 1,2,6      |
| 54   | 19.830             | 21.556             | 63.090             | 0.0                   | 0.0                   | -0.0090193 1,2,6      |
| 55   | 19.830             | 20.833             | 63.090             | 0.0                   | 0.0                   | -0.011575 1,2,6       |
| 56   | 19.830             | 20.111             | 63.090             | 0.0                   | 0.0                   | -0.014404 1,2,6       |
| 57   | 19.830             | 19.389             | 63.090             | 0.0                   | 0.0                   | -0.017996 1,2,6       |
| 58   | 19.830             | 18.667             | 63.090             | 0.0                   | 0.0                   | -0.021785 1,2,6       |
| 59   | 19.830             | 17.944             | 63.090             | 0.0                   | 0.0                   | -0.026714 1,2,6       |





10 Glenmore Road, London NW3 4DB

Vertical and Horizontal Movements from Underpinning  
Combined P-Disp and X-Disp Models

|               |           |         |
|---------------|-----------|---------|
| Job No.       | Sheet No. | Rev.    |
| J20026        |           |         |
| Drg. Ref.     |           |         |
| Made by<br>ML | Date      | Checked |

| Corner | x      | y      | Base Level | Arc Enabled | Stiffened | Prev. Side | Prev. Side | Prev. Side | Next Side | Next Side | Next Side |
|--------|--------|--------|------------|-------------|-----------|------------|------------|------------|-----------|-----------|-----------|
|        | [m]    | [m]    | [m]        |             |           | d          | p1         | p2*        | d         | p1        | p2*       |
|        |        |        |            |             |           | [m]        | [%]        | [%]        | [m]       | [%]       | [%]       |
| 1      | 10.000 | 10.000 | 62.700     | Yes         | Yes       | 0.0        | 67.000     | 25.000     | 0.0       | 67.000    | 25.000    |
| 2      | 10.000 | 15.300 | 62.700     | Yes         | Yes       | 0.0        | 67.000     | 25.000     | 0.0       | 67.000    | 25.000    |
| 3      | 10.930 | 15.300 | 62.700     | Yes         | No        | -          | -          | -          | -         | -         | -         |
| 4      | 10.930 | 16.500 | 63.320     | Yes         | Yes       | 0.0        | 67.000     | 25.000     | 0.0       | 67.000    | 25.000    |
| 5      | 19.830 | 16.500 | 63.320     | Yes         | Yes       | 0.0        | 67.000     | 25.000     | 0.0       | 67.000    | 25.000    |
| 6      | 19.830 | 10.000 | 62.700     | Yes         | Yes       | 0.0        | 67.000     | 25.000     | 0.0       | 67.000    | 25.000    |
| 7      | 10.000 | 10.000 | 62.700     | Yes         | Yes       | 0.0        | 67.000     | 25.000     | 0.0       | 67.000    | 25.000    |

| Side | x1     | y1     | x2     | y2     | G.M. Curve: Vertical        | G.M. Curve: Horizontal                  |
|------|--------|--------|--------|--------|-----------------------------|---|
|      | [m]    | [m]    | [m]    | [m]    |                             |   |
| 1    | 10.000 | 10.000 | 10.000 | 10.000 | No vertical ground movement | Underpinning                            |
| 2    | 10.000 | 15.300 | 10.930 | 15.300 | No vertical ground movement | Half underpinning for re-entrant corner |
| 3    | 10.930 | 15.300 | 10.930 | 16.500 | No vertical ground movement | Half underpinning for re-entrant corner |
| 4    | 10.930 | 16.500 | 19.830 | 16.500 | No vertical ground movement | Underpinning                            |
| 5    | 19.830 | 16.500 | 19.830 | 10.000 | No vertical ground movement | Underpinning                            |
| 6    | 19.830 | 10.000 | 10.000 | 10.000 | No vertical ground movement | Underpinning                            |
| 7    | 10.000 | 10.000 | 10.000 | 10.000 | No vertical ground movement | No horizontal ground movement           |

Ref. 2  
 Excavation Name: Installation Phase  
 Surface level [m]: 63.710  
 Contribution: Positive

| Corner | x      | y      | Base Level | Arc Enabled | Stiffened | Prev. Side | Prev. Side | Prev. Side | Next Side | Next Side | Next Side |
|--------|--------|--------|------------|-------------|-----------|------------|------------|------------|-----------|-----------|-----------|
|        | [m]    | [m]    | [m]        |             |           | d          | p1         | p2*        | d         | p1        | p2*       |
|        |        |        |            |             |           | [m]        | [%]        | [%]        | [m]       | [%]       | [%]       |
| 1      | 10.000 | 10.000 | 62.700     | Yes         | Yes       | 0.0        | 67.000     | 25.000     | 0.0       | 67.000    | 25.000    |
| 2      | 10.000 | 15.300 | 62.700     | Yes         | Yes       | 0.0        | 67.000     | 25.000     | 0.0       | 67.000    | 25.000    |
| 3      | 10.930 | 15.300 | 62.700     | Yes         | No        | -          | -          | -          | -         | -         | -         |
| 4      | 10.930 | 16.500 | 63.320     | Yes         | Yes       | 0.0        | 67.000     | 25.000     | 0.0       | 67.000    | 25.000    |
| 5      | 19.830 | 16.500 | 63.320     | Yes         | Yes       | 0.0        | 67.000     | 25.000     | 0.0       | 67.000    | 25.000    |
| 6      | 19.830 | 10.000 | 62.700     | Yes         | Yes       | 0.0        | 67.000     | 25.000     | 0.0       | 67.000    | 25.000    |
| 7      | 10.000 | 10.000 | 62.700     | Yes         | Yes       | 0.0        | 67.000     | 25.000     | 0.0       | 67.000    | 25.000    |

| Side | x1     | y1     | x2     | y2     | G.M. Curve: Vertical  | G.M. Curve: Horizontal  |
|------|--------|--------|--------|--------|---|---|
|      | [m]    | [m]    | [m]    | [m]    |   |   |
| 1    | 10.000 | 10.000 | 10.000 | 15.300 | Inst. of planar diaphragm wall in stiff clay (CIRIA C760 Fig. 6.9(b))   | Inst. of planar diaphragm wall in stiff clay (CIRIA C760 Fig. 6.9(a))   |
| 2    | 10.000 | 15.300 | 10.930 | 15.300 | Half Inst. of planar diaphragm wall in stiff clay for re-entrant corner | Half Inst. of planar diaphragm wall in stiff clay for re-entrant corner |
| 3    | 10.930 | 15.300 | 10.930 | 16.500 | Half Inst. of planar diaphragm wall in stiff clay for re-entrant corner | Half Inst. of planar diaphragm wall in stiff clay for re-entrant corner |
| 4    | 10.930 | 16.500 | 19.830 | 16.500 | Inst. of planar diaphragm wall in stiff clay (CIRIA C760 Fig. 6.9(b))   | Inst. of planar diaphragm wall in stiff clay (CIRIA C760 Fig. 6.9(a))   |
| 5    | 19.830 | 16.500 | 19.830 | 10.000 | Inst. of planar diaphragm wall in stiff clay (CIRIA C760 Fig. 6.9(b))   | Inst. of planar diaphragm wall in stiff clay (CIRIA C760 Fig. 6.9(a))   |
| 6    | 19.830 | 10.000 | 10.000 | 10.000 | Inst. of planar diaphragm wall in stiff clay (CIRIA C760 Fig. 6.9(b))   | Inst. of planar diaphragm wall in stiff clay (CIRIA C760 Fig. 6.9(a))   |
| 7    | 10.000 | 10.000 | 10.000 | 10.000 | No vertical ground movement   | No horizontal ground movement   |

Circular Excavations

Vertical Ground Movement Curves

Curve Name: No vertical ground movement  
 Coordinates: [Distance from wall / wall depth or max. excavation depth (x), Depth / wall depth or max. excavation depth (y), Settlement / wall depth or max. excavation depth (z) (%) ]  
 [0.000,0.000,0.025][1.000,0.000,0.000][0.000,1.000,0.000][1.000,1.000,0.000]

Curve Fitting Method: Polynomial  
 x Order: 1  
 y Order: 0  
 Polynomial: z = -1.25E-2x + 1.25E-2  
 Coeff. of Determination: 3.33E-1

Curve Name: Inst. of planar diaphragm wall in stiff clay (CIRIA C760 Fig. 6.9(b))  
 Coordinates: [Distance from wall / wall depth or max. excavation depth (x), Depth / wall depth or max. excavation depth (y), Settlement / wall depth or max. excavation depth (z) (%) ]  
 [0.000,0.000,0.050][0.050,0.000,0.047][0.100,0.000,0.043][0.150,0.000,0.040]  
 [0.200,0.000,0.037][0.250,0.000,0.034][0.300,0.000,0.031][0.350,0.000,0.028]  
 [0.400,0.000,0.025][0.450,0.000,0.022][0.500,0.000,0.020][0.550,0.000,0.018]  
 [0.600,0.000,0.015][0.650,0.000,0.013][0.700,0.000,0.012][0.750,0.000,0.010]  
 [0.800,0.000,0.008][0.850,0.000,0.007][0.900,0.000,0.006][0.950,0.000,0.005]  
 [1.000,0.000,0.004][1.050,0.000,0.003][1.100,0.000,0.003][1.150,0.000,0.002]  
 [1.200,0.000,0.002][1.250,0.000,0.001][1.300,0.000,0.001][1.350,0.000,0.001]  
 [1.400,0.000,0.001][1.450,0.000,0.000][1.500,0.000,0.000]

Curve Fitting Method: Polynomial  
 x Order: 4  
 y Order: 0  
 Polynomial: z = -1.2355E-2x<sup>4</sup> + 3.4814E-2x<sup>3</sup> - 2.8885E-3x<sup>2</sup> - 6.5618E-2x + 4.9987E-2  
 Coeff. of Determination: 1.0000

Curve Name: Half Inst. of planar diaphragm wall in stiff clay for re-entrant corner  
 Coordinates: [Distance from wall / wall depth or max. excavation depth (x), Depth / wall depth or max. excavation depth (y), Settlement / wall depth or max. excavation depth (z) (%) ]  
 [0.000,0.000,0.025][0.050,0.000,0.023][0.100,0.000,0.022][0.150,0.000,0.020]  
 [0.200,0.000,0.019][0.250,0.000,0.017][0.300,0.000,0.015][0.350,0.000,0.014]  
 [0.400,0.000,0.013][0.450,0.000,0.011][0.500,0.000,0.010][0.550,0.000,0.009]  
 [0.600,0.000,0.007][0.650,0.000,0.006][0.700,0.000,0.006][0.750,0.000,0.005]  
 [0.800,0.000,0.004][0.850,0.000,0.004][0.900,0.000,0.003][0.950,0.000,0.003]  
 [1.000,0.000,0.002][1.050,0.000,0.002][1.100,0.000,0.002][1.150,0.000,0.001]  
 [1.200,0.000,0.001][1.250,0.000,0.001][1.300,0.000,0.001][1.350,0.000,0.001]  
 [1.400,0.000,0.001][1.450,0.000,0.000][1.500,0.000,0.000]

Curve Fitting Method: Polynomial  
 x Order: 4  
 y Order: 0  
 Polynomial: z = -7.2134E-3x<sup>4</sup> + 2.0629E-2x<sup>3</sup> - 4.4648E-3x<sup>2</sup> - 3.2016E-2x + 2.5043E-2  
 Coeff. of Determination: 9.9943E-1

Horizontal Ground Movement Curves

Curve Name: No horizontal ground movement  
 Coordinates: [Distance from wall / wall depth or max. excavation depth (x), Depth / wall depth or max. excavation depth (y), Horizontal movement / wall depth or max. excavation depth (z) (%) ]  
 [0.000,0.000,0.000][1.000,0.000,0.000][0.000,1.000,0.000][1.000,1.000,0.000]

Curve Fitting Method: Polynomial  
 x Order: 0  
 y Order: 0  
 Polynomial: z = 0  
 Coeff. of Determination: 0

Curve Name: Inst. of planar diaphragm wall in stiff clay (CIRIA C760 Fig. 6.9(a))  
 Coordinates: [Distance from wall / wall depth or max. excavation depth (x), Depth / wall





**10 Glenmore Road, London NW3 4DB**  
**Vertical and Horizontal Movements from Underpinning**  
**Combined P-Disp and X-Disp Models**

|               |           |         |
|---------------|-----------|---------|
| Job No.       | Sheet No. | Rev.    |
| J20026        |           |         |
| Drg. Ref.     |           |         |
| Made by<br>ML | Date      | Checked |

Side      x1      y1      x2      y2      G.M. Curve: Vertical      G.M. Curve: Horizontal  
           [m]      [m]      [m]      [m]

depth or max. excavation depth (y), Horizontal movement / wall depth or max. excavation depth (z) (%)  
 [0.000,0.000,0.050][1.500,0.000,0.000]

Curve Fitting Method: Polynomial  
 x Order: 1  
 y Order: 0  
 Polynomial: z = -3.33E-2x + 5.00E-2  
 Coeff. of Determination: 1.00

**Curve Name: Underpinning**  
 Coordinates: [Distance from wall / wall depth or max. excavation depth (x), Depth / wall depth or max. excavation depth (y), Horizontal movement / wall depth or max. excavation depth (z) (%)  
 [0.000,0.000,0.150][4.000,0.000,0.000]

Curve Fitting Method: Polynomial  
 x Order: 1  
 y Order: 0  
 Polynomial: z = -3.75E-2x + 1.50E-1  
 Coeff. of Determination: 1.00

**Curve Name: Half underpinning for re-entrant corner**  
 Coordinates: [Distance from wall / wall depth or max. excavation depth (x), Depth / wall depth or max. excavation depth (y), Horizontal movement / wall depth or max. excavation depth (z) (%)  
 [0.000,0.000,0.075][4.000,0.000,0.000]

Curve Fitting Method: Polynomial  
 x Order: 1  
 y Order: 0  
 Polynomial: z = -1.88E-2x + 7.50E-2  
 Coeff. of Determination: 1.00

**Curve Name: Half Inst. of planar diaphragm wall in stiff clay for re-entrant corner**  
 Coordinates: [Distance from wall / wall depth or max. excavation depth (x), Depth / wall depth or max. excavation depth (y), Horizontal movement / wall depth or max. excavation depth (z) (%)  
 [0.000,0.000,0.050][1.500,0.000,0.000]

Curve Fitting Method: Polynomial  
 x Order: 1  
 y Order: 0  
 Polynomial: z = -3.33E-2x + 5.00E-2  
 Coeff. of Determination: 1.00

**Damage Category Strains**

| Ref. | Name                  | 0 (Negligible) to 1 (Very Slight) | 1 (Very Slight) to 2 (Slight) | 2 (Slight) to 3 (Moderate) | 3 (Moderate) to 4 (Severe) |
|------|-----------------------|-----------------------------------|-------------------------------|----------------------------|----------------------------|
| 1    | Burland Strain Limits | 0.0                               | 500.00E-6                     | 750.00E-6                  | 0.0015000                  |

**Specific Buildings - Geometry**


| Ref. | Building Name | Sub-Building Name | Displacement Line | Distance Along Start | Distance Along End | Vertical Offsets from Line for Vertical Movement Calculations [m] | Vertical Displacement Limit Sensitivity [mm] | Damage Category Strains | Poisson's Ratio | E/G    |
|------|---------------|-------------------|-------------------|----------------------|--------------------|---|--|-------------------------|-----------------|--------|
| 1    | Glenmore Road | 8A                | 8A                | 0.00000              | 5.30000            | 0.0   | 0.10000                                      | Burland Strain Limits   | 0.20000         | 2.6000 |
| 2    | Glenmore Road | 8B                | 8B                | 0.00000              | 0.90000            | 0.0   | 0.10000                                      | Burland Strain Limits   | 0.20000         | 2.6000 |
| 3    | Glenmore Road | 8C                | 8C                | 0.00000              | 1.20000            | 0.0   | 0.10000                                      | Burland Strain Limits   | 0.20000         | 2.6000 |
| 4    | Glenmore Road | 8D                | 8D                | 0.00000              | 8.80000            | 0.0   | 0.10000                                      | Burland Strain Limits   | 0.20000         | 2.6000 |
| 5    | Glenmore Road | 8E                | 8E                | 0.00000              | 6.50000            | 0.0   | 0.10000                                      | Burland Strain Limits   | 0.20000         | 2.6000 |
| 6    | Glenmore Road | 12A               | 12A               | 0.00000              | 1.10000            | 0.0   | 0.10000                                      | Burland Strain Limits   | 0.20000         | 2.6000 |
| 7    | Glenmore Road | 12B               | 12B               | 0.00000              | 0.90000            | 0.0   | 0.10000                                      | Burland Strain Limits   | 0.20000         | 2.6000 |
| 8    | Glenmore Road | 12C               | 12C               | 0.00000              | 5.30000            | 0.0   | 0.10000                                      | Burland Strain Limits   | 0.20000         | 2.6000 |
| 9    | Glenmore Road | 12D               | 12D               | 0.00000              | 9.80000            | 0.0   | 0.10000                                      | Burland Strain Limits   | 0.20000         | 2.6000 |
| 10   | Glenmore Road | 12E               | 12E               | 0.00000              | 6.50000            | 0.0   | 0.10000                                      | Burland Strain Limits   | 0.20000         | 2.6000 |

**Specific Buildings - Bending Parameters**


| Ref. | Building Name | Sub-Building Name | Height | Default | Hogging: 2nd Mom. of Area (per unit width) [m³] | Hogging: Dist. of Bending Strain from N.A. [m] | Hogging: Dist. of N.A. from Edge of Beam in Tension [m] | Sagging: 2nd Mom. of Area (per unit width) [m³] | Sagging: Dist. of Bending Strain from N.A. [m] | Sagging: Dist. of N.A. from Edge of Beam in Tension [m] |
|------|---------------|-------------------|--------|---------|---|--|---|---|--|---|
| 1    | Glenmore Road | 8A                | 9.0000 | Yes     | 243.00  | 9.0000   | 9.0000  | 60.750  | 4.5000   | 4.5000  |
| 2    | Glenmore Road | 8B                | 9.0000 | Yes     | 243.00  | 9.0000   | 9.0000  | 60.750  | 4.5000   | 4.5000  |
| 3    | Glenmore Road | 8C                | 9.0000 | Yes     | 243.00  | 9.0000   | 9.0000  | 60.750  | 4.5000   | 4.5000  |
| 4    | Glenmore Road | 8D                | 9.0000 | Yes     | 243.00  | 9.0000   | 9.0000  | 60.750  | 4.5000   | 4.5000  |
| 5    | Glenmore Road | 8E                | 9.0000 | Yes     | 243.00  | 9.0000   | 9.0000  | 60.750  | 4.5000   | 4.5000  |
| 6    | Glenmore Road | 12A               | 9.0000 | Yes     | 243.00  | 9.0000   | 9.0000  | 60.750  | 4.5000   | 4.5000  |
| 7    | Glenmore Road | 12B               | 9.0000 | Yes     | 243.00  | 9.0000   | 9.0000  | 60.750  | 4.5000   | 4.5000  |
| 8    | Glenmore Road | 12C               | 9.0000 | Yes     | 243.00  | 9.0000   | 9.0000  | 60.750  | 4.5000   | 4.5000  |
| 9    | Glenmore Road | 12D               | 9.0000 | Yes     | 243.00  | 9.0000   | 9.0000  | 60.750  | 4.5000   | 4.5000  |
| 10   | Glenmore Road | 12E               | 9.0000 | Yes     | 243.00  | 9.0000   | 9.0000  | 60.750  | 4.5000   | 4.5000  |

|               |           |         |
|---------------|-----------|---------|
| Job No.       | Sheet No. | Rev.    |
| J20026        |           |         |
| Drg. Ref.     |           |         |
| Made by<br>ML | Date      | Checked |

Vertical Settlement Contours: Grid 2 (level 63.710m) (Interval 0.1mm)



Horizontal Displacement Contours: Grid 2 (level 63.710m) Interval 0.5mm





**10 Glenmore Road, London NW3 4DB**

Vertical and Horizontal Movements from Underpinning

Combined P-Disp and X-Disp Models

|               |           |         |
|---------------|-----------|---------|
| Job No.       | Sheet No. | Rev.    |
| <b>J20026</b> |           |         |
| Drg. Ref.     |           |         |
| Made by<br>ML | Date      | Checked |

**Specific Building Damage Results - Detail**

| Stage Ref. | Stage Name | Specific Building Ref. | Specific Building Name | Sub-building Name | Vertical Offset from Line for Vertical Movement Calculations [m] | Segment | Start   | Length [m] | Curvature | Deflection Ratio [%] | Average Horizontal Strain [%] | Max Tensile Strain [%] | Max Gradient of Horizontal Displacement Curve | Max Gradient of Vertical Displacement Curve | Min Radius of Curvature [m] | Damage Category |
|------------|------------|------------------------|------------------------|-------------------|--|---------|---|------------|-----------|----------------------|-------------------------------|------------------------|---|---|-----------------------------|-----------------|
| 0          | Base Model | 1                      | 8 Glenmore Road        | 8A                | 0.0  | 1       | 0.0   | 5.3000     | Hogging   | 0.013023             | 0.012768                      | 0.019973               | -346.99E-6                                    | 875.16E-6                                   | 1228.7                      | 0 (Negligible)  |
|            |            | 2                      | 8 Glenmore Road        | 8B                | 0.0  | 1       | 0.0   | 0.90000    | Hogging   | 0.0067527            | 0.0                           | 0.0067483              | 0.0   | 136.65E-6                                   | 1659.3                      | 0 (Negligible)  |
|            |            | 3                      | 8 Glenmore Road        | 8C                | 0.0  | 1       | 0.0   | 0.0        | None      | 0.0                  | 0.0                           | 35.763E-9              | 0.0   | 122.54E-6                                   | 3276.7                      | 0 (Negligible)  |
|            |            | 4                      | 8 Glenmore Road        | 8D                | 0.0  | 1       | All vertical displacements are less than the limit sensitivity. |            |           |                      |                               |                        |   |   |                             |                 |
|            |            | 5                      | 8 Glenmore Road        | 8E                | 0.0  | 1       | 6.5000  | 0.0        | None      | 0.0                  | 0.0                           | 35.763E-9              | 150.09E-6                                     | -524.43E-6                                  | 1834.9                      | 0 (Negligible)  |
|            |            | 6                      | 12 Glenmore Road       | 12A               | 0.0  | 1       | 0.0   | 1.1000     | Hogging   | 0.020281             | 0.0                           | 0.020262               | 0.0   | 618.31E-6                                   | 672.36                      | 0 (Negligible)  |
|            |            | 7                      | 12 Glenmore Road       | 12B               | 0.0  | 1       | 0.0   | 0.90000    | Hogging   | 0.025171             | 0.0                           | 0.025155               | 0.0   | 578.20E-6                                   | 445.14                      | 0 (Negligible)  |
|            |            | 8                      | 12 Glenmore Road       | 12C               | 0.0  | 1       | 0.0   | 1.0600     | Sagging   | 0.0                  | 0.0                           | 35.763E-9              | 0.0   | 289.37E-6                                   | 3525.0                      | 0 (Negligible)  |
|            |            | 9                      | 12 Glenmore Road       | 12D               | 0.0  | 1       | All vertical displacements are less than the limit sensitivity. |            |           |                      |                               |                        |   |   |                             |                 |
|            |            | 10                     | 12 Glenmore Road       | 12E               | 0.0  | 1       | 6.5000  | 0.0        | None      | 0.0                  | 0.0                           | 35.763E-9              | 0.0   | -185.17E-6                                  | 3963.4                      | 0 (Negligible)  |

Tensile horizontal strains are +ve, compressive horizontal strains are -ve.

Geotechnical & Environmental  
Associates

(GEA) is an engineer-led and client-focused independent specialist providing a complete range of geotechnical and contaminated land investigation, analytical and consultancy services to the property and construction industries.

We have offices at

Widbury Barn  
Widbury Hill  
Ware  
Hertfordshire  
SG12 7QE  
tel 01727 824666  
mail@gea-ltd.co.uk

Church Farm  
Gotham Road  
Kingston on Soar  
Notts  
NG11 0DE  
tel 01509 674888  
midlands@gea-ltd.co.uk

Peter House  
Oxford Street  
Manchester  
M1 5AN  
  
tel 0161 209 3032  
mail @ gea-ltd.co.uk

Enquiries can also be made online at

[www.gea-ltd.co.uk](http://www.gea-ltd.co.uk)

where information can be found  
on all of the services that we offer.

