

1756/702

August 2018

Rev A November 2018

**British Museum – Number 38 Russell Square**

**ALLOWANCES AT TENDER**

In addition to those called up on the drawings, the following allowances should be made at tender:

- Repairing joist ends as per drawing C1756/705/092 over 5 linear metres
- Strengthening floor joists as per detail 02 on drawing C1756/705/093 over 5 m<sup>2</sup>
- Additional 3 linear metres of detail 02 on drawing C1756/705/094
- Additional 3 no. locations of detail 03 on drawing C1756/705/094
- Allow for making good to masonry over 1 m<sup>2</sup>
- Allow for removing decayed embedded timbers and making good to masonry over 0.5 m<sup>2</sup>
- Allow for 1 no. new RC L1 lintels to replace decayed/damage timber lintels
- Allow for making good to approx. 2m<sup>2</sup> of basement slab
- Allow for 1 no. location of drawing C1756/705/97