# 63 ROSSLYN HILL NW8 5UQ STRUCTURAL DESIGN PHILOSOPHY REPORT



Horwitz Associates 135-137 New London Road Chelmsford Essex CM2 0QT 01245 809510

Report No: 7922.1 16 July 2020 CLIENT:

**Cranbrook Basements Ltd** 

#### **Document Details:**

Job No:

7922.1

Issue Date:

20 February 2020

Written By:

**Richard Horwitz** 

BSc(Hons), CEng, MIStructE

Reviewed By:

**Nikos Chasapis** 

MSc(Hons), MScEng, BEng(Hons)

#### **CONTENTS**

1.0	Introduction
2.0	Site and Geology
3.0	The Existing Property
4.0	Proposed Works
4.1	Design Principles
4.2	<b>Ground Movement Assessment</b>
5.0	Design
6.0	Specifications

Appendix A Geotechnical Survey Report

Appendix B Cranbrook Basement Architects drawings (Existing & Proposed)

Appendix C Preliminary Design Calculations

Appendix D Design Principle drawings

Appendix E Specifications

#### 1.0 Introduction

At the request of Mr David Kavanagh of Cranbrook Basements Ltd, Horwitz Associates have been instructed to produce a Structural Design Philosophy Report for the construction of a single storey basement at 63 Rosslyn Hill Hampstead NW8 5UQ.

Horwitz Associates, Consulting Engineers, was formed in 1995 by Richard Horwitz after having spent five years as an Associate Director with Miller Osborne & Partners.

Our expertise and experience cover a full spectrum of civil and structural engineering within the building industry. The practice works on projects of all sizes, working with developers, contractors and other building professionals forming multi-discipline teams to deliver optimum designs and construction solutions.

Horwitz Associates are members of the Association of Consulting Engineers and Richard Horwitz, a Chartered Engineer, is a Member of the Institute of Structural Engineers and a Fellow of the Association of Consulting Engineers.

Horwitz Associates have undertaken structural design services on a number of similar and much larger basement projects for Cranbrook Basements Ltd and a number of other specialist contractors and developers.

#### 2.0 Site and Geology

The site is located to the south boundary of Rosslyn Hill Hampstead. Viewing the geological survey of Gt. Britain 1:50000 scale map indicates the underlying geology to be Claygate Members consisting Clay, Silt and Sand. No superficial deposits were recorded therefore it is likely these members would be encountered at shallow depths below Made Ground.

A Site Investigation report was commissioned by Cranbrook Basements and undertaken by Fastrack Ltd report ref: 20318 January 2020 (Appendix A).

Report No: 7922.1 16 July 2020

A single borehole was sunk to a depth of 8.0m below ground level within the garden to the front of the property. The ground conditions encountered were top soil and Made Ground to a depth of 1.6m below ground level overlying Dark Brown/Grey Silty Clay, changing to Stiffer Grey Clay at a depth of 4.0m which was recorded to the termination level of 8.0m below ground. Shear Vane readings taken at 3.0m below ground were 110KPa, increasing to 120Kpa at 4.0m.

The anticipated formation level of the basement will be approximately 3.0m to 3.5m below the existing ground level to the front of the property, therefore for the purposes of design the lower value will be considered. This equates to an available safe ground bearing pressure of between 200 - 235Kn/m2.

For the purposes of the design for hydrostatic pressure, an allowance for ground water will be made based on basement design guidance with the worst case level being assumed at 0.75 times the retained depth or at 1m below ground level, whichever is the worst condition, in accordance with BS8102 requirements.

This report will not provide comment on the local hydrology and the effect on the local ground water.

#### 3.0 The Existing Property

The property is a semi-detached house over three floors, with access to the front via a flight of stairs to ground floor. There are also external stairs to access the existing lower ground floor level.

Appendix B contains copies of Cranbrook Basements Architects drawings indicating the existing floor layouts and an existing long section.

The existing property appears to be of traditional construction with a timber roof, timber upper floors, and the ground floor is likely to be timber construction over the existing lower ground floor level. The existing arrangement is such that there may be hidden beams within the depth of the ground and first floor structure.

Given the property's appearance and age it is likely that the existing foundations are shallow spread footings; this is to be verified before any of the works commence on site.

#### 4.0 Proposed Works

Appendix B contains Cranbrook Basements architects drawing indicating the proposed floor plans, including the new below ground level and a building long section.

It can be seen from the plans and section that it is intended to provide a new basement/ lower ground floor extension under the property footprint accessed from the existing lower ground floor/basement level. The new basement/lower ground floor will extend to the property boundary on three sides.

Horwitz Associates have been advised that there is a basement on the party wall line with number 61 Rosslyn Hill, this will be taken into account in the design.

#### 4.1 Design Principles

Appendix C contains a preliminary assessment of the building loads to be taken for the existing construction based on assessment of materials and span directions for traditional loadbearing masonry, timber suspended floors and hand pitched tiled roof.

The proposed layouts are such that the new basement level perimeter walls are to be formed using hit and miss sequence form of underpinning existing walls where required.

It is proposed to retain the existing lower ground floor, with the existing structure left in place; all areas of new ground floor slab are to be formed using a permanent formworks system on a steel frame support.

Where steel beams are to be used under the lower ground floor level to support load bearing walls over, the steel beams are to be designed in accordance with the relevant British Standards with characteristic dead and live load deflections limited to span/500, to minimise the risk of cracking to the existing wall.

Horwitz Associates Report No: 7922.1 16 July 2020

Where the proposed basement extends to the property boundary the surcharge loads from the adjacent land is considered as set out below:

Highway/Footpath - A UDL of 10kw/m<sup>2</sup>

- A point load of 40kN applied over 0.3 x 0.3m and acting 0.6m from the boundary is considered.

The special foundations are designed for two load cases, the first a temporary case prior to the installation of dry packing over the new foundation to the underside of the existing and allows for lateral loads only; the second permanent case upon completion of the pin allows for both vertical and lateral loads.

The bases sizes for the special foundations are calculated for the permanent condition with propping loads indicated, if required, for the temporary condition. The propping forces allow for factors of safety against overturning and sliding at 2.0 and 1.5 respectively.

Temporary works, where required, will be designed to suit the design loads and propping forces as found in the structural design calculations; typically propping forces to the underpin/retaining walls will be based on factors of safety of 1.5 for sliding and overturning in the temporary condition.

#### 4.2 Ground Movement Assessments

With regards to the stability of the neighbouring structures, it is noted that the single level basement is likely to have a direct impact on the adjoining/adjacent properties only. Design of the new basement works is such that loading from the adjacent properties is assessed and included within the structural design where required. The design is undertaken to minimise vertical and lateral movement of the building over any adjacent properties. Works carried out in accordance with the design drawings and method statement typically result in movements that in turn result in damage no greater than BRE Category 1. Category 1 Fine Cracks—cracks that can be treated easily using normal decoration. However, there will always be some movement that cannot be avoided or predicated by pre-construction investigations that may result in more extensive damage. Where this does occur, typically it is no more onerous than BRE Category 2—Cracks Easily Filled.

**Horwitz Associates** 

Report No: 7922.1 16 July 2020

#### 5.0 Design

Appendix D contains drawings for the proposed foundation/underpin arrangement, the Basement G.A.

#### 6.0 Specifications

Appendix E contains a structural specification for the works.

**Richard Horwitz** 

BSc(Hons), CEng, MIStruct E

Reviewed:

**Nikos Chasapis** 

MSc(Hons), MSc(Eng), BEng(Hons)

# **APPENDIX A**

**Geotechnical Survey Report** 



# Geotechnical Survey Report

FSI Ref:

20318

Issue Date:

January 2020

Risk Address:

63 Rosslyn Hill Camden

London NW3 5UQ

Engineer:

David Kavanagh

Company:

Cranbrook Basement Design and Construction Ltd

Managing Director: Finance Director:

Martin Rush MSc FGS Louise Ayres BSc (Hons)

Geotechnical Compliance & Logistics Supervisor:

Perry Martin MCIHT

Laboratory Supervisor:

Jade McLellan

Assistant Geologists:

George Baron BSc (Hons) FGS Scott Parker BSc (Hons) FGS



Tyndales Farm, Southend Road, Woodham Mortimer, Maldon, Essex, CM9 6TQ

Telephone: 0844 3358908

Fax: 0844 3358907

Email:enquiries@fastrackgroup.co.uk

Web: www.fastrackgroup.co.uk

Appendix No:

FSI Ref:


1 20318

#### SITE PLAN

Property Address: 63 Rosslyn Hill, Camden, London NW3 5UQ

Survey date: 17/12/2019

Operative: SE1





Drawn by:

NTS GB





Manholes













Tree (Deciduous)



Fastrack Site Investigations Ltd Unit 9, Tyndales Farm Southend Road Maldon CM9 6TQ

Borehole Log

Borehole No. **BH1** 

Project Name: 6

Key: D - Disturbed Sample

Remarks: Borehole closed at 8.00m.

V - Insitu Vane Test

63 Rosslyn Hill

Project No. 20318

Site Date:

17/12/2019

Sheet 1 of 1
Hole Type
BH
Scale

Location:

Camden, London NW3 5UQ

lient: Cranbrook Ba


1:45 Logged By


Client:		Cranbrook Basement Design and Construction Ltd				
Water Strikes Donth (m)		n Situ Testing	Depth	Legend	Stratum Description	
Depth (m) Type		Results		D 0 0 0		
			0.07		Sand FILL	
					Dark Brown Silty Clayey MADE GROUND containing Brick a	ind Gravel
			0.70			
			0.70		Mid Brown Silty Sandy Clayey MADE GROUND containing E Gravel	Brick and
1.00	D	V (kPa) = 64				
		V (kPa) = 70				
			1.60			
				<u>-x-</u>	Dark Brown/Grey Sitty CLAY	
2.00	D			<u>-x-</u>		
		V (kPa) = 94 V (kPa) = 98		<u>-x</u>		
		-		<u>xx-</u>		
				×-x-		
2.00				<u>x_x</u>		
3.00		V (kPa) = 108		××		
		V (kPa) = 110		×X		
				<u>x_~</u>		
				<u>xx-</u>		
4.00	D	\/ (IrDa) = 400		<u>xx</u>		
		V (kPa) = 120 V (kPa) = 122		<u>×x</u>		
				<u>x-</u>		
				<u>-x-</u>		
5.00	D			××		
0.00		V (kPa) = 128		_ <u>×</u>		
		V (KFa) - 132	5.40	_ <u>x</u> x	Grev CLAV	
					Sidy SEXT	
6.00	D	V (kPa) = 140				
		. ,				
7.00	D			===		
		V (kPa) = 140				
0.00						
8.00	ן ט	V (kPa) = 140	8.00		End of Borehole at 8,000m	
			- 1			1
	Samp Depth (m)  1.00  2.00  3.00  4.00  6.00	Sample and I           Depth (m)         Type           1.00         D           2.00         D           3.00         D           5.00         D           6.00         D           7.00         D	Depth (m)   Type   Results	Sample and In Situ Testing         Depth (m)           Depth (m)         Type         Results         Depth (m)           1.00         D         V (kPa) = 64 V (kPa) = 94 V (kPa) = 98         0.70           2.00         D         V (kPa) = 94 V (kPa) = 98         0.60           3.00         D         V (kPa) = 108 V (kPa) = 110         0.00           4.00         D         V (kPa) = 120 V (kPa) = 122 V (kPa) = 132 V (kPa) = 132         0.40           5.00         D         V (kPa) = 140         0.40           7.00         D         V (kPa) = 140         0.00           8.00         D         8.00         0.00	Depth (m)   Type   Results   Depth (m)   Legend	Depth (m)   Type   Results   Co.77   Co.77


MP - Mackintosh Probe Test


## **APPENDIX B**

Cranbrook Basements Architects Drawings (Existing & Proposed)



















# **APPENDIX C**

**Preliminary Design Calculations** 

Civil & Structural Consulting Engineers

Appendix C.

Sheet No. Pathmin/1
Job No. 7922
Engineer

Date Fel 2020

63 EDSSLYN HILL,

He is proposed to construct a new basement beneath the existing ground from at 63 Rosslyn MM.

the following wantys are to be allowed in assessment of the building loans to be myperted on the bathant and new construction

Roof (pitched) vaflers on + u = 1.8 km/m²
Ceilinge where valamied on + u = .7 km/m²
Lofts n + u = 2.5 km/m²

Suspended Tunber Groved

Places

01 + LL = 310 km/m

Suspended Tunber Groved

Places

01 + LL = 310 km/m

- 1.5 km/m

Walls 115m. Or 4.0 km/m².

Soles Glouns Floors AL+U 7.3 KN/nh

Could.

Civil & Structural Consulting Engineers

Sheet No. Parimwaly 12 4

Job No. 7922

Engineer M

Date Fres la lo

Formations.

Proliminary Calculations for the proposed construction of huntarced Concrete Retaining with and Basenest Mals.

WM edapt 8888 \$ 150 KPa.

Ø - 21°.

Design of Walls to be prefered whill Concrete Centre Sprent Neets: Two load cates to be Considered temporary and permuent condution Subject to Contravtor proposals

the following Calculations are for example only and full analysis and design will be prepare at EIRA Stage 4 and 5.

# APRNOIX C

### HORWITZ ASSOCIATES

Civil & Structural Consulting Engineers

Sheet No. WL

Job No. 7922

Engineer 2 H

Date For Tolo

63 ROSEMN HIW.

WALL LOADS SEL WARDING FIRET LIF

18T FLOOR WASH SEE FIGHT REF. GET/B

WA. I'M- ROSE

-1.8×2 =3.6 Soot

WARL ABOVE RND - 6 x 1,3 = 6.5

2NO FLOOL - 310x 2.7 : 51

WAW 157-2NO - 5.0 x 3x.7=10.5

28712/2

WB GASIE. + STANGLAZ BALLE WALL ZNO-ROOF - 14.0 WAR 187 - MAD 5:0 = 3 = 15:0 20 EN/- + STACKS -

Wc ROOF 1.8 + 1.4 = 1.6 2ND 310x1.6 = 4.8 TLACERE COSE 710 21.1 . 14.7 war 5.0x3 = 15.0 37.0 KN/-

Civil & Structural Consulting Engineers

Sheet No. W. 1

Job No. 7911

Engineer MM

Date Fel 64

WAW 100- BOOF 13.5x1/2=6.8

2ND FLOOR 3.0 x 2.2=6.6

ROOF 1-8 x 2.3 = 4.2

WAW 157- RND 5.0 x 3x.7 - 10.5

28.1 km/-

PW 1/2 LOADS + STACK) 3 &d

EOOF PLA 20/5 = 10.0 KHL

GARE 2NO-ROOF -14.0 KM/~

2NO GOOL 3.0 = 15.0.

WAN 117-12 500 x 3 = 15.0.

42KH/~ + STANES

WE - 200 Rito = 7.20

WANY MON for \_ 200 x 5+4 = 4.00

STANT.

WF 2000 FIR WOW 13.5/2 = 6.6 2000 310 = 8.6 = 7.8 Work 310 = 1.5 = 4.5 (5.1 K25/-

Cones

Civil & Structural Consulting Engineers

Sheet No. WU 3

Job No. 7912

Engineer (M

Date Fes 20/0

WG. 'AS WF 19.1 201 ~ WH, ALLOW FOL; -\$1 4 'ROOF' 20 +4 = 510 KUIL WALL 115 43 = 4.5 NOTOWAU 3.0 - 15 = 4.5 KKN/~

WI.

THURE 7.02 lis = 7.0 WAW 510 +45 = 225 CONSERVATIVE 0.9 x L = 1.8 M1.3 KH-

WJ.

TERRANE 7.0 x 2.1 = 14.7 WAN 5.0+3x.7=10.5 25.2 4-1-

PIER A & PIER B Strco-0 Knoc 310 x 7.5x 1.65 - M.4 BEAM Sullar to Low = 20.5 Grave were 1 loof film four ut son a 1410

Goral John Conti

Civil & Structural Consulting Engineers

Sheet No. WL4

Job No. 7522

Engineer CH

Date FES 20 20

MAN LOADS

GRANNO - FILLT FLOOR

SIFE SULET REF

LOTATION DOT

WB. GARLE + Frankit & 2.

Wg 117 - ROOF - 29:00

WS a- IM 7.2x3=21,60

Nottoman 197 from- = 310 55.6 > on 55 Km/~

WC.

WC 157 - Loof = 37.0

WE GRO - 14 7.2,3 = 11.6

FMT from 3.0, 3.5-10.50

69.1KN1-

WA.

WALL OVER 1St- ROOF - 28.1

WAN 421-14 7.2+3+.7=1512

From 14 3.0 + 1.7 5 6-4

Contractory 0.8 + 9.1 × 1.9 + 1.20

Note 3.0

3.0

3.0

51.31

Civil & Structural Consulting Engineers

Sheet No. WL5

Job No. 7 722

Engineer RM

Date FES To To

WE ALLOW FOR WE 187-240 = 15.7 WE GRO-107 - 4.50 FIRMS 310+5 = 15.0 WALL F 18:18 = 15.2 SO.2 KD FM

WF 187 & over only

WG - 197-2m = 1911

GEO - 117 UAU 1.5 x 1= 4.5

FIRST FLOOR 3.0 = 3.5 = 10.5

11. #STAN 341 WW.

WH: 117-240 - 14=

HUT 310, 110 = 310

WHO 9-11 = 4.5

Civil & Structural Consulting Engineers

Sheet No WL

Job No. 7922

Engineer MH

Date FAR Zolo

UI.

W5 WKL - 31.30

won all-14 Allow 7.5 nomina)

98.8 Rm 40 km/-

M2.

ALON 117 = Bx2.2 . 4.6

war 4-17 5,023x18-1210

43.8 law/- my da KNI-

WX ELY

Man our ,- 13.2

101 3x21 = 6.3

24,7 Kul

PHERS. 'C' = O'

PIELC.

157 Fer - 3×2.1×5/2 = 15.75

WALL WA OVER 28.7 x5/2 = 71.74

Ino Wif.

Gay lloke 107.5

Civil & Structural Consulting Engineers

Sheet No. WL7

Job No. 7911

Engineer 1

Date For 2020

PIEN E A F.

PIEN E

PIEN A APONE - 70.0

FIRST Groon 3.0.2.1 x 9.8 - 17.6.

PIEN SUT -- 20.0

108 KN GMY 110 Kn

Civil & Structural Consulting Engineers

Sheet No. WUB Job No. 792

Engineer MM

Date FRS 2010

Stack 1.

2m-200 = 80

15T- 2M 3x1.25x19x17x20= 47.13

Anck 1

105 km 904 110km

Civil & Structural Consulting Engineers

Sheet No. BU/1


Job No. 7922

Engineer 2mg

Date Fis word

BASEMENT CARDINGS TO TOP OF BARFURNT AP PLIED

Layout. W LOADS ARE QL+WI SERVICE LOAD! MOTATION PLAN (RAAMS AT U/S GRO FLOOR)



Proposed Basement Floor Layout

GROUND FLOOR SYAMS /

Civil & Structural Consulting Engineers

Sheet No. BL2

Job No. 7922

Engineer W

Date \$14 No No

BASENITHT CHADINGS

BEAM WADINGS

BLAM MK A. (3.6-)

WOL = WH = 21.50

GU FA 3x1.5=4.5

4WP

2650KN/m (TN=47760.

Boom MK B. (3.75-)

WOL - WE = 50.2

GEO FLOOR - 1510

GHZW+

GSJ KH/m RTN = 33 KH.

beron MK C. (3.125 m)

COL. Wy = 24.3

brofund, = 6.7

2 .50 twas t

33-50 cm L Por = 52.5 m

from MKD, (dom)

(MT : WH 21.5

one from = 3.75

her + . 5.

14.75KN/ Mons = 52 Km

Civil & Structural Consulting Engineers

Sheet No. BL3
Job No.

Engineer MA

Date FEB 1210

branne (4,2)

Un - WH = 21.50

BRO Frank - = 3.75

SELT J - 50

25.75 EN R= 54 EN

Bran MEF.

F 2.1 & = 44 EN

SEAN MKG (2.3A) MKH = 45 FN (5)

(25.75 4

20 4.3 25

517

75 FL BOKN

BAM MK H (3.2)

WOL = WX = 21.3

ban haan .3x1.2 = 3.6

20.31 /9- 45 km

Rome T. (211-) USL-ASCI = 25.75 : Gue 27 h.

CONTON

Civil & Structural Consulting Engineers

Sheet No. BC4

Job No. 7922

Engineer Com

Date # 6 12

Brown J. (3.6)

Ashow 310-24= 7.2

0.9 1.8 = 34

TIEN/ Son Zolas-

1- 36 Ku

B NK E. (3.40)

WOL WJ = \$4 .0

GRA Cum Berliz = 66

1m-87 km

SIIOKYI

BM MK L (3.8)

CHOL = WI 31.3

ala cin 2.2 x3=6.6

35050

38KS- Em. 71KN

Beam MK M (1.6)

PL : MKG = BOKN

WOL: WC 37 = 37KSI\_ PTN: 70Km

BLAMME HISO.

Nonovar in Allow = 10 x 15 = 15 En 4Th.

any.

Civil & Structural Consulting Engineers

Sheet No. BC 5

Job No. 7911

Engineer

Date FEA ING

COLUMN GABI INTO BAVEMING LOW LEVEL.

Column laf. A

column los 6'

MKF 49Km MKB 33 EW

column lofc

MKA - 48 Em

MKG - 48th 7 128 SAY 130 Km

Comm- REFD (WORST CAN)

MKI - NIE


Civil & Structural Consulting Engineers

WB 7 - 93 KM/~

Job No. 79W
Engineer 2H

Date Firs Zolo

# PREUMINARY DISIGN WASS MILIED TO BARMENT EXCL QUIT.



Civil & Structural Consulting Engineers

Sheet No. L 7 Job No. 7922 Engineer & Date # 2 20

LOADS TO TOP OF BAKEUT WAN

WB!

WB. 55 Kulment we4.

ETACK ? . 110 KN. SHI WLB

STACK! 175KH and WLB

WEB 2

PERCEE - 110+110 - 220EN

MKO ISEN 3

30 Km

250 KM ALONG TOP

of more

W8/2/1 PIEN F HOKN MKO 15 KN

Civil & Structural Consulting Engineers

Sheet No. 1306

Job No. 79W

Engineer ·

Date FAS WW

WB 3.

WO. - 51.32 W/-

500 fur - 3,4.2 = 12.60

63.91601-

50m 64KH/-

WS4 WC-69.1 KU1-

ces ful - 3233 = 95

79 kul

WES WI - 40 KNL

WSG

Nomino 7.0KN/mx1.0=7 Gray 10KN/-

WS 7 As WJ 43.8 Kd -+ 420 fre 9.2 53 Kd -

						· · · · · · · · · · · · · · · · · · ·			
Project	63 Rosslyn	Hill - Hamp	ostead			T	he <b>Conc</b>	rete Cei	ntre
Client	Cranbrook B	asements				Made by	Date		Page
Location	Wall A - Perr			mpa		RH			
		esign to BS8110:2		ine Co	<b>ncrete</b> Centre	Checked	Revision		Job No
Origin	ated from 'RCC61 Ba	sement Wall.xls' v	4.0 © 2	2006 TCC				-	7922
IDEALISE	STRUCTURE	and FORCE	DIAGRAM			1216	DESIGN	N STATUS	: VALID
				Line Lo	ad LGK, LQK in	kN/m L x L	Wall Load		
			6	urchania 60	K, SQK in kN/m	. [ ]	WGK, WQK in k	N/m	
			5	ui ui ai ge Je	IN DOK III KIMII	114114	←		
		1		P		(TERNAL	Prop by Groun	d Floor	
				+ •	L^		TW		
	· ·			PS	里	WATER		I	
	Λ	/	PE		Ţ.	B1	BASEMENT	. "	
	/		u l	2					
		3					4		
	***		Gunahan	Line	• He	eel	В		
	Water	Earth	Surchar	ge Loa	d	•		•	
DIMENSIO H :		B =	1800	Tw =	: <u>300</u>				
п - Hw :		BI =	<u>1800</u>	Tb =	·				
He:		<u>.</u>	<u>-</u>						
		_							
	. PROPERTIES		teel class	<u>A</u>	concrete				
fcu :		N/mm² N/mm²	γm = γm =	<u>1.50</u> <u>1.15</u>	steel				
	Cover to tension		'	40	mm				
Max. allowa	able design sur			<u>0.3</u>	mm	(0.2 or 0.3 mm only)			
		Concrete	density =	<u>24.0</u>	kN/m3	J,	Wall G	eometry	
SOIL PRO	PERTIES								
	e of int'l friction			<u>21</u>	degree	(0.1	.l ( (. <b>.£</b> 9)	:	:- "0" - 0\
De	esign cohesion	of retained m of retained n		0 <u>20</u>	kN/m2 kN/m3	(Only gran	ular backilli	considered	, ie "C" = 0)
Subme	erged Density			13.33	kN/m3	(default=2/	3 of q), only	apply whe	n Hw >0
	gle of int'l fricti			21	degree	,	,, -	=	13.33
H	Design cohesio			2	kN/m2	ASSUMPT			
Nlowabla ar	Dens oss ground bea	ity of base ma		<u>20</u> 200	kN/m3 kN/m2	•	tion is zero n active ear	th pressure	= 0.25aH
	oss ground bea 6 (unfactored)	anny pressure	(001)-	200	(31 9/1116e	c) Granula		p. 000010	q''
	Surcha	rge load live		<u>5</u>	kN/m2	h) Design	not intended		ver 3.5 m hig
		e load dead		<u>10</u>	kN/m2	i)Does <b>not</b>	include che	eck for temp	or shrinkage
		ne load liv e load dea	•	<u>0</u>	kN/m kN/m				
		ne load from		<u>0</u> <u>0</u>	mm				
		II load live		<u>13.4</u>	kN/m				
		oad – Dead	-	76.4	kN/m				
	EODOES		Ко -	0.64	default Ka	= (1-SIN Ø	0.64		
LATERALI	FUKUES		Ko = Kac =	<u>0.64</u> 1.60	= 2Ko <sup>0.5</sup>	- (1-311V W	, 0.04		
					_,,,				
	Force		Lever ar		γ <sub>f</sub>		Force (kN)		
	PE =	0.00	LE =	0.000	1.40	1	.00		
	PS(GK) = PS(QK) =	0.00	LS = LS =	0.00 0.00	1.40 1.60	1	.00		
	PL(GK) =	0.00	LL =	0.00	1.40	1	.00		
	PL(QK) =	0.00	LL =	0.00	1.60		.00		
	PW =	61.25	LW =	1.17	1.40		5.75		
1	Total	61 25			1	1 85	.75	ı	

61.25

Total

85.75

## Project 63 Rosslyn Hill - Hampstead Client Cranbrook Basements

Cranbrook Basements Wall A - Permanent

Basement wall design to BS8110:2005 Originated from 'RCC61 Basement Wall.xls' v4.0 mpa
The Concrete Centre

© 2006 TCC

The Concrete Centre				
Made by RH	Date	Page		
Checked	Revision -	Job No 7922		

#### **EXTERNAL STABILITY**

Location

STABILITY CHECK: OK

#### ANALYSIS - Assumptions & Notes

- 1) Wall idealised as a propped cantilever (i.e. pinned at top and fixed at base)
- 2) Wall is braced.
- 3) Maximum slenderness of wall is limited to 15, i.e [ 0.9\*(He-Tb/2)/Tw < 15 ]
- 4) Maximum Ultimate axial load on wall is limited to 0.1fcu times the wall cross-sectional area
- 5) Design Span (Effective wall height) = He (Tb/2)
- 6) -ve moment is hogging (i.e. tension at external face of wall ) +ve moment is sagging (i.e. tension at internal face of wall )
- 7) " Wall MT. " is maximum +ve moment on the wall.
- 8) Estimated lateral deflections are used for checking the  $\textbf{P}\Delta$  effect .

#### **UNFACTORED LOADS AND FORCES**


- 1								
		Force	Lever arm	Base MT.	Wall MT.	Reaction at	Reaction at	Estimated Elastic
1	Lateral Force	(kN)	to base (m)	(kNm)	(kNm)	Base (kN)	Top (kN)	Deflection ∆ (mm)
	PE =	0.00	0.00	0.00	0.00	0.00	0.00	0.0
	PS(GK) =	0.00	0.00	0.00	0.00	0.00	0.00	0.0
	PS(QK) =	0.00	0.00	0.00	0.00	0.00	0.00	0.0
	PL(GK) =	0.00	0.00	0.00	0.00	0.00	0.00	0.0
	PL(QK) =	0.00	0.00	0.00	0.00	0.00	0.00	0.0
	PW =	55.28	1.11	-24.51	10.96	44.22	11.06	0.3
	Total	55.28		-24.51	10.96	44.22	11.06	0.3

#### **GROUND BEARING FAILURE**

LOAD CASE: Wall Load MAX ise "+") Surcharge MAX

Taking moments about centre of base (anticlockwise "+")

Vertical FOR	CES (kN) I	_ever arm (m	Moment (kNm)
Wall load =	89.8	0.75	67.3499991
Wall (sw) =	22.68	0.75	17.01
Base =	15.12	0.00	0.00
Earth =	0.00	0.90	0.00
Water =	0.00	0.90	0.00
Surcharge =	0.00	0.90	0.00
Line load =	0.00	0.90	0.00
Σ V =	127.60		$\sum Mv = 84.36$



MOMENT due to LATERAL FORCES, Mo = -24.51 kNm

RESULTANT MOMENT, M = Mv + Mo = 59.85 kNm

ECCENTRICITY FROM BASE CENTRE, M / V = 0.47 m

MAXIMUM GROSS BEARING PRESSURE = 197.40 kN/m<sup>2</sup>

< 200 OK

SLIDING AT BASE (using overall factor of safety instead of partial safety far F.O.S = 1.50

SUM of LATERAL FORCES, P = 44.22 kN BASE FRICTION,  $F_b = -(V TANØb + B.Cb) = -52.58$  kN

Factor of Safety,  $F_b/P = 1.19 < 1.50$  FAIL .. but

therefore, LATERAL RESISTANCE to be provided by BASEMENT SLAB = 13.75 kN

The Concrete Centre **Project** 63 Rosslyn Hill - Hampstead Made by Date Page Client Cranbrook Basements mpa RH Location Wall A - Permanent The Concrete Centre Checked Job No Revision Basement wall design to BS8110:2005 Originated from 'RCC61 Basement Wall.xls' v4.0 @ 2006 TCC **DESIGN CHECKS:** STRUCTURAL DESIGNS (ultimate) WALL (per metre length) AXIAL LOAD CAPACITY (Limited to 0.1fcu) = 1050.00 kN > 128.4 OK Ultimate Ult. Moment Ult. Shear Ult. Shear Force  $\gamma_{\rm f}$ Force (kN) t base (kNnat base (kN) at top (kN) Lateral Force (kN) 0.00 0.00 PE = 0.00 1.40 0.00 0.00 0.00 0.00 PS(GK) =0.00 1.40 0.00 0.00 0.00 0.00 0.00 PS(QK) =1.60 0.00 0.00 0.00 PL(GK) =0.00 1.40 0.00 0.00 0.00 0.00 0.00 0.00 1.60 0.00 0.00 PL(QK) =15.48 77.39 -34.31 61.91 PW = 55.28 1.40 15.48 77.39 -34.31 61.91 Total 55.28 EXT MOMENT (kNm) INT **Design Bending Moments** 0 5 10 15 20 25 0.00 On INTERNAL face due to lateral forces, M<sub>int</sub> = 20.28 kNm On EXTERNAL face due to lateral forces, Mext = -34.31 kNm < doj 0.67 Eccentricity of Axial Loads = 125 mm LATERAL DEFLECTION "A"= 0.3 mm 1.33  $\widehat{\mathbb{E}}$ Due to eccentricity of axial loads, Mecc = 16.1 kNm WALL ( Due to  $P\Delta$  effect,  $M_n =$ 0.04 kNm 2.00 otal Mmt on INTERNAL face (M<sub>int</sub>+0.5M<sub>ecc</sub>+M<sub>p</sub>) = 28.3 kNm 2.66 Total Mmt on EXTERNAL face  $(M_{ext}+0.5M_{ecc}) =$ -42.3kNm 3.33 **EXTERNAL FACE** INTERNAL FACE  $mm^2$ 390 Min. As = 390 WALL REINFORCEMENT:  $\phi =$ 12 mm 16 OK 200 < 762 3.12.11.2.7(b) 200 < 766 mm centres = > 390 > 390 mm<sup>2</sup> OK 1005 565 As= 254 mm **MOMENT of RESISTANCE:** d =252 z =238 241 mm  $mm^2$ As' = 0 0 **OK**  $M_{res} =$ 104.0 > 42.33 59.3 > 28.35 kNm BASE of WALL TOP of WALL mm<sup>2</sup>/m SHEAR RESISTANCE: As= 1005 10 @200 mm 393 0.40% 0.15% = 100As/bd =N/mm<sup>2</sup> vc = 0.58 0.43 OK > 15.48 kN 108.0  $V_{res} =$ 147.2 > 61.91  $\epsilon_{m} = 0.00020$ CK WIDTH to BS8100/8007 X = 73.51 mm 0.04 OK Temp & shrinkage effects not 102.92 W = < 0.30 mm Acr = mm

7922

OK

BS8110 reference

3.4.4.1

Table 3.25

3,4.4.4

3.4.4.4

Table 3.8

3.5.5.2

BS8007

App. B.2

OK OK OK

REINFORCEMENT SUMMARY for WALL

included

	Туре	ф	centres	As	Min. As	l
		mm	mm	mm <sup>2</sup>	mm <sup>2</sup>	
INTERNAL FACE	Н	12	200	565	390	
EXTERNAL FACE	Н	16	200	1005	390	l
TRANSVERSE	Н	10	200	393	390	

Project	63 Rossly	yn Hill -	Hampst	tead		TI	he Concr	ete Ce	ntre
Client Location	Cranbrook B Wall A - Perr			(mpa		Made by RH	Date		Page
	Basement wall	design to BS	88110:2005	The Con	<b>crete</b> Centre	Checked	Revision		Job No
	Originated from 'R	CC61 Basement	Wall.xls' v4.0	© 2006 TC	0		-		7922
OUTER BA	SE ( per metre <b>γ</b> <sub>f</sub> =	<u>1.50</u>	(ASSUM	•					BS8110 reference
	Ult. Shear =	8.43	kN	(AT d from					
	Ult. MT. =	0.00	kNm	TENSION -	- TOP FA	CE			
	BOTTOM REI	NFORCEM	ENT:	Min. As =	455	mm <sup>2</sup>			Table 3.2
				φ =	<u>12</u>	mm			
				centres =	225	mm	< 762	OK	
				As =	503	mm <sup>2</sup>	> 455	OK	
	MOMENT of F	RESISTANC	E:	d =	304	mm			
				Z =	289	mm			3.4.4.4
				As' =	0	mm <sup>2</sup>		_	
				Mres =	63.12	kNm	> 0.00	OK	
	SHEAR RESIS	STANCE:		100As/bd =	0.20%				
	SHEAR RESI	STANCE.		VC =	0.42	N/mm <sup>2</sup>			Table 3.8
				Vc =	126.35	kN	> 8.43	OK	
				vies –	120.33	KIN	~ 0. <del>4</del> 3	OK	3.5.5.2
	CHECK CRAC	K WIDTH I	N ACCOR	DANCE WITH I	BS8100/80	Temp & shr	inkage effects	not included	t
	X =	60.69	mm		-0.00114				BS8007
	Acr =	115.54	mm	W =	-0.26	mm	< 0.30	OK	App. B.2
					V.—V				
NINED BAS	SE / per metre l	onath \		1	NO CRAC				
NNER BAS	SE ( per metre l Ult. Shear = Ult. MT. =	ength ) -37.56 36.76	kN kNm	(AT d from TENSION -	NO CRAC	KING VALL)			
NNER BAS	Ult. Shear =	-37.56 36.76	kN kNm	(AT d from TENSION -	NO CRAC	KING VALL) I FACE			Table 3.25
NNER BAS	Ult. Shear = Ult. MT. =	-37.56 36.76	kN kNm	(AT d from TENSION - Min. As =	FACE of No. BOTTOM	VALL) I FACE mm²			Table 3.25
NNER BAS	Ult. Shear = Ult. MT. =	-37.56 36.76	kN kNm	(AT d from TENSION - Min. As = φ =	FACE of No. BOTTOM  455 12	KING VALL) I FACE	< 762	OK	Table 3.25
NNER BAS	Ult. Shear = Ult. MT. =	-37.56 36.76	kN kNm	(AT d from TENSION - Min. As =	FACE of No. BOTTOM	VALL) I FACE mm <sup>2</sup> mm	< 762 > 455	OK OK	Table 3.25
NNER BAS	Ult. Shear = Ult. MT. = BOTTOM REII	-37.56 36.76 NFORCEM	kN kNm ENT :	(AT d from TENSION - Min. As = φ = centres = As =	FACE of V BOTTOM 455 12 225 503	VALL) I FACE  mm² mm mm mm²			Table 3.25
NNER BAS	Ult. Shear = Ult. MT. =	-37.56 36.76 NFORCEM	kN kNm ENT :	(AT d from TENSION - Min. As = φ = centres = As = d =	FACE of No BOTTOM  455 12 225 503 304	VALL) I FACE  mm² mm  mm  mm²			Table 3.25
NNER BAS	Ult. Shear = Ult. MT. = BOTTOM REII	-37.56 36.76 NFORCEM	kN kNm ENT :	(AT d from TENSION -  Min. As = φ = centres = As = d = Z =	FACE of No. BOTTOM  455 12 225 503 304 289	VALL) I FACE  mm²  mm  mm  mm²  mm			Table 3.25
NNER BAS	Ult. Shear = Ult. MT. = BOTTOM REII	-37.56 36.76 NFORCEM	kN kNm ENT :	(AT d from TENSION -  Min. As = φ = centres = As =   d = Z = As' =	FACE of No. BOTTOM  455 12 225 503 304 289 0	VALL) I FACE  mm² mm mm mm² mm mm²	> 455	OK	
NNER BAS	Ult. Shear = Ult. MT. = BOTTOM REII	-37.56 36.76 NFORCEM	kN kNm ENT :	(AT d from TENSION -  Min. As = φ = centres = As = d = Z =	FACE of No. BOTTOM  455 12 225 503 304 289	VALL) I FACE  mm²  mm  mm  mm²  mm			
INNER BAS	Ult. Shear = Ult. MT. = BOTTOM REII MOMENT of R	-37.56 36.76 NFORCEMI	kN kNm ENT :	(AT d from TENSION -  Min. As = φ = centres = As =   d = Z = As' =   Mres =	FACE of V BOTTOM 455 12 225 503 304 289 0 63.12	VALL) I FACE  mm² mm mm mm² mm mm²	> 455	OK	
NNER BAS	Ult. Shear = Ult. MT. = BOTTOM REII	-37.56 36.76 NFORCEMI	kN kNm ENT :	(AT d from TENSION -  Min. As = φ = centres = As =   d = Z = As' =	FACE of No BOTTOM  455 12 225 503 304 289 0 63.12 0.17%	VALL) I FACE  mm² mm mm² mm mm² kNm	> 455	OK	3.4.4.4
NNER BAS	Ult. Shear = Ult. MT. = BOTTOM REII MOMENT of R	-37.56 36.76 NFORCEMI	kN kNm ENT :	(AT d from TENSION -  Min. As = φ = centres = As =   d = Z = As' = Mres =   100As/bd =	FACE of V BOTTOM 455 12 225 503 304 289 0 63.12	VALL) I FACE  mm² mm mm mm² mm mm²	> 455	OK	3.4.4.4 Table 3.8
NNER BAS	Ult. Shear = Ult. MT. = BOTTOM REII MOMENT of R	-37.56 36.76 NFORCEMI RESISTANCE:	kN kNm ENT:	(AT d from TENSION -  Min. As = φ = centres = As =	FACE of No BOTTOM  455 12 225 503 304 289 0 63.12 0.17% 0.42 126.35	VALL) I FACE  mm² mm mm² mm mm² kNm	> 455 > 36.76 > 37.56	ок ок ок	3.4.4.4 Table 3.8 3.5.5.2
NNER BAS	Ult. Shear = Ult. MT. = BOTTOM REII MOMENT of R SHEAR RESIS	-37.56 36.76 NFORCEMI RESISTANCE:	kN kNm ENT:	(AT d from TENSION -  Min. As = φ = centres = As =	FACE of V BOTTOM 455 12 225 503 304 289 0 63.12 0.17% 0.42 126.35	VALL) I FACE  mm² mm mm² mm mm² kNm	> 455 > 36.76 > 37.56	ок ок ок	3.4.4.4 Table 3.8 3.5.5.2
NNER BAS	Ult. Shear = Ult. MT. = BOTTOM REII  MOMENT of R  SHEAR RESIS  CHECK CRAC X =	-37.56 36.76 NFORCEMI RESISTANCE: STANCE:	kN kNm ENT : EE:	(AT d from TENSION -  Min. As = φ = centres = As =  d = Z = As' = Mres =  100As/bd = vc = Vres =  DANCE WITH E Em =	FACE of V BOTTON 455 12 225 503 304 289 0 63.12 0.17% 0.42 126.35	VALL) I FACE  mm² mm mm² mm mm² kNm  N/mm² kN  Temp & shri	> 455  > 36.76  > 37.56  inkage effects r	OK  OK  OK	3.4.4.4 Table 3.8 3.5.5.2 BS8007
NNER BAS	Ult. Shear = Ult. MT. = BOTTOM REII MOMENT of R SHEAR RESIS	-37.56 36.76 NFORCEMI RESISTANCE:	kN kNm ENT:	(AT d from TENSION -  Min. As = φ = centres = As =  d = Z = As' = Mres =  100As/bd = vc = Vres =  DANCE WITH E  εm = W =	FACE of V BOTTOM 455 12 225 503 304 289 0 63.12 0.17% 0.42 126.35 388100/800 -0.00012 -0.03	VALL) I FACE  mm² mm mm² mm mm² kNm  N/mm² kNm  Temp & shri	> 455 > 36.76 > 37.56	ок ок ок	3.4.4.4 Table 3.8 3.5.5.2 BS8007
NNER BAS	Ult. Shear = Ult. MT. = BOTTOM REII  MOMENT of R  SHEAR RESIS  CHECK CRAC X =	-37.56 36.76 NFORCEMI RESISTANCE: STANCE:	kN kNm ENT : EE:	(AT d from TENSION -  Min. As = φ = centres = As =  d = Z = As' = Mres =  100As/bd = vc = Vres =  DANCE WITH E  εm = W =	FACE of V BOTTON 455 12 225 503 304 289 0 63.12 0.17% 0.42 126.35	VALL) I FACE  mm² mm mm² mm mm² kNm  N/mm² kNm  Temp & shri	> 455  > 36.76  > 37.56  inkage effects r	OK  OK  OK	3.4.4.4 Table 3.8 3.5.5.2 BS8007
	Ult. Shear = Ult. MT. =  BOTTOM REII  MOMENT of R  SHEAR RESIS  CHECK CRAC  X = Acr =	-37.56 36.76 NFORCEMI RESISTANCE: STANCE: CK WIDTH II 60.69 115.54	kN kNm ENT: EE:	(AT d from TENSION -  Min. As = φ = centres = As =  d = Z = As' = Mres =  100As/bd = vc = Vres =  DANCE WITH E  εm = W =	FACE of V BOTTOM 455 12 225 503 304 289 0 63.12 0.17% 0.42 126.35 388100/800 -0.00012 -0.03	VALL) I FACE  mm² mm mm² mm mm² kNm  N/mm² kNm  Temp & shri	> 455  > 36.76  > 37.56  inkage effects r	OK  OK  OK	3.4.4.4 Table 3.8 3.5.5.2 BS8007
	Ult. Shear = Ult. MT. = BOTTOM REII  MOMENT of R  SHEAR RESIS  CHECK CRAC X =	-37.56 36.76 NFORCEMI RESISTANCE: STANCE: CK WIDTH II 60.69 115.54	kN kNm ENT: EE:	(AT d from TENSION -  Min. As = φ = centres = As =  d = Z = As' = Mres =  100As/bd = vc = Vres =  DANCE WITH E  εm = W =	FACE of V BOTTOM 455 12 225 503 304 289 0 63.12 0.17% 0.42 126.35 388100/800 -0.00012 -0.03	VALL) I FACE  mm² mm mm² mm mm² kNm  N/mm² kNm  Temp & shri	> 455  > 36.76  > 37.56  inkage effects r	OK  OK  OK	3.4.4.4 Table 3.8 3.5.5.2 BS8007
	Ult. Shear = Ult. MT. =  BOTTOM REII  MOMENT of R  SHEAR RESIS  CHECK CRAC  X = Acr =	-37.56 36.76 NFORCEMI RESISTANCE: STANCE: CK WIDTH I 60.69 115.54	kN kNm ENT: EE: N ACCORI mm mm	(AT d from TENSION -  Min. As = φ = centres = As =  d = Z = As' = Mres =  100As/bd = vc = Vres =  DANCE WITH E Em = W =	FACE of V BOTTON 455 12 225 503 304 289 0 63.12 0.17% 0.42 126.35 388100/80 -0.00012 -0.03 NO CRAC	VALL) I FACE  mm² mm mm² mm mm² kNm  N/mm² kNm  Temp & shri mm KING	> 455  > 36.76  > 37.56  inkage effects r	OK  OK  OK	3.4.4.4 Table 3.8 3.5.5.2 BS8007
	Ult. Shear = Ult. MT. =  BOTTOM REII  MOMENT of R  SHEAR RESIS  CHECK CRAC  X = Acr =	-37.56 36.76 NFORCEMI RESISTANCE: STANCE: CK WIDTH I 60.69 115.54	kN kNm ENT: ES:	(AT d from TENSION -  Min. As = φ = centres = As =  d = Z = As' = Mres =  100As/bd = vc = Vres =  DANCE WITH E Em = W =	FACE of V BOTTOM 455 12 225 503 304 289 0 63.12 0.17% 0.42 126.35 3S8100/80 -0.00012 -0.03 NO CRAC	VALL) I FACE  mm² mm mm² mm mm² kNm  N/mm² kN  Temp & shri	> 455  > 36.76  > 37.56  inkage effects r	OK  OK  OK	
	Ult. Shear = Ult. MT. = BOTTOM REII  MOMENT of R  SHEAR RESIS  CHECK CRAC X = Acr =	-37.56 36.76  NFORCEMI  RESISTANCE:  CK WIDTH II 60.69 115.54  MARY for B Type	kN kNm ENT: CE:	(AT d from TENSION -  Min. As =	FACE of V BOTTON 455 12 225 503 304 289 0 63.12 0.17% 0.42 126.35 388100/800 -0.00012 -0.03 NO CRAC	VALL) I FACE  mm² mm mm² mm mm² kNm  N/mm² kNm  Temp & shri mm KING	> 455  > 36.76  > 37.56  inkage effects r	OK  OK  not included	3.4.4.4 Table 3.8 3.5.5.2 BS8007

Project	63 Rosslyn Hill - Hamps	stead			Th	e Conci	ete Cer	ntre
Client Location	Cranbrook Basements Wall A - Permanent		mpa		Made by RH	Date		Page #VALUE
	Basement wall design to BS8110	:2005	The <b>Con</b>	<b>crete</b> Centre	Checked	Revision		Job No
	Originated from 'RCC61 Basement Wall.	xls' v4.0	© 2006 T	cc			-	7922
		No.	Type	Dia	Length	Unit Wt	Weight	
		_		4.00	20.40		47.00	
WALL	VERTICAL - Internal face	6	Н	12	3246	0.888	17.29	
	VERTICAL - External face	6	Н	16	3278	1.578	31.04	
	TRANSVERSE (Ext.+ Int.)	32	Н	10	1000	0.617	19.73	
BASE	TOP (MAIN)	5	Н	12	1896	0.888	8.42	
	BOTTOM (MAIN)	5	Н	12	1896	0.888	8.42	
	TRANSVERSE (T&B)	18	Н	12	1000	0.888	15.98	
	WALL STARTERS (Int.)	6	Н	12	1001	0.888	5.33	
	WALL STARTERS (Ext.)	6	Н	16	1193	1.578	11.30	

Total reinforcement per metre length of wall (kg)


118

SUMMARY

© 2005 TCC

 $IF(ECCY>(B/1000)/6,IF(XX>(B/1000/2-ECCY)^*3,0,(((B/1000/2-ECCY)^*3-XX)/((B/1000/2-ECCY)^*3))^*BP),((VL/(B/1000)^*(1-(6^*ECCY)/(B/1000))))+(B/1000-XX)/(B/1000)^*(BP-(VL/(B/1000)^*(1-(6^*ECCY)/(B/1000)))))$ 

 $IF(ABS(ECCY)>(B/1000)/G, IF((B-XX)>(B/1000/2-ABS(ECCY))^*3,0,(((B/1000/2-ABS(ECCY))^*3-(B-XX))/((B/1000/2-ABS(ECCY))^*3))^*BP),((VL/(B/1000)^*(1-(6^*ABS(ECCY))/(B/1000)))) \\ + (B/1000-(B-XX))/(B/1000)^*(B-(VL/(B/1000)^*(1-(6^*ABS(ECCY))/(B/1000))))) \\ + (B/1000-(B-XX))/(B/1000)^*(B-(VL/(B/1000)^*(1-(6^*ABS(ECCY))/(B/1000))))) \\ + (B/1000-(B-XX))/(B/1000)^*(B-(VL/(B/1000)^*(1-(6^*ABS(ECCY))/(B/1000)))) \\ + (B/1000-(B-XX))/(B/1000)^*(B-(VL/(B/1000)^*(B-(VL/(B/1000))))) \\ + (B/1000-(B-XX))/(B/1000)^*(B-(VL/(B/1000)))) \\ + (B/1000-(B-XX))/(B/1000)^*(B-(VL/(B/1000))) \\ + (B/1000-(B-XX))/(B/1000)^*(B-(VL/(B/1000))) \\ + (B/1000-(B-XX))/(B/1000)) \\ + (B/1000-(B-XX))/(B/1000) \\ + (B/1000-(B-X$ 




		197.4
BPO	0	197.4
BPE	1E-08	197.4
BPI	0.3	151.59
BPZ	1.8	0


0	197.40	0.0000	0.00	0.00	0.036 7.11	0	0.00
1	191.91	0	0.00	0.00	0.036 6.91	0	0.00
2	186.41	0	0.00	0.00	0.036 6.71	0	0.00
3	180.91	Ō	0.00	0.00	0.036 6.51	Ô	0.00
4	175.41	ō	0.00	0.00	0.036 6.31	Ö	0.00
5	169.92	ő	0.00	0.00	0.036 6.12	Ö	0.00
6	164.42	ő	0.00	0.00	0.036 5.92	Ö	0.00
7	158.92	ő	0.00	0.00	0.036 5.72	0	0.00
8	153.43	ő	0.00	0.00	0.036 5.52	0	0.00
9	147.93	0	0.00	0.00	0.036 5.33	0	
		0	0.00				0.00
10	142.43 136.94			0.00	0.036 5.13	0	0.00
11		0	0.00	0.00	0.036 4.93	0	0.00
12	131.44	0	0.00	0.00	0.036 4.73	0	0.00
13	125.94	0	0.00	0.00	0.036 4.53	0	0.00
14	120.44	0	0.00	0.00	0.036 4.34	0	0.00
15	114.95	0	0.00	0.00	0.036 4.14	0	0.00
16	109.45	0	0.00	0.00	0.00	0	0.00
17	103.95	0	0.00	0.00	0 0.00	0	0.00
18	98.46	0	0.00	0.00	0 0.00	0	0.00
19	92.96	0	0.00	0.00	0 0.00	0	0.00
20	87.46	0	0.00	0.00	0 0.00	0	0.00
21	81.97	0	0.00	0.00	0 0.00	0	0.00
22	76.47	0	0.00	0.00	0 0.00	0	0.00
23	70.97	0	0.00	0.00	0 0.00	0	0.00
24	65.47	0	0.00	0.00	0 0.00	0	0.00
25	59.98	0	0.00	0.00	0 0.00	ō	0.00
26	54.48	Ö	0.00	0.00	0 0.00	0	0.00
27	48.98	Ö	0.00	0.00	0 0.00	ŏ	0.00
28	43.49	ō	0.00	0.00	0 0.00	ŏ	0.00
29	37.99	ő	0.00	0.00	0 0.00	ŏ	0.00
30	32.49	ŏ	0.00	0.00	0 0.00	ŏ	0.00
31	26.99	ő	0.00	0.00	0 0.00	0	0.00
32	21.50	ő	0.00	0.00	0 0.00	Ö	0.00
33	16.00	0	0.00	0.00	0 0.00	0	0.00
34	10.50	Ö	0.00	0.00	0 0.00	0	0.00
35	5.01	0	0.00	0.00	0 0.00	o	0.00
36	0.00	Ö	0.00	0.00			0.00
37	0.00	0	0.00	0.00	0 0.00 0 0.00	0	
		0				0	0.00
38	0.00		0.00	0.00	0 0.00	0	0.00
39	0.00	0	0.00	0.00	0 0.00	0	0.00
40	0.00	0	0.00	0.00	0 0.00	0	0.00
41	0.00	0	0.00	0.00	0 0.00	0	0.00
42	0.00	0	0.00	0.00	0 0.00	0	0.00
43	0.00	0	0.00	0.00	0 0.00	0	0.00
44	0.00	0	0.00	0.00	0 0.00	0	0.00
45	0.00	0	0.00	0.00	0 0.00	0	0.00
46	0.00	0	0.00	0.00	0 0.00	0	0.00
47	0.00	0	0.00	0.00	0 0.00	0	0.00
48	0.00	0	0.00	0.00	0 0.00	0	0.00
49	0.00	0	0.00	0.00	0 0.00	0	0.00
50	0.00	0	0.00	0.00	0 0.00	0	0.00
			0.00	0.00	89.96		0.00


22 0.79 76.468 23 0.83 70.971 24 0.86 65.474 25 0.90 59.977 26 0.94 48.983 27 0.97 48.983 29 1.04 37.989 30 1.08 32.492 31 1.12 26.995 32 1.15 21.498 33 1.19 16.001 34 1.22 10.504 35 1.26 5.007 36 1.30 0.000 37 1.33 0.000 38 1.37 0.000 39 1.40 0.000 41 1.44 0.000 41 1.48 0.000 42 1.51 0.000 43 1.55 0.000 44 1.58 0.000 45 1.66 0.000 46 1.66 0.000 47 1.69 0.000 48 1.73 0.000
49 1.76 0.000 50 1.80 0

	MOMENTS	i			
	MTE2=	41.50			
YY= 3.875	MTE1=	-0.36	0.00	82.943	
	MTLG=	0.00		0.00	
	MTLQ=	0.00		0.00	
	MTSG=	-0.97		48.172	
	MTSQ=	-0.49		24.09	
	MTW=	-54.14		96.98	

 $SHEARS\\ SE2=IF(YY)=(L-'ANALYSIS \& STABILITY'IM28), Ka*(q-QS)*(YY-(L-'ANALYSIS \& STABILITY'IM28), Y(2)/2 (L-'ANALYSIS & STABILITY'IM28), Ka*(q-QS)*(YY-(L-'ANALYSIS & STABILITY'IM28), Y(2)/2 (L-'ANALYSIS & STABILITY'IM28), Ka*(q-QS)*(YY-(L-'ANALYSIS & STABILITY'IM28), Y(2)/2 (L-'ANALYSIS & STABILITY'IM28), Ka*(q-QS)*(YY-(L-'ANALYSIS & STABILITY'IM28), Y(2)/2 (L-'ANALYSIS & STABILITY'IM28), Y(2)/2 (L-'ANAL$ 







0.000 1.029 3.077 4.092 5.092 6.091 10.800 10.800 11.673 12.518 1	1.029 1.027 1.027 1.022 1.015 1.005 0.994 0.973 0.963 0.973 0.875 0.782 0.782 0.782 0.785 0.781 0.534 0.485 0.433 0.202 0.139 0.073 0.004 0.139 0.026 0.139 0.027 0.066 0.139 0.020 0.139 0.020 0.139 0.020 0.139 0.020 0.139 0.020 0.139 0.020 0.139 0.020 0.139 0.0066 0.139 0.0066 0.139 0.0066 0.139 0.0066 0.139 0.0066 0.139 0.0066 0.139 0.0066 0.139 0.0066 0.139 0.0066 0.139 0.0066 0.139 0.0066 0.139 0.0066 0.139 0.0066 0.139 0.0066 0.139 0.0066 0.139 0.0066 0.139 0.0066 0.139 0.0066 0.139 0.139 0.139 0.139 0.139 0.139 0.139 0.139 0.139	0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.0	0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.0
11.852 10.549	-1.199 -1.303	0.00	0.00
9.140 7.623	-1.303 -1.409 -1.517	0.00	0.00
5.996 4.255	-1.628 -1.741	0.00	0.00
2.399	-1.856	20.28	2.00

#### Geometry

0	0		
0	350		
1E-05	350		
1E-05	3650		
1800	3650		
1800	3350		
300	3350		
300	3650		
300	350		
1800	350		
1800	0		
0	0	3650	1800

Project	63 Rosslyn F	lill - Hampstead					6	
Location		Vall A - Permanent		CRACK WIDTH CALCULATIONS The Concrete Cent				
	Basement wall design to BS8110:2005 Originated from 'RCC61 Basement Wall.xls' v4.0			Made by RH Job No 7922 © 2006 TCC Date			2	
VALL								
MR=	15.06	MS=	766	Asreq =	409	fs =	135.64 \sprov%=	0.3989
As/bd=	0.004	MSS=	762	Assreg =	270		159.28 \sprov%=	
X=	73.51	MSBB=	762	ASBBreq=	0		4E-15 \sprov%=	
lc=	614620645	MSBT=	762	ASBTreq=	293	fs =	194.14 \sprov%=	0.1653
	0.000536							
	0.000680							
	0.00047647							
	102.923397							
	0.04							
Em=	0.0002							
MR=	15.06	MR= 15	.06					
sBB/bd=	0.0017	AsBT/bd= 0.0	0017					
X=	60.69	X= 60						
lc=	522535043	lc= 52	2535043	i				
STS=	0.0000	STS= 0.0	0009					
	0.0000	ST1= 0.0	0010					
	0.00114064	ST2= 0.0		•				
	115.541145		5.54114	5				
	-0.26	W= -0.	03					
€m= -	-0.0011	€m= -0.	0001					

#### Disclaimer

All advice or information from MPA-The Concrete Centre is intended for those who will evaluate the significance and limitations of its contents and take responsibility for its use and application. No liability (including that for negligence) for any loss resulting from such advice or information is accepted by MPA-The Concrete Centre or its subcontractors, suppliers or advisors. Users should note that all MPA-The Concrete Centre software and publications are subject to revision from time to time and they should therefore ensure that they are in possession of the latest version.

This spreadsheet should be used in compliance with the accompanying publication 'User Guide RC Spreadsheets: v4' available from The Concrete Centre www.concretecentre.com/rcdesign Tel +44 (0)1276 606800


Status of spreadsheet Public release version. This spreadsheet is shareware but may not be used for commercial purposes until the user has registered with The Concrete Centre using the licence validation form available on The Concrete Centre website www.concretecentre.com/rcdesign

#### Revision history RCC61 Basement Wall.xls

Date	Version	Action	
01-Apr-10	RCC61 v4.0	Re-badged as TCC/Mineral Products Association.	
21-May-09	RCC61 v3.4	Corrupted picture replaced on DATA page.	
01-Oct-08	RCC61 v3.3	Reference corrected at DESIGN!!107.	
25-Sep-08	RCC61 v3.2	Correction to ST2 values on !Crackwidth.	
28-Jun-06	RCC61 v3.1	v3 release. Page nos, User Guide and registration details amended.	565
12-Nov-05	RCC61 v3.0	Updated to 2005 versions of BS8110 & BS8666	586
22-Jan-03	RCC61 v2.1	DETR logo replaced by DTI.	
11-Oct-02	RCC61 v2.0	Version 2 enhancements	591
29-May-02	RCC61 v1.4	Data! Main diagram made into jpg	399
15-Apr-01	RCC61 v1.3	Design section reinforcment summary amended.	399
20-Jun-00	RCC61 v1.2	Eccy Mt 7 & P-Delta Mt revised (DESIGN!D29:D30)	399
24-Mar-00	RCC61 v1.1	Crack width w for top of inner base amended. Notes re crack widths and cracking added.	
06-Aug-99	RCC61 v1.0	First public release. Includes b version comments	398


## **APPENDIX D**

**Design Principle Drawings** 



PROPOSED BASEMENT PLAN SHOWING UNDERPINNING & FOUNDATIONS

PARTY WALL MIN. 480 THK.



UNDERPINNING NOTES:-

- ALL RENFORCED CONCRETE CAST ON THE GROUND TO BE PLACED ON SOME C28 CONCRETE BLINDING
- . POUNDATIONS HAVE BEEN DESIGNED ASSUMING A SAFE GROUND BEARING PRESSURE OF ROMAINS\*. THE BEARING STRATA TO BE APPRIVED BY THE LOCAL AUTHORITY BUILDING INSPECTION BEFORE LAYING ANY BUILDINGS OF CASTING OF FOUNDATIONS, ANY ADDITIONAL POEM AT THE AUTHORIS OF SOUTH OF THE BUILDING CONTINUE FINE. IN THE PUT OF ANY EXTENSIVE AUDITORIAL EXCLANTION DETAILS FINE. IN THE PUT OF ANY EXTENSIVE AUDITORIAL EXCLANTATION BERNE REQUIRED THE ENGINEER HIGH THE AUTHORIS DE AUDITORIAL PRESSION STRUCTURES OF REQUIRED.
- 3. THE ENGINEERS DESIGN ASSUMES B. TAKES ACCOUNT OF A GROUND WATER TABLE EXISTING WITHIN 2.m. OF THE BASSMENT FORMATION LEVEL ALL TO BE COMPRISED BY SUIL S MYST INCATION BY OTHERS. ANY GROUNDWATER SHALL BE NOTHED TO THE ENGINEER M WITTIN PRICE TO BE DESIGNED FOR THE BASSMENT WORKS SALL THAT MIS DESIGN HAY BE REVIEWED AND SUBJECT TO HIS FORTHER.
- CONCRETE:
  1. UNDERPRIMENT BASES & WALLS) TO BE GRADE C35 BI ACCORDANCE
  WITH BE 51th, AM APPROVED RAPID MARDEMING ASSIST TO BE ADDED
  BY ACCORDANCE WITH HAMIFACTURERS INSTRUCTIONS AND
  SPECIMELATION.
- SLAS TO BE GRADE C35 IN ACCORDANCE WITH BS 8116
- ALL CONCRETE AGAINST BLINDED ON EARTH SURFACES IS TO BE CLASS IS-2 ACEX AL-2 IN ACCORDANCE WITH SPECIAL DIGEST 1 OF DRE GUIDANCE (CONCRETE IN AGRESSIVE GROUND Part 1 Assessing the aggressive chemical environment, Special Digest 1, 2085. TULD.1
- UNDERPHANING TO BE CARRIED OUT IN 1966 MAXIMUM LENGTHS.
- ALL UNDERPOONING WALL STEMS AND BASE SECTIONS ARE TO BE DOWELD TOGETHER WITH HIZ BARS AT 150mm/ (LENGTH OF BARS 400mm)
- ANY BACKFILLING BEHIND RETAINING WALLS TO BE CARRIED OUT USING C20 CONCRETE HDC.
- B. THE UNDERSIDE OF THE EXISTING WALL OR FOUNDATION SHALL BE TREMED AND CLEAKED OF ALL MID & DEWISS BEFORE ORY PACIONS. THE DRY PACK SHALL BE A 13 MIX AND WELL RAPPED IN HORIZONTAL AYERS NOT EXCEOSING TIME THOOLOGISS. DRY PACIONS SHALL BE LEFT 24 HOURS BEFORE EXCAVATIONS ARE COMMENCED ON ADJACCHET MOREPIES.
- I. AFTER EXCAVATING ADJACENT PREVIOUSLY CAST BASES, CLEAN AND SCABBLE EXISTING SURFACE OF CONCRETE.
- 2. ALLOW 48 HOURS HINHUM BEFORE DRY-PACKING OVER WALLS.
- 3. SEQUENCE OF UNDERPROVING WORKS TO BE ASREED ON SITE WITH ENGINEER PROOF TO CONNECTE: OF WORKS.
- 4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL NECESSARY DE-WATERING OF EXCAVATIONS OURING THE EXECUTION OF THE WORKS.

- GENERAL NOTES:
- THIS DIRAWING MUST BE READ IN COMJUNCTION WITH ALL RELEVANT ARCHITECTS AND SPECIALIST DIRAWINGS WHICH MUST BE REPERRED TO FOR VERIFICATION OF LEVELS AND SETTING OUT.
- D. ALL OPPENSIONS IN HELLINETINES HALLESS MOTED OTHERWIS
- 3. DO NOT SCALE THIS DRAWING
- . THIS CIRALWING IS TO BE READ IN CONJUNCTION WITH THE GROUND INVESTIGATION REPORTS
- 5. THE MAIN CONTRACTOR SHALL BE RESPONSIBLE FOR EXCELLINIS ALL RECESSARY TEPORARY MORES OLLURION (DESIGN WHITE) SHALL BE CARRIED FOR A SHALL YELLOW THE ANALYSIS OF THE MAIN CONTRACTOR SHALL PROVIDE ALL REPRAISES SHALL PROVIDE ALL RECESSARY MAIN AND CONTRACTOR SHALL PROVIDE ALL RECESSARY MAINES FULL RECEIVED STATE INSENSIT SHOW DESCRIPTION OF ALL RECESSARY PARKIES FULL RECEIVED STATE INSENSIT SHOW DESCRIPTION OF ALL
- 5. THE CONTRACTOR IS RESPONSIBLE FOR HABITADING THE STABILITY OF THE EXISTING BULLDING AND ADJUMBED PROPERTY TOGETHER WITH EXCAVATION AND EARTH-WORKS AND PUST TAKE ALL NECESTARY PRECAUTIONS TO SAFEBLAND THIS THROUGHOUT EXECUTION OF THE WORKS.

- L THE LOCAL AUTHORSY'S BUILDING RESPECTOR AND THE EMBRIER ARE TO BE BECOMED BY THE CONTRACTOR IN WINTING AT LEAST 48 HOURS PRIOR TO THE MORKE STARTING ON STILL THEIR AGREEMENT HUST DE OBTAINED REPORTE MORK CAN COMPOSE
- II. THE CONTRACTOR MUST MAINTAIN ANY EXISTING SERVICES RE ADJOHNS PROPERTY AS NECESSARY.
- THE CAVITY DRAIN TO WALLS AND SLAB TO BE IN ACCORDANCE WITH ARCHTECTS AND SPECIALISTS DETAILS INCLUDING DRAINASE AND PT TO SPECIALISTS DESIGN AND DETAILS.
- 12. A PULL CONDITIONAL AND PHOTOGRAPHIC SURVEY IS TO BE UNDERTAKEN THE PROPERTY AND ADJACENT PROPERTIES PRICE TO THE CONNECTIONAL
- EL THE CONTRACTOR IS TO DESIGN\_SPECIFY AND PROVIDE ALL METESSARY TEMPORARY VOICES BILLIONIS THE PROPERTS AND METELINIS OF ALL DESITING WALLS AND PROMOMENTATION TO HOT THAT THE DIDETING POUNDATIONS INVESTIGATION TO WE THAT THE DIDETING POUNDATIONS HAVE BE FRANKE, LOOSE AND RECEIVE MIZARDOUS SULTABLE PREASURES AND SAFE WORKING PRACTICES AND THE WINDOWS SULTABLE PREASURES AND SAFE WORKING PRACTICES AND THE WINDOWS SETTING TO SUPPORT THE RETAINED SOR, BORNING, STRUCTURES ANDIVE AND ADMINISTRATION OF WEIGHT SAFE WINDOWS SETTING THE WINDOWS AND ADMINISTRATION OF WEIGHT SAFE WAS AND ADMINISTRATION OF WAS AND ADMINISTRATION OF WEIGHT SAFE WAS AND ADMINISTRATION OF WAS AND
- 14. TRAL PITS ARE TO BE DUE PRIOR TO THE COMPENCIONEST OF THE NAM WORK TO EXPOSE THE DOSTOR POWERATORS AND ARY POSSORE HISTORY (MOCEPHARMS VIND) HAY DOST THE DESIRE AND BETALS OF THE PROPOSED BUENDAMS NAM YEST TO SERVED TO SUIT AND SHALLD BE REPORTED IN WINTOKE TO THE ENGINEER PRIOR TO ANY PROPRICATION DEMO
- 6. NEPER TO ARCHITECTS SPECIFICATION FOR ALL DAMP PROOFING DETAILS INCLUDING OPC, DPY'S & BASEMENT WATER PROOFING.
- N. ALL WONDGAMENIP B. MATERIALS USED IN RESPECT OF THE WORKS SHALL NO IN ACCORDANCE WITH THE CUMBERT WINTED STANDARDS AND CODES OF PRACTICE WHERE RELEVANT TO THIS PROJECT.

#### SUPERSTRUCTURE NOTES:-

- STEELWORK TO BE MILD STEEL GRADE 5275 IN ACCORDANCE WITH BS 4360 FOR QUALITY AND BS 5958 FOR DESIGN, DETAIL AND
- ALL STEELWORK IS TO BE CLEANED TO SWEDISH 2 SA AND PRIMED WITH HINDREN 75 MICRON DPT. WORKS APPLIED APPROVED PRIMER.
- . ALL BEAM TO BEAM CONNECTIONS SHALL BE 12mm WELDED END PLATES (6mm FPFW) & No. H20 (8.8) BOLTS, OR SIMLAR APPROVED.
- FIRE PROTECTION TO ALL STEELWORK TO BE IN ACCORDANCE WITH ARCHITECTS DETAILS
- PADSTONES TO BE CSO GRADE CONCRETE WITH A HAX. 1999 AGGREGATE SIZE OR SOLID CLASS 'A' ENGINEERING BRICKWORK IF
- ALL NEW STRUCTURAL TIMBER TO BE GRADE C24 TO BS 5260 AND ALL ENDS TREATED ETC TREATED WITH AN APPROVED TIMBER
- 36:5 GMS STRAPS TO BE PROVIDED AT 125m CENTRES TO ALL PLOORS TO COMPLY WITH PART AS DISPROPORTIONATE COLLAPSE SECTION 5c. FOR CLASS 2A BUILDINGS.
- . Brickwork to be constructed in Class 'A' sold engreering Brickwork with a himbun crushing strength of 35 M/mm<sup>2</sup>. Blockwork to have a himbun crushing strength of 3.5 M/mm<sup>2</sup>. ALL Unless noted otherwise.
- ALL MASONRY SHALL BE LAID IN CLASS (III) MORTAR EXCEPT BELOW OPC CLASS (I).
- 10. ANY CUTTING AWAY OF EXISTING BRICKWORK TO BE CARRIED OUT CAREFULLY TO REDUCE DAHAGE TO SURROUNDING AREAS TO A MINIMUM.
- II. THE CONTRACTOR IS RESPONSIBLE FOR THE STABILITY OF THE EXISTING STRUCTURE AND ADJORMING PROPERTIES DURING EXECUTION OF THE WORKS AND MUST TAKE ALL NECESSARY PRECAUTIONS TO SAFEGUARD THIS STABILITY.

REFER TO DRAWING 7922-101 FOR **SECTIONS & DETAILS** 

Cranbrook<sup>e</sup>

Basement design & construction


**HORWITZ ASSOCIATES** 

PROPOSED BASEMENT AT No. 63 ROSSLYN HILL, HAMPSTEAD


PROPOSED BASEMENT & GROUND FLOOR GENERAL ARRANGEMENT

FEB. 2020
On — Checked \_ REV CRAMBROOK BASEMENTS 7922-PS-100


CTIO ~ FO S ZO O



SECTION 1 - 1 [Scale 1:20]



SECTION 2 - 2 [Scale 1:20]



## **APPENDIX E**

Specification

#### **63 ROSSLYN HILL NW8 5UQ**

#### **SPECIFICATION**

#### **FOR WORKS**

#### 1.0 DEMOLITION

#### 1.1 Scope

The areas to be demolished are shown on the drawings. The Contractor shall make good, at his own expense, any areas demolished beyond the limits shown on the drawings.

#### 1.2 Demolition

All demolition work shall be carried out strictly in accordance with BS 6187 2011. Before commencement of work the demolition Contractor shall submit details of his insurance cover. In particular, cover shall be obtained for claims arising out of any act, neglect or omission by the building owner, as well as providing for all contractual liability.

If it is necessary to erect temporary hoardings, etc., the Contractor shall obtain all necessary licences, give all notices and pay all dues in connection therewith.

#### 1.3 Temporary Works

The Contractor shall be responsible for the stability of the existing building on the site and any adjoining sites and he shall take all necessary precautions to safeguard this stability. Any temporary shoring, propping or strutting inserted to ensure this stability shall comply with the relevant British Standards.

Any scaffolding erected shall comply with BS EN 12811 and BS 5975 2008.

Any metal props and struts required shall comply with BS 4074 2000.

Any temporary shoring, propping or strutting shall be provided with an adequate foundation.

#### 2.0 EXCAVATIONS

#### 2.1 General

Excavation for the various parts of the works shall be carried out to the widths, lengths and depths indicated on the drawings or as directed by the Engineer on site.

Materials arising from the excavations shall be removed from the site.

Any excavations taken out below the depth required for construction of the works shall be replaced at the Contractor's own expense with approved and properly compacted materials as directed by the Engineer on site.

#### 2.2 Planking and Strutting

Where excavations are taken out with vertical sides the Contractor shall, if necessary, provide all shoring, planking and strutting for supporting the sides of excavations at his own expense. The Contractor shall be responsible for the stability of earth works and shall take all necessary precautions to safeguard this stability.

#### 2.3 Temporary Drainage

All excavations shall, as far as is reasonably possible, be kept free of water during the progress of the works and the Contractor shall provide, at his own expense, all temporary drains, sumps and pumping machinery that may be needed for this purpose.

#### 2.4 Formation of Works

No concrete shall be poured until the ground formation for it has been inspected by the Building Control Officer.

The Contractor shall notify the Local Authority when approvals are required.

The formation of all excavations shall be trimmed and levelled 75mm above the formation level shown on the drawings prior to approval of the Engineer. In the case of mass concrete footings a further 75mm shall be taken out and the whole base poured immediately. In the case of reinforced concrete bases a further 125mm shall be taken out and the formation sealed with a 50mm layer of blinding concrete 1:8 laid as dry as is practicable.

Horwitz Associates

Job No: 7922 20 February 2020

#### 2.4 Formation of Works (cont'd)

If the exposed formation is not satisfactory for the loading required, the Contractor shall execute such extra works as may be necessary to achieve a firm foundation as directed by the Engineer on site.

Should the material forming the bottom of any excavation, whilst sound at the time of excavation, become soft or deteriorated due to percolation of water or unsatisfactory protection during the progress of the works, the Contractor shall, at his own expense, remove such softened or loose material and replace it with approved material as directed by the Engineer on site.

The top surface of all blinding concrete under reinforced concrete work shall be such that the tolerance from the true level is +0, -20mm.

All existing construction and obstructions in the way of the proposed new foundations shall be reported to the Engineer. They shall then be removed or otherwise as directed by the Engineer.

#### 3.0 UNDERPINNING

WORKMANSHIP: The work shall be carried out in accordance with the Engineer's drawings and instructions and to the approval of the Architect and the Building Control Officer.

Any other sequence of operations or method of working proposed by the Contractor is to be submitted to the Architect and copied to the Engineer and agreed in writing a minimum of 14 days before work is to be commenced on site.

CONTRACTORS RESPONSIBILITIES: The Contractor shall be responsible for the safety of the underpinned structure and provide all necessary shoring, strutting and bracing to ensure its safety and stability at all times.

SERVICES: The Contractor is also to carry out a survey of the property and adjacent area to establish to location of obstructions such as service runs or drains. Any obstruction found is to be brought to the attention of the Architect/Engineer. The Contractor is to allow for any temporary support to the services or obstructions during the underpinning.

CONSTRUCTION SEQUENCE: The underpinning is to be undertaken in short sections not exceeding 1.2 metres in length. The underpinning is to be undertaken on a 'hit and miss' sequence as shown on the drawings or otherwise agreed in writing by the Engineer.

No adjacent pin is to be excavated until a minimum 48 hours after the adjacent pin has been cast and dry pack has been installed.

The Contractor is to provide drawings marked up to show the proposed sequence of underpinning a minimum of 14 days before work is commenced.

EXCAVATIONS: Excavation shall be to the depth and width shown on the drawings. However, where tree roots are encountered new underpins are to extend 600mm below the last trace of any root activity. The sides of the excavation shall be adequately shored and propped to prevent subsidence or slip of the soil. Soil faces behind the pin and at the formation level shall be undisturbed.

Any soil faces behind the underpinning that require to be retained shall be by precast concrete poling boarding. The boards are to have holes to enable the void behind the boards to be grouted up. The poling boards are to be measured as left in.

INSPECTIONS: All excavations are to be inspected by the Engineer and/or the Building Control Officer. Minimum notice of 24 hours is to be given when excavations are ready for inspection.

PREPARATION: The sides of the completed pin are to be thoroughly cleaned and scabbled to the satisfaction of the Engineer.

The soffit of the existing footings is to be levelled off and cleaned of all loose or detrimental material.

No projecting partitions of the existing footings are to be trimmed except as shown on the drawings or directed by the Engineer.

The Contractor must provide shear keys.

Allow for 150 deep x 100 wide shear keys across width of scabbled interfaces at 1m maximum vertical centres. Minimum 2 per face. Form in timber or polystyrene.

ANTI-HEAVE PRECAUTIONS: Before carrying out concreting introduce anti-heave precautions in the form of Claymaster as directed by the Engineer to the faces of the excavation.

PLACING CONCRETE: The concrete for the underpinning is to be mass concrete and poured continuously to 75mm below the soffit of the existing footing. The concrete is to be fully compacted using a mechanical vibrator.

The top 75mm of the pin is to be filled to the full depth and width of the void with a well rammed C35 concrete using 5mm-10mm coarse aggregate and Conbex 100' expanding admixture by Messrs Fosroc UK Ltd in accordance with their instructions. The filling of this void is to be undertaken 24 hours after the mass concrete has been poured.

CONCRETE GRADE: On works where a full specification has not been provided, a FND2 mix should be used. This has characteristic 28 day strength of 35N/mm2 and is suitable for Class 2 sulphate soils.

OVER-EXCAVATION: Except where noted otherwise on the drawings, areas of over-excavation are to be backfilled with a granular material and compacted in 225mm layers to provide a stable sub-base compatible wish the final finishes.

SPOIL: The Contractor will include in his prices for the removal of all spoil arising from the works which is not suitable for backfilling purposes.

RECORDS: A full record of each section underpinned is to be kept on site and readily available for inspection by the Engineer or Building Control Officer.

GUARANTEE: The Contractor is to provide a 10 year insurance backed guarantee for the underpinning works.

#### 4.0 PLAIN & REINFORCED CONCRETE WORK

#### 4.1 Scope

This specification applies to the materials and workmanship in plain and reinforced concrete work to beams, columns, foundations, slab, staircases, walls and similar work, the extent of which is shown on the drawings.

#### 4.2 Materials

Aggregates - fine and course aggregate shall be obtained from natural sources and shall comply with BS EN 12620 2012.

Cement shall be Ordinary Portland Cement complying with BS EN 197-1 2011.

Water used for any purpose shall be from an approved public supply.

Reinforcement - mild steel bars shall be plain round, hot rolled bars complying with BS 4449. High tensile bars shall be rolled steel bars of square or rolled ribbed indented section, which have been twisted cold, complying with BS 4461. Hot rolled bars shall have a yield stress of 420 N/mm² complying with BS 4449. Welded fabrics, twisted square bar fabric or expanded metal shall comply with BS 4483.

#### 4.3 Concrete Mixes

Concrete mixes to be used are noted on the drawings. The proportions of aggregate and cement shall be measured by weigh batching.

Ready-mix concrete may be used in accordance with BS EN 206 with the Engineer's prior approval.

The mix proportions and minimum strength requirements shall comply with BS 8110 and BS 8500 as stated on drawings.

All reinforced concrete work, unless otherwise specified, shall be compacted by means of poker vibrators.

#### 4.4 Workmanship

Workmanship shall be in accordance with BS 8110 as stated on the drawings.

All concrete shall be properly cured for a minimum of seven days. The method of curing shall be agreed with the Engineer prior to the commencement of the work.

The interval between adding water to the dry mix and final placing shall not exceed thirty minutes and thereafter the concrete shall not be disturbed.

The method of working in cold weather shall be as set out in BS 8500 and Concrete Society Publication CS164-Good Concrete Guide 8 and is to be agreed with the Engineer prior to the commencement of the work.

The Contractor shall be responsible for the strength and stability of all temporary formwork and its supports. All formwork shall be constructed to prevent any losses of grout or mortar from the concrete. Adequate openings and removable panels shall be provided in shuttering for inspection and cleaning, etc. Connections shall be so constructed to permit easy removal of the shuttering.

All faces of shuttering and moulds in contact with wet concrete shall be treated with mould oil or other coating to the Engineer's approval.

The timing of the removal of formwork shall be entirely the Contractor's responsibility and forms shall not be struck until the concrete reaches a strength of at least twice the stress to which the concrete may be subjected at the time of striking. All formwork shall be removed without shock or vibration that would damage the concrete construction.

The surface finish to the concrete shall be as specified by the Inspecting Officer.

Concrete test cubes shall be made as directed by the Engineer and shall conform to BS 1881. The location of the concrete under test shall be clearly stated on the Test Certificate.

Reinforcement shall be free from pitting, loose rust, mill scale, paint, oil, grease, adhering earth, ice or any harmful matter that may impair the bond between the concrete and the reinforcement.

All reinforcement shall be bent in accordance with BS 4466.

All reinforcement shall be placed and maintained in the position shown on the drawings with plastic chairs or similar.

#### 4.5 Concrete in Cold Weather

No concrete shall be mixed or placed whilst the temperature is below 2°C on a rising thermometer or below 4°C on a falling thermometer, or freezing temperatures are forecast in the next 24 hours, but in any event, the following should be noted:-

- 1. No part of fresh concrete, at the time of placing, should have a temperature of less than 5°C.
- All surfaces with which the fresh concrete will come into contact, including those of formwork, reinforcement and hardened concrete, should be free of snow, ice and frost.
- Regardless of the air temperature at the time of placing, the temperature of the concrete should at no point fall below 5°C, nor should the water curing be applied until the concrete in the structural element reaches a strength of 5N/m².
- 4. Any concrete damaged by frost shall immediately be removed and the member re-constructed at the Contractor's own cost.
- 5. The Contractor shall provide an accurate maximum and minimum thermometer and hang in an approved position in the works and keep accurate daily record of these maximum and minimum temperatures for inspection by the Engineer.
- 6. Concrete may be preheated in the mixer by heating the mixing water to not more than 40°C.
- 7. The use of calcium chloride or any other chemicals to accelerate hardening will not be allowed.

#### 5.0 STRUCTURAL STEEL WORK

#### 5.1 Scope

This specification applies to the supply of materials and workmanship in connection with the fabrication, delivery to site and erection of structural steelwork consisting of beams, stanchions, connections, including all necessary fittings, bolts and welding, the extent of which is shown on the drawings.

The Contractor shall visit the site and carry out a survey to check the spans, section sizes and setting out of the existing steelwork and structural arrangement.

#### 5.2 Materials

Mild steel shall comply with BS EN 10025 2004 Grade 5275 for quality and BS 4-1 with regard to form.

High tensile steel shall comply with BS 1775 for quality and BS 4 Part 2 with regard to form.

Steel tubes shall comply with BS 1775 for quality and BS 4 Part 2 with regard to form.

Cold formed steel sections formed from plate, sheet or strip steel 6mm thick and under shall comply with P.D. 4064 Addendum No 1 to BS 449.

Black bolts and nuts shall comply with BS 916 and BS 1769.

High strength friction grip bolts shall comply with BS 4395 and BS 4604.

The term 'weld', 'welds' and 'welding' shall refer to work done by electric metal arc welding and shall comply with BS EN 1011-2 2001. The Contractor shall provide certified evidence that every welding operative has passed tests as required by BS 5950 and specified in BS 2645.

#### 5.3 Workmanship

Workmanship shall be of a first class standard and the design, fabrication and form of details shall be in accordance with BS 5950 and to the approval of the Engineer.

Cleaning of all surfaces to be painted shall be carried out in accordance with the requirements of BS ISO 27831.

All steelwork, unless otherwise agreed, shall be painted with one coat of zinc phosphate to 75 micron DFT.

The size of the steel members are shown on the Engineer's drawings and must not be varied without his approval.

#### 5.4 Connections

The connections are to be of bolted or welded construction and of adequate strength to sustain the various loads indicated on the drawings and all details shall be sent to the Engineer for his examination before any work is put in hand.

Job No: 7922 20 February 2020

#### 6.0 SHORING TO FORM OPENINGS

#### 6.1 Scope

The scope of the work comprises the erection of internal shoring to support the structure whilst new openings are formed or existing openings are extended, the extent of which is indicated on the drawings.

Details of the existing work have been assumed. These are to be checked on site by the Main Contractor and any discrepancies reported to the Engineer so that adjustments may be made to the structural scheme if necessary.

#### 6.2 Materials

All structural timber used to form the temporary shoring shall comply in all respects with BS 5268 and BS 4978, the grade of timber to be used shall be as specified on the drawings.

Any metal props and struts required shall comply with BS 4074. The type of prop shall be as specified on the drawings.

Any scaffolding erected shall comply with BS EN 12811 and BS 5975 2008.

Any shoring, propping or strutting shall be provided with an adequate foundation to the approval of the Engineer.

#### 7.3 Sequence of Operation

Before any openings are formed by removal of brickwork, the internal shoring, as shown on the drawings, shall be in position and shall be to the satisfaction of the Engineer.

The Contractor shall, at all times, allow access to the Engineer to inspect the works.

Notwithstanding the work specified to be carried out, the Contractor shall carry out the work in such a manner as to safeguard the structure from further structural damage.

The Contractor shall regularly inspect all shoring to ensure that it is maintained in a rigid condition and also regularly inspect the structure for any movement whatsoever. Should any movement be noted before, during or after the execution of the works described in this specification, he shall notify the Engineer immediately and shall also place in position any props, needles and shores he may consider necessary.

Job No: 7922 20 February 2020

#### 6.3 Sequence of Operation cont'd

The Contractor shall provide all necessary scaffolds, screens, platforms, etc., to protect the adjoining properties and public from damage or falling objects during the execution of the works.

The shoring shall be constructed with props, needles, braces, wedges, etc., as shown on the drawings or in accordance with any written instructions which may be issued by the Engineer.

The whole shall be placed in position with the minimum of shock to the existing structure and shall, in every way, be to the satisfaction of the Engineer. The location of the seating for members shall be inspected by the Contractor to ensure that the existing brickwork is sound. In no case shall a shoring member be placed against lathe and plaster work. In such locations the lathe and plaster shall be cut away to expose the brickwork or main structural frame. The Contractor shall provide all necessary timber packs, folding wedges, etc., as may be instructed by the Engineer. All braces shall be properly mitred, bolted or spiked as instructed by the Engineer and the whole of the shoring maintained in a rigid condition.

On completion of the shoring the openings of the required size shall be formed. All brickwork shall be removed by hand, brick by brick, with the minimum of shock on the existing structures. Under no circumstances shall mechanical appliances be used for this work without prior approval of the Engineer in writing.

The brickwork reveals shall be reinstated in accordance with the drawings. The padstones shall be positioned to the levels shown on the drawing. The new steel supports shall be erected and shall be pinned up solid using semi-dry 1:1.1/2:3 mix having a minimum cube crushing strength of 25:5 N/mm² at 28 days using a maximum aggregate size of 10mm well rammed into position using a club hammer and caulking tool. None of the shoring shown on the drawing shall be removed until the dry packing has achieved its full strength.

During the removal of the shoring, the Contractor shall ensure that it is taken down with the minimum of shock and that all props are released slowly to ensure that all displaced members are securely bedded down to their new seating.