

NOTE: S2 TO REMAIN ON EXISTING TECHNOLOGIES AS NO CURRENT PATH FOR UPGRADE

PROPOSED MBNL 2No. ANTENNAS AT 32.60m MEAN BEARING OF 330° MOUNTED ON EXISTING SUPPORT POLES FIXED TO GRILLAGE

EXISTING MBNL 2No. ANTENNAS MOUNTED ON SUPPORT POLES FIXED TO GRILLAGE , RRUS AND BOB MOUNTED ON FREESTANDING FRAME.

EXISTING 1No. CTIL ANTENNA ON FACE MOUNTED POLE

EXISTING 2No. MBNL DISHES MOUNTED ON SUPPORT POLES FIXED TO GRILLAGE

EXISTING CAT LADDERS TO UPPER ROOF

UPPER ROOF
+30.2m AGL

LOWER ROOM ROOF LEVEL
+23.95m AGL

TOP OF MBNL ANTENNAS
+33.70m AGL

C/L OF MBNL ANTENNAS
+32.60m AGL

U/S OF MBNL ANTENNAS
+31.50m AGL

C/L OF DISHES
+31.70m AGL

PARAPET LEVEL
+34.0m AGL

ROOF LEVEL
+33.70m AGL

EXISTING 2No. CTIL ANTENNAS ON FACE MOUNTED POLES
EXISTING CTIL ANTENNA ON FIXED TRIPOD

PROPOSED 2No. MBNL 6000 DISHES MOUNTED ON MAFI 4309 FRAME

PROPOSED MBNL 8No. RRUs, 2No. MHA's , 3No. BOBs, 2No. ACTIVE ROUTERS & EXISTING 2No. RRU's 1No. BOB ON PROPOSED BOX STRUCTURE

EXISTING MBNL INTERNAL ROOM TO BE UPGRADED INTERNALLY C/W BOB's & PASSIVE ROUTERS

PROPOSED MBNL 2No. ANTENNAS AT 36.40m MEAN BEARING OF 240°, 8No. RRUs, 2No. MHA's , 3No. BOBs, 2No. ACTIVE ROUTERS ON PROPOSED ROOFPD STRUCTURE

EXISTING CAT LADDER TO PLANT ROOM ROOF

TOP OF MBNL ANTENNAS
+37.50m AGL

C/L OF MBNL ANTENNAS
+36.40m AGL

U/S OF MBNL ANTENNAS
+35.30m AGL

Antenna Aperture ID	Proposed 4G/5G Bearing	Operator: Shared/ EE/H3G
A1	330°	EE
A2	330°	H3G
B1	120°	EE/H3G
B2	120°	EE/H3G
C1	240°	EE
C2	240°	H3G

Master:	MBNL / EE / H3G	Project:	ATAP	Purpose of Issue:	Planning	Issue:	F
Date:	19/09/2020	Revision / Upgrade Description: Sectors 3 amended to Roofpod					
Drawn:	ASE						
Checked:	J Maguire						
Approved:	C.Yates						
Master:	MBNL / EE / H3G	Project:	ATAP	Purpose of Issue:	Planning	Issue:	E
Date:	22/07/2020	Revision / Upgrade Description: Sector 2 being retained as is					
Drawn:	B.Binding						
Checked:	J Maguire						
Approved:	C.Yates						
Master:	MBNL / EE / H3G	Project:	ATAP	Purpose of Issue:	Planning	Issue:	D
Date:	31/03/2020	Revision / Upgrade Description: Sectors 2 & 3 amended to freestanding solution Sector 2 Bearing amended					
Drawn:	S. Tyndall						
Checked:	J Maguire						
Approved:	C.Yates						
Master:	MBNL / EE / H3G	Project:	ATAP	Purpose of Issue:	Planning	Issue:	C
Date:	29/02/2020	Revision / Upgrade Description: Site Solution changed to H4a as a result of HLD					
Drawn:	ASE						
Checked:	J Maguire						
Approved:	C.Yates						
Master:	MBNL / EE / H3G	Project:	Acquisition Trial	Purpose of Issue:	Planning	Issue:	B
Date:	08/02/2019	Revision / Upgrade Description: Antenna mounting arrangement amended					
Drawn:	J.Howden						
Checked:	C.Yates						
Approved:	D.Pankhania						



Hutchison 3G UK Limited
Star House, 20 Grenfell Road
Maidenhead, SL6 1EH
Tel: 01628 765 000
Fax: 01628 765 001
H3G Base Station Information Line
0845 6043000
Available 24/7 Monday to Friday



Hatfield Business Park
Hatfield
Hertfordshire
AL10 9BW
Tel: 01707 315000
Fax: 01707 319001



Mobile Broadband Network Limited
Sixth Floor, Thames Tower, Station Road, Reading, RG1 1LX

MSP & Design Consultant



WALDON TELECOM
PHOENIX HOUSE
PYRFORD ROAD
WEST BYFLEET
SURREY
KT14 6RA

TEL : 01932 411011
FAX : 01932 411012

Site Name:

GREATER LONDON HOUSE

Site ID:

788847

Address:

HAMPSTEAD ROAD
CAMDEN
LONDON
NW1 7QY

Title:

265 PROPOSED MAX CONFIG ELEVATION

Project:

ACQUISITION TRIAL

Purpose of Issue:

PLANNING

EE Cell ID:
98528

MBNL Cell ID:
CMN041

3UK Cell ID:
NWO187

Master Drawing No:

788847_CMN041_98528_NWO187_M006

Issue:

F

PROPOSED MAX CONFIGURATION ELEVATION NORTH

