

**BUILDING ENGINEERING SERVICES
TENDER SPECIFICATION
FOR
CAMDEN ROUNDHOUSE CAMPUS BUILDING**

CHECKING AND REVISION					
Revision	Description	Originator	Checked	Approved	Date
00	Tender (Mech)	HW	TS	WH	27/03/2020
01	Tender (Mech)	HW	TS	WH	17/04/2020

This document has been prepared for the titled project or named part thereof and should not be relied upon or used for any other project without an independent check being carried out as to its suitability and prior written authority of Ingleton Wood being obtained. Ingleton Wood accepts no responsibility or liability for the consequence of this document being used for a purpose other than the purposes for which it was commissioned. Any person using or relying on the document for such other purpose agrees and will by such use or reliance be taken to confirm his agreement to indemnify Ingleton Wood for all loss or damage resulting there from. Ingleton Wood accepts no responsibility or liability for this document to any party other than the person by whom it was commissioned.

Mechanical Ventilation Extract for Discharge of
Planning Condition 17 September 2020

SECTION 1.2

MECHANICAL INSTALLATION

PARTICULAR WORKS

1.2.6.3	TESTING AND COMMISSIONING DOCUMENTATION	66
1.2.6.4	WATER REGULATIONS	66
1.2.7	HEAT PUMP SYSTEMS	67
1.2.7.1	GENERAL	67
1.2.7.2	INDOOR FAN COIL UNITS	67
1.2.7.3	BS BOXES.....	68
1.2.7.4	VRV OUTDOOR HEAT PUMP UNITS.....	68
1.2.7.5	SPLIT HEAT PUMP UNITS.....	69
1.2.7.6	HEAT PUMP UNITS FOR VENTILATION PLANT.....	70
1.2.7.7	PIPEWORK AND ISULATION	71
1.2.7.8	CONTROLS.....	72
1.2.7.9	REFRIGERANT LEAK DETECTION AND PUMP DOWN SYSTEMS	73
1.2.7.10	REFRIGERANT COILS FOR AHUS	74
1.2.7.11	TESTING AND COMMISSIONING	74
1.2.8	MECHANICAL VENTILATION	75
1.2.8.1	VENTILATION PLANT – GENERAL INSTALLATION REQUIREMENTS.....	75
1.2.8.2	VENTILATION DUCTWORK	76
1.2.8.3	ACOUSTIC TREATMENT TO DUCTWORK	78
1.2.8.4	DUCTWORK WITHIN FLOOR VOIDS.....	78
1.2.8.5	AIR HANDLING UNITS.....	78
1.2.8.6	ATTENUATORS	80
1.2.8.7	DUCT MOUNTED ATTENUATORS.....	80
1.2.8.8	VENTILATION WEATHER TERMINALS.....	80
1.2.8.9	SUPPLY AND EXTRACT GRILLES	81

1.2.8.10	DISPLACEMENT VENTILATION TERMINALS	81
1.2.8.11	EXTRACT FANS	81
1.2.8.12	DOOR TRANSFER GRILLES	82
1.2.8.13	DUCTWORK FIRE & SMOKE DAMPERS	82
1.2.8.14	DUCTWORK FIRE DAMPERS	84
1.2.9	AUTOMATIC CONTROLS AND POWER.....	84
1.2.9.1	AUTOMATIC CONTROLS AND POWER WORKS.....	85
1.2.9.2	CONTROL REQUIREMENTS.....	85
1.2.9.3	MECHANICAL CONTROL PANELS.....	86
1.2.9.4	PROPOSED NEW ELECTRICAL POWER INSTALLATIONS.....	89
1.2.9.5	BMS HEAD END.....	91
1.2.9.6	CONTROLS AND POWER: DESCRIPTION OF OPERATIONS.....	91
1.2.9.7	CONTROLS AND POWER: COMMISSIONING	94
1.2.9.8	TESTING AND COMMISSIONING DOCUMENTATION	95
1.2.10	ABOVE GROUND DRAINAGE	95
1.2.10.1	ACOUSTIC INSULATION	96
1.2.10.2	ABS PIPEWORK AND FITTINGS	96
1.2.10.3	PVC-U PIPEWORK AND FITTINGS	96
1.2.10.4	INTUMESCENT FIRE COLLARS	97
1.2.10.5	SHOWER OUTLETS	97
1.2.10.6	AIR ADMITTANCE VALVES.....	97
1.2.10.7	INSTALLATION GENERALLY	97
1.2.10.8	PIPEWORK ROUTES.....	98
1.2.10.9	FIXING PIPEWORK.....	98

£	p

£	p

£	p

£	p

To collection:

£	p

- To collection:**

The Contractor shall liaise with the main Contractor to coordinate opening positions and sizes. This shall include for the dampers and actuators access requirements

All grilles are to be supplied with PBD (plenum box for D diffusers with top/side entry to suit contractor's installation drawings) for louvre-faced diffusers. Air velocities to be less than 2m/s for plenum boxes.

To collection:

£	p

£	p

To collection:

£	p

APPENDIX A

MECHANICAL SERVICES

MECHANICAL SERVICES SCHEDULE

AHU Ref.		AHU-1	AHU-2	AHU-3	AHU-4	AHU-5	AHU-6
Location		Plant (R.E.03)	Plant (R.E.03)	Plant (R.E.05)	Plant (R.E.05)	Plant (R.E.05)	Plant (R.E.05)
Areas Being Served		Co-Working Space, Meeting Room and Breakout Space.	Studio C	Studio A	Studio B	Recording Studio	Reception, Multi-Use Space and 3rd Floor WC's
Size excl. ancillaries (mm)	(L)	2500	2500	1900	1900	1600	1700
	(H)	1476	1476	470	470	260	340
	(W)	954	954	1560	1560	1000	1150
AHU Type		Nuaire Vertical AHU XBC75-V-NCOWP	Nuaire Horizontal AHU XBC75-V-NCOWP	Nuaire Horizontal XBC55-H-NCO	Nuaire Horizontal XBC55-H-NCO	Nuaire Horizontal XBC15-H-NCO	Nuaire Horizontal XBC25-H-NCO
Design Flow Rate	(m3/s)	0.950	0.600	0.400	0.400	0.080	0.150
Heating / Cooling Coil		CON-3, 33kW	CON-4, 33kW	CON-5, 15.5kW	CON-6, 15.5kW	CON-7, 4kW	CON-8, 8kW
Power Supply	(ph/V/Hz)	3/400/50	3/400/50	1/230/50	1/230/50	1/230/50	1/230/50

Comments: **AHU-1- Co-Working Space, Meeting Room and Breakout Space.**

Inlet/outlet terminal, shut-off damper, 2No. Double deck silencers, frost coil, DX coil. Fully Weather proof.

AHU-2 - Studio C

Inlet/outlet terminal, shut-off damper, 2No. Double deck silencers, frost coil, DX coil. Silencer and DX coil modules inline ductwork, rather than connected to AHU. Fully Weather proof.

AHU-3 - Studio A

Inlet/outlet terminal, shut-off damper, 2No. Double skinned silencers, frost coil, DX coil. Fully Weather proof.

AHU-4 - Studio B

Inlet/outlet terminal, shut-off damper, 2No. Double skinned silencers, frost coil, DX coil. Fully Weather proof.

AHU-5 - Recording Studio

Inlet/outlet terminal, shut-off damper, 1No. Double skinned silencer, DX coil. Fully Weather proof.

AHU-6 - Reception, Multi-Use Space and 3rd Floor WC's

Inlet/outlet terminal, shut-off damper, 2No. Double skinned silencers, frost coil, DX coil. Fully Weather proof.