

Asbestos Containing Materials: Discovery: Give notice immediately of suspected asbestos containing

materials discovered during demolition work. Avoid disturbing such materials. Methods for safe removal. Submit details and statutory risk assessments.

Unforeseen Hazards: Unrecorded voids, tanks, chemicals, etc. discovered during demolition: Give notice.

Methods for safe removal, filling, etc: Submit details.

Site Condition at Completion Debris: Clear away and leave the site in a tidy condition.

Other requirements: Building occupied at all times and must be kept clear

All Materials removed from site are to be recycled offsite where ever possible. This includes existing floor finishes noted for removal (i.e. existing vinyl and carpet), metal framework and concrete/blockwork.

## PANELLING

match existing.

WINDOWS

Panelling to be refurbished, made good and protected throughout the construction programme; where infill/ replacement is required details to match existing. First FFL 91.66

construction programme; where infill/ replacement is required details to

Paint to windows to be stripped back, substrate to be made good and

prepared to receive new paint application. All detailing to window reveal to

be retained, refurbished and protected throughout the construction

programme. Materials and finish to match existing.

CEILING Lath and plaster ceiling to be retained and refurbished. Architectural moulds to be retained, made good and protected throughout the construction programme; where infill/replacement is required details to match existing. All redundant services to be removed. Any redundant penetrations to be infilled with matching materials. New penetrations introduced where required.

## WINDOWS

Paint to windows to be stripped back, substrate to be made good and prepared to receive new paint application. All detailing to window reveal to be retained, refurbished and protected throughout the construction programme. Materials and finish to match existing.

## Ground FFL 88.34


EXTERNAL WALL Existing face brickwork to be cleaned using water based system only; no chemical clean permitted. Masonry to be re-pointed; any damaged brickwork to be repaired where possible or replaced with matching brickwork.

WALLS Walls to be removed. Substrate to wall, ceiling and floor to be made good with all materials to match existing.

PARQUET FLOORING Existing floor finish to be retained, refurbished and protected throughout the construction programme.

DOOR

Paint to door to be stripped back, substrate to be made good and prepared to receive new paint application. All detailing to door reveal to be retained, refurbished and protected throughout the construction programme. Materials and finish to match existing.



SCAL	0 0.5 1 1.5 E - 1:50	2.5 m
Rev: D E F	Comments: Minor Material Amendments Minor Material Amendments Combined information from LBC App. Ref 2020/1464/L.	By: Date: RM 13-03-2019 MStL 27-03-2020 RM 08-09-2020

Do not scale this drawing All dimensions must be checked on site All rights reserved. No reproduction in any material form is permitted without consent.

Client:				
Sarah Bard Sassoon				
Project Title:				
24 Heath Drive, London, NW3 7SB				
Drawing Title:				
Strip-Out				
Section B				
Scale:	Date:	Drawn:	Checked:	
1:50@A1	JAN 18	ST	HV	
)				

<u></u>		

28 Scrutton	Street
London	
UK	
EC2A 4RP	

:	+44(0) 20 7247 2462
	enquiries@kyson.co.u
1.	www.leveen.co.uk

Project No.:	Drawing No.:	Revision:
508-16	1701	F

K V S O