




Internal Window Treatment: Window opening to be framed out with softwood timber packer to extents of existing frame offset by 15mm to allow for material infill to extents, which should be installed as per existing wall condition. Allowance to be made for 3-5mm skim coat and making good of plaster surround.

2. External Window Treatment: External wall finish to be lined with 25x50mm treated softwood timber battens at 400mm centres, installed to present level finished internal surface, finished with 15mm moisture resistant plasterboard.

3. Infill Treatment: Existing windows to be kept in-situ. No fixing to existing frames permitted.



A WG-05 Removed MStL 27-03-2020 WG-05 and WG-09 added. Windows RM 08-09-2020 to be blocked out instead of removals.

> Scale: Date: 1:20@A1 JAN 18 ST

Do not scale this drawing All dimensions must be checked on site All rights reserved. No reproduction in any material form is permitted without consent.

Client:

Project Title: 24 Heath Drive. London. NW3 7SB

Drawing Title: Proposed Window Schedule - Blocked Windows

Studio 28 Scrutton Street London EC2A 4RP T: +44(0) 20 7247 2462 E: enquiries@kyson.co.uk W: www.kyson.co.uk

Project No.: Drawing No.: 508-16 6104