

## SASH WINDOW OVERHAUL SPECIFICATION

- 1. Sand down and replace any rotten timber
- 2. Replace pulleys & chords
- 3. Re-weight sashes and install correct weights
- Install ventrolla draft strips to top, middle, and bottom rails and staff bead as indicated H on diagram
- 5. Replace parting beads and staff beads
- 6. Install new brass hardware ironmongery:
  - Sash catch hook catch brass
  - Sash lifts brass
  - Sash pulley brass
  - Sash pulls brass
  - Security lock brass
    Child restrictor brass
- Retain existing single glazing (I) 7.
- 8. Redecorate as per M60/130 and M60/131
- 9. Refix into existing openings
  - 10. Mastic sealant internally and externally

All as per L10/200

No.	Note
1	All dimensions to be verified on site by GENERAL CONTRACTOR prior to any work, setting out or shop drawings being prepared.
2	The contractor not to scale the drawings. Work to figured dimensions only.
3	© copyright SAUNDERS BOSTON LIMITED. All rights reserved. This drawing remains the property of SAUNDERS BOSTON LIMITED at all times and may not be reproduced or copied in whole or in part without their prior written consent.
4	This drawing and related specifications are for use only in the stated location.
5	This drawing is to be read in conjunction with all other Consultants drawings and specifications.

- 6 Drainage has not been surveyed and any/all pipe locations and below ground drainage runs are indicative.
- It is assumed that all works will be carried out by a competent contractor who will be working, where appropriate, to an approved method statement.

cale 1:5			C4 C3 C2	Secondary Glaz Planning discuss CONTRACT ISS SecondaryGlazii	SUE	08/10/20 18/09/20 10/09/20	SBA SBA SBA	RJB NG RJB
0.05 0.1 0.15	0.25m		C1 No.	Stage 4 - Contra Revision	actor's Proposals	04/09/20 Date	Chk	Auth
	Bo	unders oston	Client University College London Job GAMMA					
Eastern Gate House, 119 New Cambridge CB5 8HA	vmarket Road, The Gene	erator, The Gallery, King's Wharf , Exeter EX2 4AN	Drawing Proposed Window Overhaul Schematic					
T:01223 367733 office@saundersboston.co.uk	T:01392 3	348627 ndersboston.co.uk						
			Scale 1:	5 @A1		Revision	C2	ŀ
BA Project Code 1802	Drawn SBA Checked AA	Date 14/08/20 Suitability Code	project		originator zone level -SBA-XX-ZZ -	51	<sup>umber</sup> 760	