

STEEL COLUMN SCHEDULE

SC1 - 150x150x16.0 SHS (S355)
SC2 - 152x152x37UC
SC3 - 203x203x86 UC
SC4 - 120x80x10 RHS (S355)
SC5 - 200x100x8 RHS (S355)
SC6 - 203x203x46 UC
SC7 - 254x146x43 UB
SC8 - 200x150x10 RHS (S355)
SC9 - 160x80x10 RHS (S355)

STEEL BEAM SCHEDULE

SB1 - 152x152x37 UC	SB11 - 125x65x15 PFC
SB2 - 203x203x46 UC	SB12 - 200x150x10 RHS
SB3 - 203x203x60 UC	SB13 - 200x100x10 RSA
SB4 - 203x203x71 UC	SB14 - 152x89x16 UB
SB5 - 203x203x86 UC	
SB6 - 203x102x23 UB	
SB7 - 203x133x30 UB	
SB8 - 200x90x30 PFC	
SB9 - 150x90x24 PFC	
SB10 - 305x102x33 UB	


TIMBER MEMBER SCHEDULE

Rafter Schedule (C24 at 400crs)
Joist Schedule (C24 at 400crs)
J1 125x50
J2 250x50
J3 150x50
J4 200x50
Fitch Beams (C24 joists+ S235 plate)
FB1 - 2No 225x50 + 220x12

CONCRETE BEAM, COLUMN AND PADSTONE SCHEDULE

CB1 - 600x600 (4no H16 T+B, EF; 4leg H8 links at 250crs)
CB2 - 600x900 (4no H16 T+B, EF; 4leg H8 links at 250crs)
CC1 - 200x800 (4no H16 EF; H8 links at 150crs)
P1 - 450lg x 110wd x 215dp
P2 - 600lg x 110wd x 215dp
P3 - 450lg x 215wd x 215dp

**FOR COSTING
NOT FOR CONSTRUCTION**



All internal faces of ground beams to have 75mm cordeck heaveguard or similar

All exposed RC to be fair faced in accordance with Architects specification

Existing terrace build-up retained below new rear extension

Piles designed by Contractor, assume CFA piles, 12-18m deep. Pile Loads: DL=125kN, LL=25kN (unfactored load/pile)

- Legend**
- Existing structure
 - Existing structure demolished
 - Structure under
 - New brickwork (20N)
 - New blockwork (7N)
 - New steel beam
 - New steel transfer beam
 - Denotes moment connection
 - Sxx* Astrix denotes hot dip galvanised steelwork
 - HB/VB 100x10 steel cross bracing
 - Existing joists
 - New C24 joist at 400crs with 2no layers of 12mm WBP plywood deck glued and screwed to all joists, cross lapped. Refer to joist schedule for sizes
 - 110thk Comflor51+ with H8 bars in every trough (150crs) and A193 mesh in top, 30mm cover to all rebar
 - Reinforced concrete slab
 - RCS1 - H12s at 150 T+B EW
 - RCS2 - A393 mesh T+B
 - GB - Ground bearing on 50mm Gen1 blinding on 150mm well compacted type 1 hardcore

Cellcore requirements
 Under ground beams - 220thk Hx-B 24/32
 Internal face of ground beams and pad foundations - 75thk heaveguard
 Under ground floor extension slab - 225thk Hx-S 7/10

Proposed Basement Floor Plan

Temporary Works
 Contractor to allow for temporary propping to retained existing roof structure while internal load bearing structure removed below. Also allow for restraint at each floor level to existing brick elevations. Undermining of temporary works should be considered during the excavation of basement/foundations

6 Oakhill Avenue
8 Oakhill Avenue

8 Oakhill Avenue
10 Oakhill Avenue