

## Applications

The Cellcore HX S range is designed to protect reinforced concrete floor slabs from the upward forces associated with the effects of ground heave.

Not sure this product is right? [Compare ground heave products](#)

Suitability

Firstly the depth of the Cellcore HX S panel should be determined by the heave potential of the soil, as detailed in table one below:

**Table One:**

Results of Soil Analysis	NHBC Category	Predicted Ground Movement or BRE/NHBC requirement	Depth of Cellcore HX required to achieve 'Equivilant Void'
Plasticity Index	Shrinkage Category	Void Dimension (mm)	HX S (mm)
10-20	Low	50	90
20-40	Medium	100	160
40-60*	High	150	225

**Table two:**

Grade *	Safe Load (kN/m2)	Fail Load (kN/m2)	Maximum Concrete Depth ** (mm)
7/10	7	10	220
9/13	9	13	300
13/18	13	18	460
18/24	18	24	660
24/32	24	32	900



Project name:

elliottwood

engineering  
a better society

Project number:

Sheet:

Revision:

Date:

Engineer:

Checked:

CHECK TOTAL DEAD LOAD OF STRUCTURE TO RESIST TOTAL UPLIFT

$$\text{SELF-WEIGHT OF BASEMENT WALLS} = 25 \times 0.25 \times 3.41 \\ = 21.3 \text{ kN/m}$$

350mm THICK

$$\text{SELF-WEIGHT OF BASEMENT SLAB} = 25 \times 0.35 \\ = 8.75 \text{ kN/m}^2$$

DEAD LOAD FROM COLUMNS SAT ON NEW BASEMENT WALLS (KN)	(FROM TERLA MODEL - SEE COVER)
483	
531	
746	
616	
599	
639	
1241	
1180	
<hr/>	
TOTAL = 6035	

$$\text{TOTAL DEAD LOAD RESISTING UPLIFT (TO BE FACTORED BY 0.9)} = \\ (21.3 \times 40.5 + 8.75 \times 7.4 \times 20.1 + 6035) \times 0.9 = 7379.2 \text{ kN}$$

TOTAL DEAD LOAD ON BASEMENT < UPLIFT

∴ CONTIG PILES TO BE DESIGNED FOR TENSION

$$\text{LOAD FROM UPLIFT PER PILE} = 328.6 \times 0.6 = 197.2$$

$$\text{SKIN FRICTION FROM CLAY UP TO 4m Dp} = 50 \text{ kN/m}^2$$


$$\therefore \text{RESISTANCE OF PILE TO 4m DEEP} = 50 \times (2 \times \pi \times 0.225) \times 4 \\ = 282.7 \text{ kN}$$

RESISTANCE > UPLIFT FORCE ∴ OK

NOTE: HEAVE CAN BE REDUCED BY USING CORDEX CELL CORE  
→ WILL USE IN DETAILED DESIGN OF PILES

SLAB TO BE DESIGNED TO SPAN SIDE TO SIDE TO PILES





This drawing is to be read in conjunction with all relevant architects, engineers and specialists drawings and specifications.

Do not scale from this drawing.

#### LEGEND

	EXISTING STRUCTURE
	NEW REINFORCED CONCRETE
	NEW PRECAST CONCRETE
	NEW REINFORCED WATER RESISTANT CONCRETE
	PADSTONES
	LOAD BEARING STRUCTURE BELOW
	EXISTING STRUCTURE TO BE REMOVED
	NEW STEEL BEAMS
	NEW LINTELS OVER OPENINGS
	MOMENT CONNECTION
	CRANK IN BEAM
	NON-COMPOSITE USED BEAM
	ASSUMED SITE BOUNDARY

#### NOTES

- METAL DECK SLABS TO BE 140mm THK KINGSPAN MULTIDECK 80 V2 WITH 1.0mm GAUGE AND A142 MESH TO TOP + H10 BARS IN EACH TROUGH
- ALL SETTING OUT TBC BY ARCHITECT
- ALL BEAMS ACTING COMPOSITELY WITH SLAB UNLESS NOTED OTHERWISE. ALLOW FOR 15mm, 95mm LONG SEAR STUDS IN EVERY RIB OR MIN 350mm CRS.

#### BRACING SCHEDULE

REF	DESIGNATION
VB1	100x15mm FLAT PLATE VERT CROSS BRACING
VB2	INVERTED V - BRACING FLAT PLATE 100x15mm
VB3	V - BRACING FLAT PLATE 100x15mm

**NOT FOR CONSTRUCTION**

rev	date	by	chk	description
P1	04.03.19	Div	SCe	Issued For Planning

**elliottwood** | engineering a better society

elliottwood Partnership p.l.l.c.  
Central London • Wimbledon • Nottingham  
Consulting Structural and Civil Engineers  
(020) 7499 3688 • [elliottwood.co.uk](mailto:elliottwood.co.uk)

Project  
The Hall School  
NW3

Drawing title  
Proposed Lower Ground Floor  
Plan

Scale (s) Date Drawn  
1:50 (s) A1: 1:100 (s) A3 March / 2019

Drawing status Status Revision  
Preliminary S2 P1

Project no. Originator Zone Level Type Role dng no.  
2190008-EWP-ZZ-B1-DR-S-0900




DESIGN OF SLAB

$$w = 61.2 \text{ - SW OF SLAB}$$

$$= 61.2 - (25 \times 1 \times 0.35)$$

$$= 52.5 \text{ kN/m}$$



$$M = 52.5 \times 7.4^2 / 8 = 359.4 \text{ kNm /m}$$

$$V = 52.5 \times 7.4 / 2 = 194.3 \text{ kN /m}$$

FLEXURE:

$$k = 0.171$$

$$z = 224.1 \text{ mm}$$

$$A_s = 5008.5 \text{ mm}^2 \quad (\text{USE 8 NO. H32s} \dots A_{s\text{prov}} = 6434 \text{ mm}^2)$$

H32s @ 140 o/c



---

8.3 Ground beam and pile cap design



Project name:

HALL SCHOOL

Project number:

21910008

Sheet:

Revision:

Date:

MARCH '19

Engineer:


DOE

Checked:

elliottwood

engineering  
a better society

## BASEMENT COLUMN SUPPORT



MAX. POINT LOAD = 1660 kN [SLS]

2360 kN [ULS]

FOR GROUND BEAM:

$$M_{max} = 2360 \times 1.5 = 3540 \text{ kNm}$$

$$V_{max} = 2360 \text{ kN}$$

Limiting  $\nu$  to  $2 \text{ N/mm}^2$ ,  $A_{req} = 1.18 \times 10^6 \text{ mm}^2$  i.e.  $1000 \times 1200$

SPAN-TO-DEPTH OK BY INSPECTION



USE C32/40, 75mm COVER so  $d = 1100 \text{ mm}$

$$K = 3540 \times 10^6 / (1000 \times 1100^2 \times 32) = 0.09 < 0.168 \checkmark$$

$$Z = 1004 \text{ mm}, A_s = 3540 \times 10^6 / (0.87 \times 500 \times 1004) = 8106 \text{ mm}^2$$

$$\text{e.g. } 11 \text{ No. H32} = 8847 \text{ mm}^2$$



Project name:

HALL SCHOOL

Project number:

21410008

Sheet:

Revision:

Date:

MARCH '14

Engineer:

DDe

Checked:

elliottwood

engineering  
a better society

$$v_{Ed} = 2360 \times 10^3 / (1000 \times 1004) \\ = 2.35 \text{ N/mm}^2$$

$$v_{rel, max} = 3.84 \text{ N/mm}^2 \quad \text{So } \cot \theta = 2.5$$

$$\frac{A_{sreq}}{s} = \frac{2.35 \times 1000}{(0.87 \times 500) \times 2.5} \\ = 2.2 \text{ mm}^2/\text{mm}$$

$$\text{e.g. } 10 \text{ No. H10 LINKS @ } 300 \text{ c/c} = 2.62 \text{ mm}^2/\text{mm}$$

USE 1200 x 1000 RC GROUND BEAM  
WITH 11 No. H32 TOP BARS & 10 No. H10  
LINKS @ 300 C/C

## PILES

GEA SITE INVESTIGATION SUGGESTS WORKING  
LOAD OF 840 kN FOR 21m DEEP 450mm  $\phi$  PILE.

$$1660 / 840 = 2.0$$

TO ALLOW FOR LOAD FROM RC SUBSTRUCTURE,  
PROVIDE 3 No. PILES.

FOR GROUND BEAM ON GRID '3' SUPPORTING SLAB,  
WORST CASE IS UPLIFT.

$$\text{UPLIFT} = 3.7 \text{ m} \times 54 \text{ kN/m}^2 = 200 \text{ kN/m}$$

$$L = 6 \text{ m}, \quad M = 900 \text{ kNm}, \quad V_{max} = 600 \text{ kN}$$

$$\text{SO USE 1200 DEEP BEAM, WIDTH} = \frac{900}{2360} \times 1000 \\ \text{USE WIDTH PROPORTIONAL TO} \\ \text{LOAD DIFFERENCE TO CANTILEVER.} = 381$$

USE 500 WIDE BEAM.



---


8.3 Check on existing basement wall in the proposed case




---

8.4 Check on existing basement wall in the proposed case



EXISTING BASEMENT WALL

THE EXISTING BASEMENT WALL IS TO BE CUT DOWN & THE NEW COLUMNS ARE TO BE SAT ON THE WALL  $\therefore$  THE RETAINING WALL NEEDS TO BE CHECKED IN THE PROPOSED CASE:

EXISTINGNEW

↳ SEE OVER FOR ARCHIVE DRAWING OF EXISTING BASEMENT

EXISTING LOAD:

BAY WIDTH = 3m (FROM ARCHIVE DRAWINGS) SPREAD OVER 3m

DL = 3.05 kN/m<sup>2</sup> (ribdeck)

LL = 0.75 kN/m<sup>2</sup> (access)

Pe DL =  $3.05 \times 1.35 \times 3 \times 11.9 / 2 = 73.5 \text{ kN}$  1/3 = 24.5 kN

LL =  $0.75 \times 1.5 \times 3 \times 11.9 / 2 = 20.1 \text{ kN}$  1/3 = 6.7 kN

LOAD REMOVED IN THE PROPOSED CASE











Project name:

elliottwood

Project number:

Sheet:

Revision:


Date:

Engineer:


Checked:

1) NEIGHBOURING STRUCTURE - 1<sup>ST</sup> LOCATION OF NEIGHBOUR FROM ARCHIVE:

BASED ON ARCHIVE DRAWINGS; FRANK & LEWIN 8559/03 & 06.



FROM SECTION B-B ON 8559/06



FROM 55 ON 8559/03.

SEE ENCLOSED DRAWINGS.



Project name:

elliottwood

Project number:

Sheet:


Revision:

Date:

Engineer:

Checked:

IF WE TAKE EXTERNAL = FFL = 55.9



LOAD FROM GARAGE  
FOUNDATION.

ALLOW DEAD LOAD  
ONLY AS  $10 \text{ kN/m}^2$   
SURCHARGE WILL  
BE INCLUDED IN CALCS.

ROOF ALLOW

$$1 \text{ kN/m}^2 \times \frac{4 \text{ m}}{2} = 2 \text{ kN/m}$$

WALL

$$19 \text{ kN/m}^3 \times 0.275 \times 3 = 12.8 \text{ kN/m}$$

GROUND


ASSUME GROUND BEARING  
SLAB  $\therefore$  NO REQUIREMENT  
AS  $\angle$  SOIL  $\neq$  NOT ON  
FOUNDS

$$\text{TOTAL DL} = 14.8 \text{ kN/m}$$

$$\text{AS PRESSURE} = \frac{14.8}{2.8} = 5.3 \text{ kN/m}^2$$

DL ON WALL =  $5.3 \times 0.42 = 2.2 \text{ kN/m}$   
STARTING  $\approx 2 \text{ m}$  BELOW TOP





ISSUED FOR CONSTRUCTION

FOR SECTION A-A TO D-D  
SEE DRG. NO. 8559/06 & 07.

Refer to Architects drgs.  
for all setting out dimensions

J	ACTIVITIES SHALL BE IN ACCORDANCE WITH THE REVISIONS TO THE SITE ESTABLISHED SITE CONDITIONS.
N	GRADE OF #1016 & A-1 & A-2 TO BE ADJUSTED IN ACCORDANCE WITH ARCHITECT'S REQUIREMENTS.
C	LEVELS EXCHANGED. SIGN BLOCK REVISED TO BUILT GRASSY BANK.
F	STREET PERFORMED ON GRID LINE 1+0.0.
E	AMENDED FOR CONTRACT ISSUE.
D	SEAN BASE DETAIL ADDED MIN. AMENDS.
C	FINISHED ADJACENT ROOF ACTIVATED. DRAINAGE ADJUSTED.
B	REVISED IN ACCORDANCE WITH LATEST ARCHITECT'S AND SERVICES REQUIREMENTS.
A	MINOR REVISIONS ISSUED FOR BUILDING REG. APPROVAL.

Revision	Description															
Date	5-1-87	10-4-87	16-5-87	16-7-87	11-8-87	12-8-87	13-8-87	16-10-87								
Revision	A	B	C	D	E	F	G	H	J	K	L	M	N	P	R	S
Client																
Architect	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
Quantity Surveyor	1	1	1	2	2	3	3	3	3	3	3	3	3	3	3	3
Contractor H.O.				2	2											
E.O.																
M.B.E. Consultant	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
Mech. Engineer																
Elect. (LFB)				1												
Local Authority	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
Project Manager																

Franks and Lewin

21 Bloomsbury Way, London, WC1A 2TH Tel: 01-242 7943

Job  
THE HALL SCHOOL HAMPSTEAD  
EXTENSION PHASE TWO.

Drawing  
THREE STOREY BLOCK & EXTENSION  
LEVEL 1. FOUNDATIONS - G.A.

Architect Michael Haskoll Associates

Scale	1:50 1:20	Drawing Number	Revision
-------	-----------	----------------	----------

Drawn	S.F.A.	8559/03	J
Checked	CA		



Project name:

THE HALL SCHOOL

Project number:

2190008

Sheet:

Revision:

Date:

Feb 19

Engineer:


SCO

Checked:


elliottwood

engineering  
a better society

# NEW CANTILEVER RETAINING WALL



$$\phi = 24^\circ \text{ clay} \therefore k_a = 0.42 \quad (\text{FROM SI})$$




$$10 \times 3.8 = 38 \text{ kN/m}^2$$

$$\gamma \quad (1.2)$$



$$0.42 \times (20 - 10) \times 3.8 = 15.96 \text{ kN/m}^2$$

$$(1.35)$$




$$10 \times 0.42 = 4.2 \text{ kN/m}^2$$

$$(1.5)$$




$$5.3 \times 0.42 = 2.3 \text{ kN/m}^2$$

$\Rightarrow$  SEE TEOOS CACC FOR ANALYSIS





 <b>Tekla</b> <b>Tedds</b> Elliott Wood 46-48 Foley Street London W1W 7TY	Project Hall School				Job no. 2190008	
	Calcs for Existing basement wall - proposed case				Start page no./Revision 1	
	Calcs by SCO	Calcs date 11/03/2019	Checked by	Checked date	Approved by	Approved date

## RC MEMBER ANALYSIS & DESIGN (EN1992-1-1:2004)

In accordance with EN1992-1-1:2004 incorporating Corrigenda January 2008 and the UK national annex

Tedds calculation version 3.0.04

## ANALYSIS

Tedds calculation version 1.0.17

### Geometry

Geometry (m)



### Material - Concrete (C32 2500 Quartzite)

Density	2500 kg/m <sup>3</sup>	Youngs Modulus	33.3457645 kN/mm <sup>2</sup>
Shear Modulus	13.8940685 kN/mm <sup>2</sup>	Thermal Coefficient	0.00001 °C <sup>-1</sup>

### Section type - R 1000x375

Area	3750 cm <sup>2</sup>		
Major moment of inertia	439453 cm <sup>4</sup>	Shear area A <sub>y</sub>	3125 cm <sup>2</sup>
Minor moment of inertia	3125000 cm <sup>4</sup>	Shear area A <sub>z</sub>	3125 cm <sup>2</sup>

### Support conditions

Support 1	X Fixed	Z Fixed	Rotationally Fixed
Support 2	X Free	Z Free	Rotationally Free

### Spans

Span 1	3.4 m
--------	-------

### Loading

Water - Loading



Soil - Loading





Project Hall School				Job no. 2190008	
Calcs for Existing basement wall - proposed case				Start page no./Revision 2	
Calcs by SCO	Calcs date 11/03/2019	Checked by	Checked date	Approved by	Approved date

### Surcharge - Loading



### Neighbour - Loading



### Load combination factors

Load combination	Self Weight	Water	Soil	Surcharge	Neighbour
ULS (Strength)		1.20	1.35	1.50	1.50
SLS (Strength)		1.00	1.00	1.00	1.00

### Member VDL loads

Member	Load case	Type	Position		Load		Orientation
			Start	End	Start (kN/m)	End (kN/m)	
Beam	Water	Ratio	0	1	38	0	GlobalZ
Beam	Soil	Ratio	0	1	15.96	0	GlobalZ
Beam	Surcharge	Ratio	0	1	4.2	4.2	GlobalZ
Beam	Neighbour	Absolute	0 m	0.9 m	2.3	2.3	GlobalZ


### Results

#### Forces

#### Strength combinations - Moment envelope (kNm)




#### Strength combinations - Shear envelope (kN)





LOAD FROM WALL TO BE RE SUPPORTED ON GROUND BEAM  
- CHANGED FROM GROUND BEARING IN THE EXTG CASE



DISTANCE BETWEEN WALL & PILE CAP WILL BE SUCH THAT THE SHEAR DOES NOT EXCEED THE CAPACITY OF THE SCAB. UPON SCANNING TO UNDERSTAND THE REINFORCEMENT THIS CAN BE ASSESSED.

GROUND BEAM TAKES LOAD BACK TO PILES



Project name:

Project number:

Sheet:


Revision:

Date:

Engineer:

Checked:

## EXISTING RETAINING WALL ANALYSIS




$$\text{SOIL} = 20. \text{ kN/m}^3$$

$$\phi = 24$$

$$k_a = 0.42$$

(FROM SI)

$\Rightarrow$  SEE TEDDS CALC



MOMENT & AXIAL LOAD  
GETS TRANSFERRED THROUGH  
THE BASE INTO THE GROUND



Project Hall School				Job no. 2190008	
Calcs for Existing basement wall - existing case				Start page no./Revision 1	
Calcs by SCO	Calcs date 11/03/2019	Checked by	Checked date	Approved by	Approved date

## RC MEMBER ANALYSIS & DESIGN (EN1992-1-1:2004)

In accordance with EN1992-1-1:2004 incorporating Corrigenda January 2008 and the UK national annex

Tedds calculation version 3.0.04

## ANALYSIS

Tedds calculation version 1.0.17

### Geometry

#### Geometry (m)



### Material - Concrete (C32 2500 Quartzite)

Density	2500 kg/m <sup>3</sup>	Youngs Modulus	33.3457645 kN/mm <sup>2</sup>
Shear Modulus	13.8940685 kN/mm <sup>2</sup>	Thermal Coefficient	0.00001 °C <sup>-1</sup>

### Section type - R 1000x375

Area	3750 cm <sup>2</sup>		
Major moment of inertia	439453 cm <sup>4</sup>	Shear area A <sub>y</sub>	3125 cm <sup>2</sup>
Minor moment of inertia	3125000 cm <sup>4</sup>	Shear area A <sub>z</sub>	3125 cm <sup>2</sup>

### Support conditions

Support 1	X Fixed	Z Fixed	Rotationally Fixed
Support 2	X Free	Z Fixed	Rotationally Free

### Spans

Span 1	6.8 m
--------	-------

### Loading

#### Water - Loading




#### Soil - Loading





Project Hall School				Job no. 2190008	
Calcs for Existing basement wall - existing case				Start page no./Revision 2	
Calcs by SCO	Calcs date 11/03/2019	Checked by	Checked date	Approved by	Approved date

### Surcharge - Loading



### Neighbour - Loading



### Load combination factors

Load combination	Self Weight	Water	Soil	Surcharge	Neighbour
ULS (Strength)		1.20	1.35	1.50	1.50
SLS (Strength)		1.00	1.00	1.00	1.00

### Member VDL loads

Member	Load case	Position			Load		Orientation
		Type	Start	End	Start (kN/m)	End (kN/m)	
Beam	Water	Ratio	0	0.5	38	0	GlobalZ
Beam	Soil	Ratio	0	0.5	15.96	0	GlobalZ
Beam	Surcharge	Ratio	0	0.5	4.2	4.2	GlobalZ
Beam	Neighbour	Absolute	0 m	0.9 m	2.3	2.3	GlobalZ

### Results

#### Forces

#### Strength combinations - Moment envelope (kNm)



#### Strength combinations - Shear envelope (kN)





Project name:

Project number:

Sheet:

Revision:


Date:

Engineer:

Checked:

## COMPARISON BETWEEN EXTG & PROPOSED

EXTG



SLAB WILL BE SCANNED TO ASSESS IF IT HAS ADEQUATE REINFORCEMENT TO TAKE INCREASED MOMENT. ASSUME IT HAS.

REINFORCEMENT REQUIRED =  $2106 \text{ mm}^2/\text{m}$   
FOR EXAMPLE H 20s @ 125 c/c



**Wimbledon**

241 The Broadway  
London  
SW19 1SD

tel. (020) 8544 0033  
fax. (020) 8544 0066

**Central London**

46-48 Foley Street  
London  
W1W 7TY

tel. (020) 7499 5888  
fax. (020) 7499 5444


**Nottingham**

1 Sampsons Yard  
Halifax Place  
Nottingham  
NG1 1QN

tel. 0870 460 0061  
fax. 0870 460 0062

email: [info@elliottwood.co.uk](mailto:info@elliottwood.co.uk)  
[www.elliottwood.co.uk](http://www.elliottwood.co.uk)

Elliott Wood Partnership Ltd  
Structural and Civil Engineers



INVESTOR IN PEOPLE



E

Movement Monitoring Report



---

The Hall School  
23 Crossfield Road  
Hampstead  
NW3 4NU

---

## Movement Monitoring Report

---

Job  
number: 2190008  
Revision: P1  
Status: Preliminary  
Date: March 2019



Document Control

---

		remarks:	Secant Piled Wall Added				
revision:	P1	prepared by:	Suzanna Cooper	checked by:	Agata Downey	approved by:	James Souter
date:	4 <sup>th</sup> March 2019	signature:		signature:		signature:	



---

## Contents

---

1.0	Introduction	page	4
2.0	General	page	4
3.0	Monitoring of Perimeter Wall Structures	page	4
4.0	Trigger Levels	page	6



## 1.0 Introduction

- 1.1 Elliott Wood Partnership Ltd has been appointed to act as structural and civil engineers for the proposed redevelopment of the Hall School site, further details of which can be found in the 'Structural and Civil Engineering Planning Report and Basement Impact Assessment'. This report sets out the proposed movement monitoring regime to be carried out during the works. It will be updated to incorporate any specific requirements or trigger level limits agreed under the Party Wall Awards.

## 2. General

- 2.1. The contractor shall be responsible for establishing and setting out all levels and data in order to coordinate any work with the future proposed constructions.
- 2.2. The integrity of the excavation is to be maintained by the contractor at all times.
- 2.3. The contractor shall take all necessary precautions to ensure that noise, dust and vibration as a result of the works are kept to a minimum.

## 3. Monitoring of Perimeter Wall Structures

- 3.1. The contractor is to identify all buried services provide a schedule of conditions of all adjacent properties with photographs agreed with the CA and relevant wall surveyors prior to works commencing.
- 3.2. Any cracks to the fabric of the adjacent structures of perimeter retained walls are to have graduated tell tales applied prior to commencement of all demolition works, or as they are uncovered, subject to the contractor gaining approval from the respective party wall surveyors.
- 3.3. In accordance with the Burland Category of Damage, the category of damage shall not exceed "1 - Very Slight". This limits crack width to 1mm and tensile strain to 0.05-0.075.
- 3.4. The perimeter walls shall be monitored regularly for signs of movement via the following methods.
- 3.4.1. Visual inspection
  - 3.4.2. Accurate survey techniques
  - 3.4.3. Graduated tell tales



Movement Monitoring Report

---

- 3.5. Movement shall be measured with the use of prism reflector targets allowing measurement of movement in all three directions using an electronic distance measuring instrument (EDM). Location of monitoring targets shall be agreed prior to commencing works and shall be recorded on survey drawings and results tabulated and presented graphically and submitted to the CA on a weekly basis.
- 3.6. During demolition, excavation and basement works, visual monitoring should be carried out daily in conjunction with measured monitoring in the morning and evening. Once basement works have been completed, measured monitoring to be carried out weekly whilst daily visual monitoring should be maintained.
- 3.7. Monitoring of movement shall have a minimum accuracy of  $\pm 1\text{mm}$ . Monitoring cracks shall have a minimum accuracy of  $\pm 0.2\text{mm}$ .
- 3.8. Exact monitoring positions to be agreed with the contractor/surveyor to permit a line of sight. 3-D monitoring to be undertaken weekly by an independent survey company during the main demolition and construction works until the demolition and basement works are complete. Following this, monitoring should continue on a monthly basis. During the defects/liability period, two measurements should be taken at least six months apart.



#### 4. Trigger Levels

- 4.1. Monitoring to be undertaken for a suitable period prior to main excavation works commencing to enable base movement due to daily thermal effects to be established.
- 4.2. Readings should be taken at the same time each day to minimise the effects of temperature fluctuations.
- 4.3. Frequency of monitoring to be in accordance with CIRIA Guide C579.
- 4.4. Lateral or vertical movements and deflections of the perimeter retained party walls and adjacent structures above those due to thermal effects will be monitored based on a traffic light system to be proposed by the contractor based on the following trigger points (to be agreed with party wall surveyor):

Adjacent to Contiguous Piled Wall			
LEVEL	ALLOWABLE HORIZONTAL MOVEMENT	ALLOWABLE VERTICAL MOVEMENT	ACTIONS TO BE TAKEN
Green	Up to 13mm	Up to 7mm	Site works and frequency of monitoring can proceed as normal.
Amber	Exceeding 13mm but less than 18mm	Exceeding 7mm but less than 12mm	Monitoring frequency is increased and a meeting is to be convened to review working procedure and assumptions.
Red	Exceeding 18mm	Exceeding 12mm	All work to be immediately ceased and a meeting is to be convened to identify reasons for the exceedance of the limit and to discuss remedial actions that may be required.



**Wimbledon**

241 The Broadway  
London  
SW19 1SD

tel. (020) 8544 0033  
fax. (020) 8544 0066

**Central London**

46-48 Foley Street  
London  
W1W 7TY

tel. (020) 7499 5888  
fax. (020) 7499 5444

**Nottingham**

1 Sampsons Yard  
Halifax Place  
Nottingham  
NG1 1QN

tel. 0870 460 0061  
fax. 0870 460 0062

email: [info@elliottwood.co.uk](mailto:info@elliottwood.co.uk)  
[www.elliottwood.co.uk](http://www.elliottwood.co.uk)

Elliott Wood Partnership Ltd  
Structural and Civil Engineers



**INVESTOR IN PEOPLE**





# elliottwood

engineering  
a better **society**

## **London**

46 – 48 Foley St  
W1W 7TY  
+44 207 499 5888

## **Wimbledon**

241 The Broadway  
London  
SW19 1SD  
+44 208 544 0033

## **Nottingham**

1 Sampsons Yard  
Halifax Place  
Nottingham  
NG1 1QN  
+44 870 460 0061

[www.elliottwood.co.uk](http://www.elliottwood.co.uk)