



### **Document History and Status**

Revision	Date	Purpose/Status	File Ref	Author	Check	Review
D1	May 2018	Comment	RMam12727- 70-080518-23 West Heath Road-D1.doc	AM	RM	RM
F1	July 2018	Comment	RMam-12727- 70-020718-23 West Heath Road-F1.doc	AM	RM	RM

This document has been prepared in accordance with the scope of Campbell Reith Hill LLP's (CampbellReith) appointment with its client and is subject to the terms of the appointment. It is addressed to and for the sole use and reliance of CampbellReith's client. CampbellReith accepts no liability for any use of this document other than by its client and only for the purposes, stated in the document, for which it was prepared and provided. No person other than the client may copy (in whole or in part) use or rely on the contents of this document, without the prior written permission of Campbell Reith Hill LLP. Any advice, opinions, or recommendations within this document should be read and relied upon only in the context of the document as a whole. The contents of this document are not to be construed as providing legal, business or tax advice or opinion.

### © Campbell Reith Hill LLP 2015

#### **Document Details**

Last saved	02/07/2018 14:44
Path	RMam-12727-70-020718-23 West Heath Road-F1.doc
Author	A Morcos, MSc CEng MICE
Project Partner	E M Brown, BSc MSc CGeol FGS
Project Number	12727-70
Project Name	23 West Heath Road, London, NW3 7UU
Planning Reference	2018/0853/P and 2018/1114/L

Structural ◆ Civil ◆ Environmental ◆ Geotechnical ◆ Transportation

Date: July 2018

i



### Contents

1.0	Non-technical summary	. 1
2.0	Introduction	. 3
3.0	Basement Impact Assessment Audit Check List	. 5
4.0	Discussion	. 8
5.0	Conclusions	. 11

## Appendix

Appendix 1: Residents' Consultation Comments

Appendix 2: Audit Query Tracker Appendix 3: Supplementary Supporting Documents

Date: July 2018



#### 1.0 NON-TECHNICAL SUMMARY

- 1.1. CampbellReith was instructed by London Borough of Camden, (LBC) to carry out an audit on the Basement Impact Assessment submitted as part of the Planning Submission documentation for 23 West Heath Road, London, NW3 7UU (planning reference 2018/0853/P and 2018/1114/L). The basement is considered to fall within Category C as defined by the Terms of Reference.
- 1.2. The Audit reviewed the Basement Impact Assessment for potential impact on land stability and local ground and surface water conditions arising from basement development in accordance with LBC's policies and technical procedures.
- 1.3. CampbellReith was able to access LBC's Planning Portal and gain access to the latest revision of submitted documentation and reviewed it against an agreed audit check list.
- 1.4. The BIA and the Structural Engineering Method Statement have been carried out by well established firms of engineering consultants using individuals who possess suitable qualifications.
- 1.5. The basement proposal involves Grade II listed building namely Sarum Chase and it sits within the Redington and Frognal Conservation Area.
- 1.6. An appropriate site specific SI has been carried out.
- 1.7. The proposed basement will be founded partly within Bagshot Formation and Claygate Member.
- 1.8. It is accepted that the excavation level is unlikely to be below groundwater level or impact on groundwater flows.
- 1.9. The proposed development consists of the excavation of a new basement beneath the entire footprint of the existing garage located at the eastern side of the property, under a part of the main Sarum Chase house and a subterranean extension beneath the rear with a new light-well.
- 1.10. An appropriate construction methodology has been proposed which indicates the basement is to be constructed in accordance with good practise construction principles using common techniques.
- 1.11. Category 1 damage is predicted to the neighbouring properties and Serum Chase, which is within the limits of the maximum permitted category allowed by LBC.
- 1.12. The Ground Movement Monitoring has been recommended to the surrounding properties during construction with set limits to the vertical and horizontal movements.



- 1.13. A Construction Management Plan (CMP) has been provided.
- 1.14. It is accepted that the impermeable area is not changing.
- 1.15. It is accepted that nearby rail assets are outside of the zone of influence of the proposed site.
- 1.16. It is accepted that the surrounding slopes to the development site are stable.
- 1.17. It is accepted that the development will not impact on the wider hydrogeology of the area and is not in an area subject to flooding.
- 1.18. It can be confirmed that the proposal adheres to the requirements of CPG Basements.



#### 2.0 INTRODUCTION

- 2.1. CampbellReith was instructed by London Borough of Camden (LBC) on 18/04/2018 to carry out a Category C Audit on the Basement Impact Assessment (BIA) submitted as part of the Planning Submission documentation for 23 West Heath Road, London, NW3 7UU.
- 2.2. The Audit was carried out in accordance with the Terms of Reference set by LBC. It reviewed the Basement Impact Assessment for potential impact on land stability and local ground and surface water conditions arising from basement development.
- 2.3. A BIA is required for all planning applications with basements in Camden in general accordance with policies and technical procedures contained within
  - Guidance for Subterranean Development (GSD). Issue 01. November 2010. Ove Arup & Partners.
  - Camden Planning Guidance Basements: Basements.
  - Camden Development Policy (DP) 27: Basements and Lightwells.
  - Camden Development Policy (DP) 23: Water.
  - Local Plan Policy A5 Basements.
- 2.4. The BIA should demonstrate that schemes:
  - a) maintain the structural stability of the building and neighbouring properties;
  - avoid adversely affecting drainage and run off or causing other damage to the water environment;
  - avoid cumulative impacts upon structural stability or the water environment in the local area, and;

evaluate the impacts of the proposed basement considering the issues of hydrology, hydrogeology and land stability via the process described by the GSD and to make recommendations for the detailed design.

Status: F1

2.5. LBC's Audit Instruction described the planning proposal as "Excavation of a new basement beneath the existing garage/plant rooms in order to provide additional ancillary staff quarters and utility space; and partial excavation beneath the main house in order to provide access. With a subterranean extension beneath the rear garden in order to create a games room, with installation of a light-well with metal grille to the rear."

The Audit Instruction also confirmed 23 West Heath Road involved listed buildings.

Date: July 2018



- 2.6. CampbellReith accessed LBC's Planning Portal and gained access to the following relevant documents for audit purposes:
  - Design & Access Statement
  - JCH000056 Sarum Chase, Heritage Statement CgMs
  - 191-000 Block Plan
  - 191-001 OS Location Plan
  - 191-011-Existing Plans
  - 191-021-Existing Elevations
  - 191-031-Existing Section AA & BB
  - 191-032-Existing Section CC & DD
  - 191-101-Proposed Basement
  - 191-102-Proposed Lower Ground Floor
  - 191-103-Proposed Raised Ground Floor
  - 191-201-Proposed Elevations
  - 191-301-Proposed Section AA & BB
  - 191-302-Proposed Section CC & DD
  - TGC\_SCH\_AIA\_01 Arboricultural Impact Assessment Report
  - Sarum Chase\_CMS
  - CMS APPENDIX A 171026 760-SK-S-008TO 017 STRUCTURAL SCHEME
  - CMS APPENDIX B 3849 J16233 Ground Investigation, Basement Impact Assessment & Ground Movement Assessment Report

Status: F1

2.7. Follow the D1 issue of this audit the following information was reviewed from the applicant;

Date: July 2018

• Outline Project Calculation Documentation for Planning – engenuiti, 20 June 2018



5

### 3.0 BASEMENT IMPACT ASSESSMENT AUDIT CHECK LIST

Item	Yes/No/NA	Comment
Are BIA Author(s) credentials satisfactory?	Yes	
Is data required by CI.233 of the GSD presented?	Yes	
Does the description of the proposed development include all aspects of temporary and permanent works which might impact upon geology, hydrogeology and hydrology?	Yes	
Are suitable plan/maps included	Yes	
Do the plans/maps show the whole of the relevant area of study and do they show it in sufficient detail?	Yes	
Land Stability Screening: Have appropriate data sources been consulted? Is justification provided for 'No' answers?	Yes	
Hydrogeology Screening: Have appropriate data sources been consulted? Is justification provided for 'No' answers?	Yes	
Hydrology Screening: Have appropriate data sources been consulted? Is justification provided for 'No' answers?	Yes	
Is a conceptual model presented?	Yes	
Land Stability Scoping Provided? Is scoping consistent with screening outcome?	Yes	
Hydrogeology Scoping Provided? Is scoping consistent with screening outcome?	Yes	



Item	Yes/No/NA	Comment
Hydrology Scoping Provided? Is scoping consistent with screening outcome?	No	No potential issues to be assessed.
Is factual ground investigation data provided?	Yes	
Is monitoring data presented?	Yes	
Is the ground investigation informed by a desk study?	Yes	
Has a site walkover been undertaken?	Yes	
Is the presence/absence of adjacent or nearby basements confirmed?	Yes	
Is a geotechnical interpretation presented?	Yes	
Does the geotechnical interpretation include information on retaining wall design?	Yes	
Are reports on other investigations required by screening and scoping presented?		
Are the baseline conditions described, based on the GSD?	Yes	
Do the base line conditions consider adjacent or nearby basements?	Yes	
Is an Impact Assessment provided?	Yes	
Are estimates of ground movement and structural impact presented?	Yes	
Is the Impact Assessment appropriate to the matters identified by screen and scoping?	Yes	
Has the need for mitigation been considered and are appropriate mitigation methods incorporated in the scheme?	Yes	

RMam-12727-70-020718-23 West Heath Road-F1.doc Date: July 2018 Status: F1 6



Item	Yes/No/NA	Comment
Has the need for monitoring during construction been considered?	Yes	
Have the residual (after mitigation) impacts been clearly identified?	Yes	
Has the scheme demonstrated that the structural stability of the building and neighbouring properties and infrastructure will be maintained?	Yes	
Has the scheme avoided adversely affecting drainage and run-off or causing other damage to the water environment?	Yes	
Has the scheme avoided cumulative impacts upon structural stability or the water environment in the local area?	Yes	
Does report state that damage to surrounding buildings will be no worse than Burland Category 1?	Yes	Mitigation measures reduced Damage Category 2 to 1 by introducing props during excavation.
Are non-technical summaries provided?	Yes	

RMam-12727-70-020718-23 West Heath Road-F1.doc Date: July 2018 Status: F1 7



#### 4.0 DISCUSSION

- 4.1. The Basement Impact Assessment (BIA) has been carried out by an established firm of engineering consultants, Geotechnical & Environmental Associates Limited (GEA) and the individuals concerned in its production have suitable qualifications.
- 4.2. The Structural Engineering Method Statement has similarly been carried out by an established firm of engineering consultants, Engenuity. The author and reviewer are both chartered structural engineers.
- 4.3. The LBC Instruction to proceed with the audit identified that the basement proposal involves Grade II listed building namely Sarum Chase. It sits within the Redington and Frognal Conservation Area.
- 4.4. The BIA submissions include land Stability, Hydrogeology and Hydrology screening and scoping, relevant site investigations and impact assessment as defined and required in the LBC `Camden Planning Guidance Basements`.
- 4.5. The ground is sloping across the site, with a ground level of approximately 115.2m AOD at the rear of the property, and 111.1m AOD at the front.
- 4.6. The proposed development consists of the excavation of a new basement beneath the entire footprint of the existing garage to the depth of 3.0m to 4.0m bgl located at the eastern side of the property, and under a part of the main Sarum Chase house. A subterranean extension beneath the rear garden is also proposed to the depth of 5.0m bgl at the southern side of the property with a new light-well.
- 4.7. A site specific ground investigation was conducted by GEA in November 2016 and consists of two single cable percussion bore holes to the depth of 15 and 18m bgl, a single drive-in window sampler borehole to the depth of 5m, and three hand excavated trial pits to a maximum depth of 1.1m.
- 4.8. To the rear of the property the investigation has encountered 300mm of soft landscaping, then 2.5m (112.73 m OD) thick layer of Made Ground of orange-brown fine sand with clay partitions, overlaying 3.5m thick layer of dense orange-brown medium to fine grained sand with partings of greyish orange-brown clay indicating the Bagshot Formation. Variable Claygate Formation has been identified underneath and up to the depth of the borehole at 15.0 m (100.23 m OD). The 400mm thick layer of cobbled driveway and concrete screed to the front of the property is located directly over Bagshot Formation overlaying Claygate Formation to the depth of the bore hole at 18m (93.72m OD).
- 4.9. Groundwater was encountered at 13.0 m bgl (98.72 m OD) during drilling in Borehole No 1 to the front of the property. Three monitoring standpipes were installed on the 5<sup>th</sup> December 2016, to depths of between 5.10 m and 6.35 m and one return monitoring has been carried out over



the winter period. The return visit on the 19<sup>th</sup> December 2016 has found them to be dry. The report suggests that groundwater will not be encountered within the basement excavations, however despite this it is suggested the contractor needs to ensure he has an adequate strategy to deal with ground water should it be identified during construction.

- 4.10. Considering the ground condition, the formation level of the proposed rear basement is within the Bagshot Formation, whilst formation level of the basement beneath the eastern part of the house is within the Claygate Member.
- 4.11. CFA piled secant retaining walls with a capping beam is proposed to form three sides of the rear garden basement games room with the existing property forming the fourth side. Lining wall to the inner face of the basement is proposed with 450mm thick slab on heave protection is proposed with 450mm thick RC slab over the basement. Approx. 1m thick layer of soil is proposed to cover the box. The basement walls under the existing garage are proposed to be formed by series of 1.5m wide underpinning sections and similar slab construction at the base to the rest of the extension.
- 4.12. The Construction Management Statement (CMS) proposes sequential works to the basement construction taking into account propping works to the rear garden secant piled wall excavation. Slab supports and propping is proposed throughout all the process of underpinning of the existing garage foundation.
- 4.13. The interpretive report has shown net allowable bearing pressure of 150 kN/m2 in the medium dense silty sand of the Bagshot Formation and 125kN/m2 in the variable clay, silt and sands of the Claygate Member. In order to mitigate the effects of differential settlement it is recommended that suitable reinforcement is installed.
- 4.14. A site walkover survey confirmed there are no existing basements to the neighbouring properties.
- 4.15. A Ground Movement Analysis has been carried out by GEA which follows the method as described in CIRIA 760 for vertical and horizontal ground movements. The predicted movement have been calculated due to excavation and construction of the basement, with an estimated damage category to all internal and external walls to Sarum Chase and neighbouring properties (21A and 21B West Heath Road) be in general no higher than Category 1 ("very slight") and 0 ("very slight") on the Burland Scale. One wall to Sarum Chase is shown to be resulting in Category 2 ("slight") damage, and further assessment has shown that if total vertical movements can be restricted to 13 mm behind the piled wall then the unacceptable damage category is reduced to 1 (Very Slight). It is accepted that movements can likely be restricted given good workmanship and suitably applied designed temporary works, given the employment of a suitably experienced basement contractor. Whilst the CIRIA approach is

Date: July 2018



intended for embedded retaining walls, we accept that the predicted ground movements are within the range typically anticipated for underpinning techniques carried out with good control of workmanship.

- 4.16. The Ground Movement Monitoring during construction has been recommended to the Sarum Chase house and to the surrounding properties to ensure the predicted movements restricted to 13 mm (Vertical) and 6 mm (horizontal) are aligned with the analysis and that the propping scheme is working effectively.
- 4.17. The development is proposed beneath the existing garage at the eastern side of the property and the rear garden extension will be covered with 1m of soil to allow for natural filtration of water over the basement soffit slab. It is therefore accepted that the impact on surface water drainage is likely to be minimal.
- 4.18. Outline structural calculations for the basement retaining walls have not been provided to demonstrate feasibility of the proposed structural form of the basement.
- 4.19. A Construction Management Plan (CMP) has been provided with an outline works construction programme covering key phases of work.
- 4.20. The proposed basement construction is not adjacent to any public highway and there are no London Underground or Network Rail Tunnels within 250 m of the site.
- 4.21. A hillside setting ranging from 7° to 10° has been observed to the south of the site, however it is accepted that the development will not affect the slope stability.
- 4.22. The site is located within 50 m of the catchment area of the Golders Hill Pond and the site is underlain by Bagshot Formation sands considered as a Secondary 'A' Aquifer, however it is accepted that the proposed development will not have any effect on groundwater flow and is not in an area prone to flooding.
- 4.23. It can be confirmed that the proposal satisfies the requirements of CPG Basements. A number of now closed queries have been summarised in Appendix 2.

Date: July 2018



#### 5.0 CONCLUSIONS

- 5.1. The BIA and the Structural Engineering Method Statement have been carried out by well established firms of engineering consultants using individuals who possess suitable qualifications.
- 5.2. The basement proposal involves Grade II listed building namely Sarum Chase and it sits within the Redington and Frognal Conservation Area.
- 5.3. The BIA submissions include land Stability, Hydrogeology and Hydrology screening and scoping, relevant site investigations and impact assessment as defined and required in the LBC Planning Guidance document 'CPG Basements'.
- 5.4. An appropriate site specific SI has been carried out consisting of three boreholes and three trial pits.
- 5.5. The proposed development consists of the excavation of a new basement beneath the entire footprint of the existing garage located at the eastern side of the property, under a part of the main Sarum Chase house and a subterranean extension beneath the rear with a new light-well.
- 5.6. The site investigation has identified a moderate depth of Made Ground overlaying shallow depth of Bagshot Formation and variable layer of Claygate Formation to be the lowest strata. The proposed basement therefore will be founded partly within Bagshot Formation and Claygate Member. An appropriate reinforcement will be installed to mitigate effects of differential settlement.
- 5.7. Groundwater was encountered at the depth of the bore hole No. 1 to the front of the property and the return monitoring of three standpipes has confirmed them to be dry. The findings suggest that groundwater will not be encountered within the basement excavations, however it is suggested the contractor needs to ensure he has an adequate strategy to deal with ground water should it be identified during construction.
- 5.8. Secant piled retaining walls is proposed to form three sides for the subterranean basement attached to the existing property with linning wall, capping beam and RC slab at the top and bottom of the box. The basement under the garage is proposed to be built in the sequence of underpinning to the existing garage foundations with ground bearing blab.
- 5.9. System of propping has been proposed during the underpinning works to the garage and to the excavation of the secant piled wall of the rear garden.
- 5.10. Heave protection is proposed by way of compressible material beneath the basement slab.



- 5.11. 4.1m level difference between front and back of the property has been noted and the hillside setting is ranging between 7 and 10°, however it is accepted that the development will not impact on the stability of the hillside and the surrounding slopes to the development site are stable.
- 5.12. It is stated that the impermeable area is not changing. It is accepted that the impact on surface water drainage is likely to be minimal, as the development on the eastern side of the property is within the footprints of the existing garage and the back garden basement will be covered with 1m of soil, which will allow for natural filtration of water over the basement soffit slab.
- 5.13. The predicted movement have been calculated due to excavation and construction of the basement, with an estimated damage category to the Sarum Chase and neighbouring properties be no higher than Category 1 ('very slight') and 0 ("very slight") on the Burland Scale. Adequate propping to the retining wall and vertical movement monitoring has been proposed to limit damage Category from 2 ("slight") to 1 for one of the Serum Chase walls. This mitigation method is acceptable, however good level of workmanship and adequate temporary propping needs to be ensured for this proposal.
- 5.14. The Ground Movement Monitoring has been recommended to the surrounding properties during construction with set limits to the vertical and horizontal movements.
- 5.15. It is accepted that nearby rail assets are outside of the zone of influence of the proposed site.
- 5.16. A Construction Management Plan (CMP) has been provided with an outline works construction programme covering key phases of work.
- 5.17. The site is located within 50 m of the catchment area of the Golders Hill Pond, however it is accepted that the development will not impact on the wider hydrogeology of the area and is not in an area subject to flooding.
- 5.18. Outline structural calculations for the basement retaining walls have been provided.
- 5.19. It can be confirmed that the proposal conforms to the requirements of CPG Basements. A number of now closed queries have been summarised in Appendix 2.

Date: July 2018



Appendix 1: Residents' Consultation Comments

RMam-12727-70-020718-23 West Heath Road-F1.doc Date: July 2018 Status: F1 Appendices



### Residents' Consultation Comments

Surname	Address	Date	Issue raised	Response
Not available	21,21A,21B West Heath Road	unspecified	Stability of excavations, damage to neighbouring property due to excavation.	A Ground Movement Analysis (GMA) has been carried out for neighbouring properties and the estimated damage category is estimated to be no higher than Category 1 ('very slight') on the Burland Scale.  Also a construction monitoring scheme is proposed to be carried out throughout the construction stage to demonstrate that movements are within those predicted in the GMA.



Appendix 2: Audit Query Tracker

RMam-12727-70-020718-23 West Heath Road-F1.doc Date: July 2018 Status: F1 Appendices



## **Audit Query Tracker**

Query No	Subject	Query	Status	Date closed out
1	Stability	Outline structural calculations for retaining walls to be submitted to demonstrate feasibility of the proposed structure.	Closed	02/07/18
2	Stability	The applicant's own property of 23 West Heath Road is to be monitored in accordance with the movement monitoring strategy during the basement construction works, given the listed status of the property.	To be secured via a planning condition	N/A



Appendix 3: Supplementary Supporting Documents

None

RMam-12727-70-020718-23 West Heath Road-F1.doc Date: July 2018 Status: F1 Appendices

## Birmingham London Friars Bridge Court Chantry House 41- 45 Blackfriars Road High Street, Coleshill London, SE1 8NZ Birmingham B46 3BP T: +44 (0)20 7340 1700 T: +44 (0)1675 467 484 E: london@campbellreith.com E: birmingham@campbellreith.com Manchester Surrey No. 1 Marsden Street Raven House 29 Linkfield Lane, Redhill Manchester Surrey RH1 1SS M2 1HW T: +44 (0)1737 784 500 T: +44 (0)161 819 3060 E: manchester@campbellreith.com E: surrey@campbellreith.com **Bristol** UAE Office 705, Warsan Building Hessa Street (East) Wessex House Pixash Lane, Keynsham PO Box 28064, Dubai, UAE Bristol BS31 1TP T: +44 (0)117 916 1066 E: bristol@campbellreith.com T: +971 4 453 4735 E: uae@campbellreith.com Campbell Reith Hill LLP. Registered in England & Wales. Limited Liability Partnership No OC300082 A list of Members is available at our Registered Office at: Friars Bridge Court, 41- 45 Blackfriars Road, London SE1 8NZ VAT No 974 8892 43