

EXISTING GRANITE COBBLE DRAINAGE CHANNEL
 IN-SITU CONCRETE ACCESS ROAD TO ADJOIN EXISTING. TO BE MADE GOOD AND REPLACED WHERE NECESSARY FOLLOWING WORKS
 EXISTING TREES IN CIRCULAR TREE PITS TO BE RETAINED
 EXISTING GRANITE COBBLE DRAINAGE CHANNEL

EXISTING MAN HOLE TO BE RETAINED

STEPS DOWN TO BE RETAINED

EXISTING FLAG PAVING TO BE RETAINED AND MADE GOOD WHERE NECESSARY FOLLOWING REMOVAL OF COMPOUNDS

EXISTING GRANITE COBBLED PAVING TO BE RETAINED

EXISTING MAN HOLE TO BE RETAINED

TREE PIT TO BE INCREASED IN SIZE WITH TREE PIT EDGING MATERIALS TO BE REMOVED AND REPLACED

NEW RAMP WITH GRANITE KERBS AND RE-USED GRANITE COBBLES TO MATCH EXISTING AND METAL RAILINGS ALONG ROADSIDE

NEW PLANTING BEYOND APPLICATION LINE REQUIRED TO TIE IN WITH PROPOSALS

EXISTING MAN HOLES TO BE RETAINED

GRANITE COBBLES REQUIRED BEYOND APPLICATION LINE TO MAKE GOOD AND TIE IN WITH PROPOSALS

RE-USED GRANITE COBBLES AND SUPPLEMENTED IF REQUIRED

Plant Schedule

Species Name	Height	Pot Size	Specification	Density	No.
<i>Aucuba japonica</i> 'Variegata'	80-100cm	3L	Bushy .C	4/m ²	14 No.
<i>Camellia williamsii</i>	80-100cm	3L	Bushy .C	4/m ²	14 No.
<i>Choysya 'Aztec Pearl'</i>	80-100cm	3L	Bushy .C	4/m ²	14 No.
<i>Coloneaster 'Coral Beauty'</i>	80-100cm	3L	Branched .C	3/m ²	9 No.
<i>Forsythia ovata</i>	80-100cm	10L	Branched .C	3/m ²	9 No.
<i>Hamamelis intermedia</i> 'Allgold'	80-100cm	3L	Branched 3 brks. .C	Counted	3 No.
<i>Hebe 'Nicola's Blush'</i>	80-100cm	5L	Bushy .C	3/m ²	9 No.
<i>Hypericum 'Hidcote'</i>	80-100cm	3L	Bushy .C	4/m ²	16 No.
<i>Ligustrum ovalifolium</i>	80-100cm	10L	Bushy .C	Planted and maintained as hedge	30m
<i>Skimmia japonica</i> 'Fructo Alba'	80-100cm	3L	Bushy .C	4/m ²	16 No.

Climbers

Species Name	Height	Pot Size	Specification	Density	No.
<i>Hedera 'Erecta'</i>	30-40cm	5.5L	Several Shoots .Caned	Counted	1 No.

Herbaceous

Species Name	Height	Pot Size	Specification	Density	No.
<i>Echinacea pallida</i>	3L	Full Pot		4/m ²	17 No.
<i>Geranium phaeum</i> 'Lily Lovell'	3L	Full Pot		5/m ²	17 No.
<i>Verbena bonariensis</i>	3L	Full Pot		3/m ²	6 No.
<i>Viola odorata</i>	3L	Full Pot		Full Pots/m ²	17 No.

Bulbs

Species Name	Specification	Density	No.
<i>Allium caeruleum</i>	plant in groups of 3-5	5/m ²	9 No.

Ferns

Species Name	Height	Pot Size	Specification	Density	No.
<i>Adiantum pedatum</i>	Full Pot	5m ²		17	No.
<i>Asplenium scolopendrium</i>	Full Pot	5m ²		17	No.

Soft Landscape Legend

- Existing trees to be removed
- Existing trees to be retained and protected during construction
- Proposed shrub planting to receive 75mm bark mulch after planting operations
- Proposed mixed herbaceous planting to be planted in groups of 3-5 no. of each specie, and as above
- Proposed specimen shrubs
- Proposed *Buxus* (box) hedge planting to be planted in a single row at 300mm centres. To be maintained at 0.5m height
- Proposed hedge planting to be planted in a double staggered row 300mm apart and at 500mm centres in each row. To be maintained at 1.5m height
- Proposed site boundary

SPECIFICATION
 All works generally, to comply with the written Soft Landscape Specification.
 NOTE: DO NOT SCALE FROM DRAWING

Rev	Date	Details	Drawn
D	21.09.17	Client comments	CB
C	16.08.17	Client comments	CB
B	01.04.16	Client comments	JS
A	26.02.16	VE updates	JS



Ecology
 Archaeology
 Arboriculture
 Landscape Architecture

ACD at these offices:
 Rodbourne Rail Business Centre, Grange Lane,
 Malmesbury, SN16 0ES
 Tel: 01666 825646

Courtyard House, Mill Lane, Godalming, GU7 1EY
 Tel: 01483 425714

Suite 6, Crescent House, Yonge Close, Eastleigh, SO50 9SX
 Tel: 02382 026 300
 email: mail@acdenv.co.uk
 www.acdenvironmental.co.uk

Lovell Partnerships Limited

scheme: Regent's Park Estates
 Cape of Good Hope
 client: Lovell Partnerships Ltd
 drawing: Soft Landscape Proposals
 date: October 2015
 scale: 1:100@A1
 drawing no: LOV20037-11D
 drawn: JS checked: JNT

Copyright of ACD Environmental Ltd. All rights described in Chapter IV of the Copyright, Designs and Patents Act 1988 have been generally asserted. 2011. Copyright of this plan remains with ACD until all fees have been paid in full.