

Manhole Schedule - Surface Water									
MH Ref	MH Type	MH Internal Diameter (mm)	Cover Type	Cover Level (m)	Invert Level (m)	Outgoing Pipe Size (mm)	Depth to Outgoing Pipe Invert (m)	Depth to Outgoing Pipe Soffit (m)	Comments
EX01	2		D400	29.150	26.700	225	2.450	2.225	REBUILD EXISTING MANHOLE DUE TO POOR CONDITION. TWO 100Ø INCOMING PIPES REQUIRE DE-SILTING. EXISTING INTERCEPTOR TO BE REMOVED WHEN REBUILDING.
CMH01	PPIC	600	D400	30.200	27.950	225	2.250	2.025	
CMH02	PPIC	600	D400	30.200	27.817	225	2.383	2.158	
CMH03	PPIC	600	D400	30.000	26.752	225	3.248	3.023	
HR FW 01	PPIC	450	D400	30.120	28.175	150	1.945	1.795	
HR SW 01	PPIC	450	D400	30.200	28.550	150	1.650	1.500	
HR SW 02	PPIC	450	D400	30.120	28.480	150	1.640	1.490	
HR SW 03	PPIC	450	D400	30.220	28.480	150	1.740	1.590	
R FW 01	PPIC	450	D400	30.120	27.559	150	2.561	2.411	
R FW 02	PPIC	450	D400	30.050	27.509	150	2.541	2.391	
R FW 03	PPIC	450	D400	30.000	27.477	150	2.523	2.373	

REVISION CHANGES - T2
ALL MAJOR CHANGES ARE CLOUDED AND / OR LISTED BELOW:
ADDITIONAL MANHOLE TO ALLOW GRAVITY DRAINAGE OF SAID CHANNEL DRAIN.

T2	15.12.20	REVISED SCHEDULE	RB	QS	QS
T1	30.09.20	TENDER ISSUE	CN	RB	QS
Rev	Date	Description	By	Check	App.

COPYRIGHT: THE COPYRIGHT OF THIS DRAWING IS VESTED IN CLANCY CONSULTING. IT SHALL NOT BE USED WITHOUT PERMISSION BY ANYONE FOR ANY PURPOSE. DO NOT SCALE THE DRAWING ELECTRONICALLY OR MANUALLY. WORK TO DIMENSIONS ONLY. ALL DIMENSIONS ARE IN MILLIMETRES UNLESS SHOWN OTHERWISE. DO NOT TURN ON LAYERS THAT HAVE BEEN TURNED OFF. DO NOT THAW LAYERS THAT HAVE BEEN FROZEN.

Client	DENMAR HOLDINGS (BVI) LTD
Project	HIGH STREET HUB HOTEL CAMDEN HIGH STREET LONDON NW1 7JR
Office	NORWICH - 01603 305 190
Discipline	CIVIL ENGINEERING
Title	DRAINAGE CONSTRUCTION MANHOLE SCHEDULE
Scale @ A1	NTS
Status	TENDER



www.clancy.co.uk

Originator	Job Number	Discipline	Building/Zone
CCL	28971	C	HUB
Type	Level	Drawing No.	Revision
DET	DRN	400411	T2