


shed base construction



Maxerio Basic Piles

Method: tree roots were located by hand digging and careful probing with metal rod. 60cm Maxerio piles were hand screwed between roots which were recovered in topsoil. 100 x 44 treated timber joists forming base were side screwed to Maxerio cleats at pile head leaving 50mm clearance between underside joists and ground covering roots. Roof drainage discharges back into floor void to maintain moisture levels in soil.



	SCALE	1:25 @ A4	DATE	01-02-21	DRAWN	PROJECT		
	TITLE	DETAILS OF TIMBER BASE				36A ESTELLE ROAD NW3		
JOB		PA-7		DRAWING		011		REV.