

## SITE INVESTIGATION FACTUAL REPORT

Report No: [REDACTED]  
Client: Sedgwick International UK - Maidstone  
Site: 124 Greencroft Gardens, London  
Client Ref: [REDACTED]  
Date of Visit: 01/09/2020



<h1 style="margin: 0;">Investigation Layout Plan</h1>		Sheet: 1 of 1 Job No: <span style="background-color: black; color: black;">XXXXXXXXXX</span> Date: 01/09/20	Site: 124, Greencroft Gardens, NW6  Work carried out for: Sedgwick International UK
DB (SI)	SA (Checked)	Jo (Drawn)	Weather: Dry

The diagram illustrates the investigation layout for a property. Key features include:

- Property Structure:** A central building with a **PORCH** and **STEPS UP** (0.6m high).
- Lightwell:** A rectangular area labeled **LIGHTWELL** and **CONCRETE**, measuring 2.8m by 6.5m.
- Gravel Area:** A large area labeled **GRAVEL** adjacent to the lightwell.
- Trees:** Two trees are shown on the left, with a note: **TREES HT 13.0m DT 6.5m**.
- Drainage Points:**
  - MH1:** A manhole located near the porch.
  - R1, R2:** Points on the lightwell structure.
  - TP/BH1:** A tree pit/born hole located near the gravel area.
  - RWP O/D:** A road water point located on the right side.
- Scale:** A scale bar indicates distances of 0.6m, 2.8m, and 6.5m.
- Legend:**
  - Surface Water Drain:** Represented by a dashed blue line with an arrow.
  - Foul Water Drain:** Represented by a solid red line with an arrow.

**PROPERTY  
ASSURANCE**  
Giving our all

### Trial Pit

████████████████████

TP 1

Sedgwick International UK


\_\_\_\_\_

### Hand tools

01/09/2020

124 Greencroft Gardens

Dry



For Strata below 600mm see Bore Hole log

Key:

D	Small disturbed sample	J	Jar sample
B	Bulk disturbed sample	V	Pilcon vane (kPa)
W	Water sample	M	Mackintosh probe
TDTD	Too dense to drive		

## Remarks:

Test results reported relate only to the items tested.  
This report shall not be reproduced except in full without approval of the Laboratory.

For and on behalf of CET  
Scott Alger - Lab

Report Format:

Approved Signatory  
02-Sep-20

<b>Borehole</b>		<b>1</b>	Sheet: 1 of 1 Job No: Date: 01/09/2020 Ground Level:		Site: 128 Greencroft Gardens  Client: Sedgwick International UK - Maidstone	
Boring Method: Hand Auger		Weather: Dry				
Diameter (mm): 75						
Depth	Soil Description				Thickness	Legend
(m)						
0.00	See Trial Pit				0.60	
0.60	MADEGROUND medium compact becoming compact orange-brown gravelly silty clayey with brick pieces				0.90	
1.50	Very stiff orange-brown gravelly silty CLAY				0.30	
1.60	End of BH					
Remarks: BH ends at 1.6m. Too gravelly to hand auger. BH dry and open on completion.					Key: D - Disturbed Sample B - Bulk Sample W - Water Sample      Roots J - Jar Sample        Roots V - Pilcon Shear Vane (kPa) Roots M - Mackintosh Probe    Depth to Water (m) TDTD - Too Dense To Drive	
Logged: DB      SA      Checked:      Approved:					Version: V1.0 28/01/16      N.T.S.	

### Laboratory Summary Results

Our Ref : XXXXXXXXXX

Location : 128, Greencroft Gardens, London

Client: Sedgwick International UK - Maidstone

Address: [REDACTED]

Date Sampled: 01/09/2020

Date Received : 02/09/2020

Date Tested : 02/09/2020

Date of Report : 04/09/2020

Sample Ref		Type	Moisture Content (%) [1]	Soil Fraction > 0.425mm (%) [2]	Liquid Limit (%) [3]	Plastic Limit (%) [4]	Plasticity Index (%) [5]	Liquidity * Index [5]	Modified * Plasticity Index (%) [6]	Soil * Class [7]	Filter Paper Contact Time (h)	Soil Sample Suction (kPa) [8]	Oedometer Strain [9]	Estimated* Heave Potential (Dd) (mm) [10]	In situ * Shear Vane Strength [kPa] [11]	Organic * Content (%) [12]	pH * Value [13]	Sulphate Content * (g/l)		* Class [16]
TP/BH No	Depth (m)																	SO <sub>3</sub> [14]	SO <sub>4</sub> [15]	
1	U/S 0.40	D	17	47	40	20	20	-0.16	11	CI	Not suitable for suction testing- Made ground									
	1.0	D	18	33	65	22	43	-0.10	29	CH	Not suitable for suction testing- Made ground									
	1.5	D	30	44	Insufficient sample for further testing															

## Test Methods / Notes

(1) BS 1377 : Part 2 : 1990, Test No 3.2

(2) Estimated if <5%, otherwise measured

[3] BS 1377 : Part 2 : 1990, Test No 4.4

[4] BS 1377 : Part 2 : 1990, Test No 5-3

[5] BS 1377 : Part 2 : 1990, Test No 5.4

[5] BS 1377 : Part 2 : 1990, Test No 5.4

[6] BRE Digest 240:1993

[7] BS 5930: 2018 : Figure 8 - Plasticity

(8) In-house method S9a adapted from ORE IP 4/93

[9] In-house Test Procedure S17a: One Dimensional Swell/Strain Test

[10] Estimated Heave Potential (Od)

[21] Values of shear strength were determined in situ by CET using

<sup>a</sup> Wilson hand type or Gougeon type 1015.

Test No. 4

[22] 85-1877 : Part 8 : 1990, Test No 4

(13) BS 1377 : Part 2 : 1990, Test No 9

[14] BS 1377 : Part 3

(16) DPE Special Digest One (Concrete in Aggressive Ground) August 2005

Note that if the SO<sub>4</sub> content falls into the DS-4 or DS-5 class, it would be

prudent to consider the sample as falling into the DS-4M or DS-5M.

class respectively unless water soluble magnesium testing is undertaken.

to permit alternative:

to prove otherwise.

\* These tests are not UKAS accredited

**Key**

D	Disturbed sample (small)
---	--------------------------

7	Disturbed sample ( small )
8	Disturbed sample ( bulk )

B	Disturbed sample (bulk)
U	Undisturbed sample

U	Undisturbed sample
M	Groundwater sample

W	Groundwater sample
WSP	Groundwater sample - 10 m - 10 m - 10 m

END      Essentially Non-Plastic by

U/S                      Underside of Foundation

Test results reported relate only to the items tested.

This report shall not be reproduced except in full without approval of the laboratory.

Version: SBH V1 - 30.06.20

0927





Moisture Content Profiles

Our Ref : XXXXXXXXXX  
Location : 128, Greencroft Gardens, London  
Work carried out for: Setgwick International UK - Maidstone

Shear Strength Profiles

Date Sampled : 01/09/2020  
Date Received : 02/09/2020  
Date Tested : 02/09/2020  
Date of Report : 04/09/2020



**Notes**  
1. If plotted, O.L.L. and P.L.-2 (after Driscoll, 1983) should only be applied to London Clay (and similarly overconsolidated clay) at shallow depths.  
2. Unless specifically noted the profiles have not been related to a site datum.

**Notes**  
1. Unless otherwise stated, values of Shear Strength were determined in situ by CET using a Pilon Hand Vane the calibration of which is limited to a maximum reading of 130 kPa.  
2. Unless specifically noted the profiles have not been related to a site datum.

<b>EPSL</b> European Plant Science Laboratory	Sheet: 1 of 1	Site: 128 Greencroft Gardens,	
	Job No: [REDACTED]	Work carried out for: Sedgwick International UK	
	Date: 07/09/2020		
	Order No: [REDACTED]		
	EPSL Ref: [REDACTED]		


  

***Certificate of Analysis***

The following work was commissioned by CET on behalf of their client. Root samples were obtained in sealed packets from the above site with no reference given as to the types of tree or shrub from which they may have originated.  
 The results were as follows -

<b>Trial pit/ Borehole number</b>	<b>Root diameter (mm)</b>	<b>Tree, shrub or climber from which root originates</b>	<b>Result of starch test</b>
TP1 (USF)	6 mm	Tilia spp. 5 roots	Positive
BH1 (0.8-1.6m)	10 mm	Tilia spp. 2 roots	Positive

Tilia spp. are limes.

  
 MDM

Head of Laboratory Services : M D Mitchell B.Sc. (Hons), M.Phil.  
 Plant Anatomist : Dr G S Turner B.Sc. (Hons), M.Sc., Ph.D  
 Plant Anatomist : Dr R J Shaw B.Sc. (Hons), Ph.D  
 Consultant: Dr M P Denne B.Sc. (Hons), M.Sc., Ph.D

To: Sedgwick International UK - Maidstone

Our Ref:

Your Ref:

Date: 03-Sep-20

From: Michael Whittington

## ESTIMATE

Site:- 124 Greencroft Gardens, London

### Item

1.0	Location	<b>Run 1</b>
	Shared System	flats
	Condition Grade	B
	Drain Serviceability	Unserviceable
	Work Spec	install a 5 metre 100mm flexi liner to cover over defects in drain run. confined spaces required due to depth of chamber (2400mm) drain trace to cracked junction at 6 metres and report from site best way to excavate and remove. (possibly in light well)
2.0	Location	<b>Run 2</b>
	Shared System	flats
	Condition Grade	N/a
	Drain Serviceability	N/a
	Work Spec	HPWJ to remove concrete in run at 0.0 metres then CCTV survey upstream. confined spaces required due to depth of chamber (2400mm)

### Notes

Repairs to shared runs and off boundary pipe-work may be the responsibility of the water authority.

### Condition Grade

A - Structurally sound with no leakage evident.  
B - Cracks and fractures observed.  
C - Structurally unsound

Quotation is binding only if accepted within 28 days from date of issue and is subject to our Standard Terms and Conditions  
The price qualification notes, stated on the drainage solutions schedule of rates, apply to this quotation.  
CET Structures Ltd undertakes to return to site free of charge to carry out remedial work to the drainage repairs set out above for a period of 2 months from the date of this invoice. The company standard charge rates will apply to the visit should the work requested be unrelated to the said repairs.



Client ref	
Job Number :	
Insurer	Allianz Insurance
Date:-	03-Sep-20
Recommendation	1

Item No	Description	Unit	Quantity
1.0	<b>Emergency Drain Blockage Clearance</b>		
1.1	Unblock drain 8am-6pm - First 1/2 Hour	Item	
1.2	Unblock drain 8am-6pm- Subsequent 1/2 Hour	Item	
1.3	Unblock drain 6pm-midnight	Item	
1.4	Unblock drain 6pm-midnight - Subsequent 1/2 hour	Item	
2.1	<b>CCTV Surveys</b>		
2.2	Undertake CCTV survey 8am-6pm (up to 3 hours)	Item	
2.3	Additional 1/2 hr survey charge	Item	
3.0	<b>Replacing Underground Drainage</b>		
3.1	<b>Gullies</b>		
3.2	Take out and replace gully (100mm outlet)	Item	
3.3	Take out and replace rodding point (100mm outlet)	Item	
3.4	<b>Bends/junctions</b>		
3.5	Excavate and replace rest bend (100mm outlet)	Item	
3.6	Excavate and replace rest bend (150mm outlet)	Item	
3.7	Excavate and replace junction/bend (100mmØ), Excavation depth 0-1m.	Item	
3.8	Excavate and replace junction/bend (150mmØ), Excavation depth 0-1m	Item	
3.9	Excavate and replace junction/bend (100mmØ), Excavation depth 1-1.5m.	Item	
3.10	Excavate and replace junction/bend (150mmØ), Excavation depth 1-1.5m.	Item	
3.11	Excavate and replace junction/bend (100mmØ), Excavation depth 1.5-2.0m.	Item	
3.12	Excavate and replace junction/bend (150mmØ), Excavation depth 1.5-2.0m.	Item	
3.13	<b>Pipes</b>		
3.14	Excavate trench and replace 100mmØ pipework, Excavation depth 0-1m, First 10m.	m	
3.15	Excavate trench and replace 150mmØ pipework, Excavation depth 0-1m, First 10m.	m	
3.16	Excavate trench and replace 100mmØ pipework, Excavation depth 0-1m.	m	
3.17	Excavate trench and replace 150mmØ pipework, Excavation depth 0-1m.	m	
3.18	Excavate trench and replace 100mmØ pipework, Excavation depth 1-1.5m, First 10m.	m	
3.19	Excavate trench and replace 150mmØ pipework, Excavation depth 1-1.5m, First 10m.	m	
3.20	Excavate trench and replace 100mmØ pipework, Excavation depth 1-1.5m.	m	
3.21	Excavate trench and replace 150mmØ pipework, Excavation depth 1-1.5m.	m	
3.22	Excavate trench and replace 100mmØ pipework, Excavation depth 1.5-2.0m, First 10m.	m	
3.23	Excavate trench and replace 150mmØ pipework, Excavation depth 1.5-2.0m, First 10m.	m	
3.24	Excavate trench and replace 100mmØ pipework, Excavation depth 1.5-2.0m.	m	
3.25	Excavate trench and replace 150mmØ pipework, Excavation depth 1.5-2.0m.	m	
3.26	<b>Surface Reinstatement of Trenches</b>		
3.27	Excavate through and reinstate turf	m	
3.28	Excavate through and replace concrete paving slabs	m	
3.29	Excavate through and replace block paving	m	
3.30	Excavate through and reinstate plain concrete, maximum thickness 100mm.	m	
3.31	Excavate through and reinstate plain concrete, thickness 100- 200mm.	m	
3.32	Excavate through and reinstate reinforced concrete, maximum thickness 100mm.	m	
3.33	Excavate through and reinstate reinforced concrete, thickness 100-200mm.	m	
3.34	Excavate through and reinstate Tarmac - Cold rolled	m	
3.35	Excavate through and reinstate Tarmac - Hot rolled	m	
3.36	Reinstatement of crazy paving	m	
4.0	<b>Lining</b>		
4.1	Set up lining rig for drain lining including first 3m of lining per run, for 100mm or 150mm	Item	1
4.2	Line 100mmØ drain	m	
4.3	Super Flex Liner 100mm drain	m	2
4.4	Line 150mmØ drain	m	
4.5	Super Flex Liner 150mm drain	m	
4.6	Post lining CCTV survey	no	1
4.7	Minimum lining charge	Item	
4.8	Root cutting of drain prior to lining	hr	1
4.9	Set up lining rig for patch lining	Item	
4.10	Patch line 100mmØ drain	no	1
4.11	Patch line 150mmØ drain	no	
4.12	Post patch lining CCTV survey	Item	
4.13	Minimum patch lining charge	Item	
4.14	Re-open lateral branch up to 2m length, pipe up to 150mm	no	
4.15	Re-open lateral branch over 2m length, pipe up to 150mm	no	
4.16	Epoxy resin	no	
5.0	<b>Miscellaneous</b>		
5.1	Excavation and backfill of soakaway (1m3) with stone	Item	
5.2	% Uplift on disbursements and suppliers charges	%	
5.3	Daywork - Hourly labour rate	hr	
5.4	Minimum project value	Item	
5.5	Confined space equipment	Item	1
5.6			
5.7			
5.8			
6.0	<b>Additional items</b>		
6.1	De-scaling (fat/grime)	hr	
6.2	De-scaling (scale using chain flails)	hr	
6.3	Gully surround	item	
6.4	Manhole works (up to 1.2m)	item	
6.5	Oversize soakaway (1.5m3)	item	
6.6	Soakaway >1.5m3	item	
6.7	Waste disposal	m	
6.8	Shoring	m	0
6.9			
6.10	<b>Total Estimate Price For Recommendation Number</b>		<b>1.0</b>
6.11	Subject to discount		<b>0.00</b>

Note: Subject to the attached Terms and Conditions  
A - When calculating prices, all measurements are rounded up  
C - Every effort will be made to match existing surfaces where disturbed although this cannot be guaranteed  
G - Daywork rates do not include for materials that are charged at cost plus 25%  
KEY: ne = not exceeding, eo = extra over rate, m = linear metre, nr = number, hr = hour

B - Depths are taken to the base of excavations  
D - All rates exclude VAT  
F - The above rates are subject to re-measurement  
E - Depths are taken to the base of excavations

**ESTIMATING & COSTING SHEET - DOMESTIC DRAINAGE**

Site:-

124 Greencroft Gardens, London

Client :-

Sedgwick International UK - Maidstone

Attention of:-

Michael Whittington

Client ref

Job Number :-

Insurer

Date:-

Recommendation

2

Item No	Description Run 2	Unit	Quantity
1.0	<b>Emergency Drain Blockage Clearance</b>		
1.1	Unblock drain 8am-6pm - First 1/2 Hour	Item	
1.2	Unblock drain 8am-6pm- Subsequent 1/2 Hour	Item	
1.3	Unblock drain 6pm-midnight	Item	
1.4	Unblock drain 6pm-midnight - Subsequent 1/2 hour	Item	
2.1	<b>CCTV Surveys</b>		
2.2	Undertake CCTV survey 8am-6pm (up to 3 hours)	Item	1
2.3	Additional 1/2 hr survey charge	Item	
3.0	<b>Replacing Underground Drainage</b>		
3.1	<b>Gullies</b>		
3.2	Take out and replace gully (100mm outlet)	Item	
3.3	Take out and replace rodding point (100mm outlet)	Item	
3.4	<b>Bends/junctions</b>		
3.5	Excavate and replace rest bend (100mm outlet)	Item	
3.6	Excavate and replace rest bend (150mm outlet)	Item	
3.7	Excavate and replace junction/bend (100mmØ), Excavation depth 0-1m.	Item	
3.8	Excavate and replace junction/bend (150mmØ), Excavation depth 0-1m.	Item	
3.9	Excavate and replace junction/bend (100mmØ), Excavation depth 1-1.5m.	Item	
3.10	Excavate and replace junction/bend (150mmØ), Excavation depth 1-1.5m.	Item	
3.11	Excavate and replace junction/bend (100mmØ), Excavation depth 1.5-2.0m.	Item	
3.12	Excavate and replace junction/bend (150mmØ), Excavation depth 1.5-2.0m.	Item	
3.13	<b>Pipes</b>		
3.14	Excavate trench and replace 100mmØ pipework, Excavation depth 0-1m, First 10m.	m	
3.15	Excavate trench and replace 150mmØ pipework, Excavation depth 0-1m, First 10m.	m	
3.16	Excavate trench and replace 100mmØ pipework, Excavation depth 0-1m.	m	
3.17	Excavate trench and replace 150mmØ pipework, Excavation depth 0-1m.	m	
3.18	Excavate trench and replace 100mmØ pipework, Excavation depth 1-1.5m, First 10m.	m	
3.19	Excavate trench and replace 150mmØ pipework, Excavation depth 1-1.5m, First 10m.	m	
3.20	Excavate trench and replace 100mmØ pipework, Excavation depth 1-1.5m.	m	
3.21	Excavate trench and replace 150mmØ pipework, Excavation depth 1-1.5m.	m	
3.22	Excavate trench and replace 100mmØ pipework, Excavation depth 1.5-2.0m, First 10m.	m	
3.23	Excavate trench and replace 150mmØ pipework, Excavation depth 1.5-2.0m, First 10m.	m	
3.24	Excavate trench and replace 100mmØ pipework, Excavation depth 1.5-2.0m.	m	
3.25	Excavate trench and replace 150mmØ pipework, Excavation depth 1.5-2.0m.	m	
3.26	<b>Surface Reinstatement of Trenches</b>		
3.27	Excavate through and reinstate turf.		
3.28	Excavate through and replace concrete paving slabs	m	
3.29	Excavate through and replace block paving	m	
3.30	Excavate through and reinstate plain concrete, maximum thickness 100mm.	m	
3.31	Excavate through and reinstate plain concrete, thickness 100-200mm.	m	
3.32	Excavate through and reinstate reinforced concrete, maximum thickness 100mm.	m	
3.33	Excavate through and reinstate reinforced concrete, thickness 100-200mm.	m	
3.34	Excavate through and reinstate Tarmac - Cold rolled	m	
3.35	Excavate through and reinstate Tarmac - Hot rolled	m	
3.36	Reinstatement of crazy paving	m	
4.0	<b>Lining</b>		
4.1	Set up lining rig for drain lining including first 3m of lining per run, for 100mm or 150mm	Item	
4.2	Line 100mmØ drain	m	
	Super Flex Liner 100mm drain	m	
4.3	Line 150mmØ drain	m	
	Super Flex Liner 150mm drain	m	
4.4	Post lining CCTV survey	no	
4.5	Minimum lining charge	Item	
4.6	Root cutting of drain prior to lining	hr	
4.7	Set up lining rig for patch lining	Item	
4.8	Patch line 100mmØ drain	no	
4.9	Patch line 150mmØ drain	no	
4.10	Post patch lining CCTV survey	Item	
4.11	Minimum patch lining charge	Item	
4.12	Re-open lateral branch up to 2m length, pipe up to 150mm	no	
4.13	Re-open lateral branch over 2m length, pipe up to 150mm	no	
	Epoxy resin	no	
5.0	<b>Miscellaneous</b>		
5.1	Excavation and backfill of soakaway (1m3) with stone	Item	
5.2	% Uplift on disbursements and suppliers charges	%	
5.3	Daywork - Hourly labour rate	hr	
5.4	Minimum project value	Item	
5.5			
5.6			
5.7			
5.8			
6.0	<b>Additional items</b>		
6.1	De-scaling (fat/grime)	hr	1
6.2	De-scaling (scale using chain flails)	hr	
6.3	Gully surround	Item	
6.4	Manhole works (up to 1.2m)	Item	
6.6	Oversize soakaway (1.5m3)	Item	
6.7	Soakaway >1.5m3	Item	
6.8	Waste disposal	m	
6.9	Shoring	m	
<b>Total Estimate Price For Recommendation Number</b>			2.0
Subject to discount			0.00
Total subject to VAT @ 20%			

Note: Subject to the attached Terms and Conditions

A - When calculating prices, all measurements are rounded up

C - Every effort will be made to match existing surfaces where disturbed although this cannot be guaranteed

G - Daywork rates do not include for materials that are charged at cost plus 25%

KEY: ne = not exceeding, ex = extra over rate, m = linear metre, nr = number, hr = hour

B - Depths are taken to the base of excavations

D - All rates exclude VAT

F - The above rates are subject to re-measurement

E - Depths are taken to the base of excavations

<b>Coding Sheet</b>		Sheet:	1	Site:	128 Greencroft Gardens		
		Job No.:					
		Date:		Client:	Sedgwick International UK - Maidstone		

<b>Run:</b>	<b>1</b>						
From:	MH1		Invert Level:	2400mm	Direction:	U/S	
To:	front		Invert Level:		Function:	F/W	
Pipe Material:	VC		Pipe Dia:	100			
Water/Pressure Test:			Drain Break-In:	No	Gully Condition:		
Distance (m)	Code	Clock Ref at to	Dia mm	Intrusion % mm	Shared Run:	Yes	
					If Shared How:	With flats	
0.00	ST				Remarks	Surface Material	Length (m)
0.20	LL				slight	concrete	0.6
0.20	CC	3	6		Crack circumferential	under steps	2.8
0.60	CL	4			Crack longitudinal	concrete	3.2
3.20	CC	12	12		Crack circumferential		
4.30	RFJ				Roots fine at joint		
6.10	JX	9			Junction defective at		
6.10	CC	12	6		Crack circumferential		
6.60	FH				unable to push		
Comments:							
deep mh.camera lead keeps flexing in deep chamber.not pushing along.							

<b>Run:</b>	<b>2</b>						
From:	MH1		Invert Level:	2400mm	Direction:	U/S	
To:	front		Invert Level:		Function:		
Pipe Material:	VC		Pipe Dia:	100			
Water/Pressure Test:			Drain Break-In:	No	Gully Condition:		
Distance (m)	Code	Clock Ref at to	Dia mm	Intrusion % mm	Shared Run:	Yes	
					If Shared How:	With flats	
0.00	ST				Remarks	Surface Material	Length (m)
0.00	DE			75	Debris	concrete	0
0.00	FH				unable to push		
Comments:							

<b>Manhole Details</b>	Sheet:	1	Site:	128 Greencroft Gardens
	Job No.:			
	Date:	01/09/20	Client:	Sedgwick International UK - Maidstone

MH:- MH1 Depth:- 2400mm (mm)

Chamber Dimension:- 800 / 500 (mm)

Depths of run if different to invert level:-

Run	Depth (mm)
1	2250mm
2	525mm

Manhole Condition:- Very Good

Reasons for poor condition.

MH:-   Depth:-   (mm)

Chamber Dimension:-   /   (mm)

Depths of run if different to invert level:-

Run	Depth (mm)

Manhole Condition:-  

Reasons for poor condition.

MH:-   Depth:-   (mm)

Chamber Dimension:-   /   (mm)

Depths of run if different to invert level:-

Run	Depth (mm)

Manhole Condition:-  

Reasons for poor condition.

Key

Interceptor

Internal Back Drop.

External Back Drop.

Additional Comments for Poor Condition