

# soiltechnics

environmental ▪ geotechnical ▪ building fabric

Proposed basement development

14A Hampstead Hill Gardens

London

## **Basement Impact Assessment Report**

Cedar Barn, White Lodge, Northamptonshire, NN6 9PY

T: 01604 781877  
F: 01604 781007

e: [mail@soiltechnics.net](mailto:mail@soiltechnics.net)  
w: [www.soiltechnics.net](http://www.soiltechnics.net)

**Proposed basement redevelopment  
14A Hampstead Hill Gardens  
Camden  
London  
NW3 2PL**

**Basement Impact Assessment Report**

Soiltechnics Ltd. Cedar Barn, White Lodge, Walgrave, Northampton. NN6 9PY.  
Tel: (01604) 781877 Fax: (01604) 781007 E-mail: [mail@soiltechnics.net](mailto:mail@soiltechnics.net)

**Report originators**

Prepared  
by



Angus Wilson CEng MICE, UK RoGEP  
(Professional)

[angus.wilson@soiltechnics.net](mailto:angus.wilson@soiltechnics.net)  
Associate Technical Director

Reviewed  
by




Seb Crolla B.Sc, (Hons), MEnvSc., FGS

[seb.crolla@soiltechnics.net](mailto:seb.crolla@soiltechnics.net)  
Associate Director



## Aerial photograph of site



## Report status and format

Report Section	Principal Coverage
1	Introduction
2	Existing and Proposed Development
3	Desk Study
4	Screening
5	Scoping
6	Ground Investigations
7	Engineering
8	Basement Impact Assessment

## List of drawings

Drawing	Principal coverage	Revision	Comments
01	Site location plan		
02	Existing site features		

## List of appendices

Appendix	Content
A	Author's CV
B	Letter of approval from Chartered Geologist
C	Project proposals
D	Copies of responses from statutory undertakers
E	Ground Movement Analyses

## **Non – Technical Summary**

The site is located at 14A Hampstead Hill Gardens, London, NW3 2PL.

The site is generally flat and is currently occupied by two single garages. Hampstead Hill Tunnel, which carries the North London Line, passes directly under the site. The crown of the tunnel is approximately 14m below ground level at the site.

The proposed development comprises demolition of the existing garages followed by construction of a three storey property including single storey basement.

The site was occupied by a field prior to construction of the present-day properties along Hampstead Hill Gardens at some point between 1871 and 1895. The site and immediate vicinity remains largely unchanged from 1915 until the present day

A ground investigation was undertaken in October 2020. Ground conditions comprise Made Ground sequentially overlying Head and London Clay. Groundwater was encountered during the site investigation within the Head deposits. Post fieldwork monitoring recorded groundwater at a depth of around 3m below ground level.

Ground movement analyses have been undertaken to assess the impact on the adjoining properties from the proposed works. Those analyses demonstrate that with appropriate controls, the potential damage to adjoining properties can be limited to Burland Category 1, in accordance with planning guidance

## **1 Introduction**

### **1.1. Objectives**

- 1.1.1 This report presents a Basement Impact Assessment (BIA) for a proposed basement at 14A Hampstead Hill Gardens, London, NW3 2PL. This report considers the effect of the proposed basement on the local hydrology, geology, hydrogeology and potential impacts to neighbours and the wider environment. A site location plan is presented as Drawing 01.
- 1.1.2 The principal objective of the assessment is to present evidence to support a planning application for the project as required by policy A5 Basements in the Camden Local Plan (2017) and Camden Planning Guidance – Basements (March 2018).

### **1.2. Client instructions and confidentiality**

- 1.2.1 This report has been produced following instructions received from Price and Myers on behalf of our mutual client, Mr Alon Mekel.
- 1.2.2 This report has been prepared for the sole benefit of our above-named instructing client, but this report, and its contents, remains the property of Soiltechnics Limited until payment in full of our invoices in connection with production of this report.

### **1.3. Author qualifications**

- 1.3.1 The report has been prepared by a Chartered Civil Engineer with over 10 years relevant experience in geotechnical engineering. A copy of the CV is presented in Appendix A.
- 1.3.2 This report has also been reviewed by a Chartered Geologist to satisfy Camden planning guidance with respect to groundwater flow; a letter of approval is presented as Appendix B.

### **1.4. Sources of information**

- 1.4.1 Specific documents are referenced at appropriate places within this report. Reference has also been made to the following documents:
- Camden Planning Guidance – Basements (London Borough of Camden, 2018)
  - Camden geological, hydrogeological and hydrological study – Guidance for subterranean development (Arup, 2010)
  - Camden Local Plan (London Borough of Camden, 2017)
- 1.4.2 A construction method statement has been prepared by a Structural Engineer which is presented separately.

### **1.5. Soiltechnics Liability**

- 1.5.1 Soiltechnics disclaims any responsibility to our Client and others in respect of any matters outside the scope of this report. This report has been prepared with reasonable skill, care and diligence in accordance with the terms of our contract, taking account of the manpower, resources, investigations and testing devoted to it by agreement with our Client. This report is confidential to our Client and Soiltechnics accepts no responsibility of whatsoever nature to third parties to whom this report or any part thereof is made known. Any such party relies upon the report at their own risk.



## **2 Existing and Proposed Development**

### **2.1. Description of the existing site**

- 2.1.1 The existing features at the site are presented as Drawing 02.
- 2.1.2 The site comprises two garages located between a four storey and three storey residential property. The garages are in a satisfactory state of repair.
- 2.1.3 The site is located on the side of a hill with the ground sloping down towards the east at a gradient of approximately 1V:15H. The level of the site is approximately 72m above Ordnance Datum (AOD)
- 2.1.4 The locale is dominated by residential properties of masonry construction, many of which have a basement or lower ground floor.
- 2.1.5 There is a gap in the houses along both sides of Hampstead Hill Gardens. This gap coincides with the alignment of a railway line, owned and operated by London Overground, which passes through a tunnel beneath the site.

### **2.2. Project proposals**

- 2.2.1 The proposed development comprises demolition of the existing garages followed by the construction of a three storey building including single storey basement.
- 2.2.2 The project proposals are shown on the drawings presented as Appendix C.

### **3 Desk Study**

#### **3.1. Site history**

- 3.1.1 A review of Ordnance survey and London town maps dating back to 1850 has been undertaken.
- 3.1.2 The site was occupied by open fields in 1850. Significant residential development in the wider area is recorded on the 1871 maps; this includes construction of the railway tunnel beneath the site carrying the North London Line. The railway tunnel, which connects Hampstead Heath Station in the East to Finchley Road and Frognal Station in the west, is understood to have been opened in 1860 (<https://www.theundergroundmap.com/article.html?id=3364>)
- 3.1.3 Development of the area continued throughout the 1800s and includes the construction of Hampstead Hill Gardens and several of the present day properties at some point between 1871 and 1895. The remaining properties along Hampstead Hill Gardens were constructed prior to 1915.
- 3.1.4 The site and immediate vicinity remains largely unchanged from 1915 until the present day.

#### **3.2. Geology**

- 3.2.1 Reference has been made to the 1:50 000 scale geological map published by the British Geological Survey (BGS) – Sheet 256 North London (2006). Reference has also been made to historical exploratory hole logs available from the BGS GeoIndex.
- 3.2.2 The site is indicated to be underlain by London Clay, which is anticipated to extend for tens of metres beneath the site.
- 3.2.3 No superficial deposits have been mapped at or in close proximity to the site. However, head propensity is mapped at the site indicating a possible chance of encountering head deposits.

#### **3.3. Hydrogeology**

- 3.3.1 The site is underlain by London Clay which is designated as an unproductive stratum.
- 3.3.2 The site is not located within a Source Protection Zone.


#### **3.4. Hydrology, drainage and flood risk**

- 3.4.1 The site is not located within close proximity (250m) of any surface water features.
- 3.4.2 Reference has been made to Figure 11 from the Camden Geological, Hydrogeological and Hydrological Study (Arup, 2010). The site is not located within close proximity to any historical watercourses. An extract of Figure 11 is presented below with the approximate position of the site represented by the red box.





- 3.4.3 The site lies outside of the catchment of the Hampstead Heath Ponds.
- 3.4.4 The front of the site is surfaced hard surfaced to facilitate access to the garage. The rear of the site is soft landscaped. It is understood that there is an existing drainage pipe situated between the garages and discharging to the main sewer on the street.
- 3.4.5 Reference has been made to GOV.UK website to assess the risk of flooding due to a variety of sources. The site is indicated to be at low to medium risk of flooding from surface water, sometimes referred to as flash flooding.



- 3.4.6 Reference has been made to Figure 15 of the Camden Geological, Hydrogeological and Hydrological Study (Arup, 2010). That Figure shows the property to be remote from areas of historical flooding.
- 3.4.7 Reference has been made to the London Borough of Camden, Strategic Flood Risk Assessment (URS, 2014). Figure 6 of that document indicates that the site is not situated within a Critical Drainage Area. A Critical Drainage Area (CDA) is defined as “a discrete geographic area (usually a hydrological catchment) where multiple and interlinked sources of flood risk (surface water, groundwater, sewer, main river and/or tidal) cause flooding in one or more Local Flood Risk Zones during severe weather thereby affecting people, property or local infrastructure”.

### **3.5. Quarrying and mining**

- 3.5.1 The site is not within an area affected by mining.
- 3.5.2 Inspection of historical Ordnance Survey maps dating back to 1850 does not reveal any quarrying activities within 250m of the property.

### **3.6. Unexploded Ordnance (UXO)**

- 3.6.1 Reference has been made to The London County Council Bomb Damage Maps, 1939 – 1945 (Ward, 2015). Those maps show that the site and immediate vicinity did not suffer bomb damage during World War 2.
- 3.6.2 Additionally, a UXO preliminary risk review was commissioned by Soiltechnics and undertaken by MACC International Ltd who are a UXO specialist. They concluded that “the UXO risk is considered to be LOW within the site boundary”.

### **3.7. Below ground services and infrastructure**

- 3.7.1 We have contacted the following Statutory Undertakers (SUs) to obtain copies of their records for the purposes of our ground investigation activities. Copies of statutory undertaker’s responses are presented in Appendix D.
- BT Openreach Ltd;
  - Cadent Gas Ltd;
  - Thames Water;
  - UK Power Networks; and
  - London Underground Ltd.
- 3.7.2 There is an existing railway tunnel situate beneath the site. The crown of the tunnel is estimated to be ~14m below current site ground level.
- 3.7.3 There is a sewer and a water main indicated to be located within the centre of the highway. BT cables are indicated to be present beneath the pavement closest to the site. A gas pipe is indicated to be present in the footpath furthest from the site.

## 4 Screening

### 4.1. Introduction

4.1.1 A screening process has been undertaken to satisfy Stage 1 of Camden Planning Guidance – Basements; this section of the report provides direct responses to the questions posed in Figures 12 to 14.

### 4.2. Subterranean (groundwater) flow

Question	Response	Details
1a. Is the site located directly above an aquifer?	No	The site is underlain by London Clay.
1b. Will the proposed basement extend beneath the water table surface?	No	The London Clay Formation comprises reasonably homogenous relatively impermeable clays which are not able to transmit groundwater under normal hydraulic gradients
2. Is the site within 100m of a watercourse, well (used / disused) or potential spring line?	No	The site is remote (in excess of 100m) of any known watercourse. The geology of the area is not conducive to spring lines or wells for extraction of water.
3. Is the site within the catchment of the pond chains on Hampstead Heath?	No	The site is outside the catchment area.
4. Will the proposed basement development result in a change in the proportion of hard surfaced / paved areas?	No	The basement will be beneath the existing garages and marginally extending into the rear garden, which is paved in this area. Accordingly, there will be negligible change to the impermeable area.
5. As part of site drainage, will more surface water (e.g. rainfall and run-off) than at present be discharged to the ground (e.g. via soakaways and/or SUDS)?	No	The size of the rear garden will be reduced and therefore the volume of water discharged to the ground will also be reduced.
6. Is the lowest point of the proposed excavation (allowing for any drainage and foundation space under the basement floor) close to, or lower than, the mean water level in any local pond (not just the pond chains on Hampstead Heath) or spring line?	No	There are no ponds or spring lines within 100m of the site.

**Table 4.2**

### 4.3. Slope stability

Question	Response	Details
1. Does the existing site include slopes, natural or man-made greater than 7 degrees (approximately 1 in 8)?	No	The site is generally flat.
2. Will the proposed re-profiling of landscaping at the site change slopes at the property boundary to more than 7 degrees (approximately 1 in 8)?	No	N/A
3. Does the development neighbour land, including railway cuttings and the like, with a slope greater than 7 degrees (approximately 1 in 8)?	No	The site is located on the side of a hill with the ground sloping down towards the east at a gradient of approximately 1V:15H
4. Is the site within a wider hillside setting in which the general slope is greater than 7 degrees (approximately 1 in 8)?	No	The wider site setting comprises a hill sloping down to the east at a gradient of circa 1V:15H.

5. Is the London Clay the shallowest strata at the site?	Yes	A nominal, inconsequential, thickness of Made Ground associated with the existing building is anticipated.
6. Will any trees be felled as part of the development and/or are any works proposed within any tree protection zones where trees are to be retained?	No	No trees to be removed
7. Is there a history of seasonal shrink-swell subsidence in the local area and/or evidence of such effects at the site?	Yes	London Clay is susceptible to shrink swell subsidence. However, the proposed basement foundations will be below the depth of susceptibility.
8. Is the site within 100m of a watercourse or a potential spring line?	No	The site is remote from any current watercourses. The geology of the area is not conducive to spring lines or wells for extraction of water.
9. Is the site within an area of previously worked ground?	No	There is no evidence to suggest quarrying has taken place at the site.
10. Is the site within an aquifer. If so, will the proposed basement extend beneath the water table such that dewatering may be required during construction?	No	The property is underlain by London Clay, which is relatively impermeable.
11. Is the site within 50m of the Hampstead Heath Ponds?	No	The site is circa 350m away from the Hampstead No. 1 Pond.
12. Is the site within 5m of a highway or pedestrian right of way?	Yes	The site will be within 5m of the Hampstead Hill Gardens highway and pavement.
13. Will the proposed basement significantly increase the differential depth of foundations relative to neighbouring properties?	No	The neighbouring properties both have existing basements and therefore foundation levels are likely to be similar.
14. Is the site over (or within the exclusion zone of) any tunnels, e.g. railway lines?	Yes	The site directly overlies an existing railway tunnel.

**Table 4.3**

#### 4.4. Surface flow and flooding

Question	Response	Details
1. Is the site within the catchment of the ponds chains on Hampstead Heath?	No	The site is outside the catchment of the ponds.
2. As part of the proposed site drainage, will surface water flows (e.g. volume of rainfall and peak run-off) be materially changed from the existing route?	No	There will be a marginal change to the area of garden that is impermeable and therefore marginal change to the site drainage and surface water flows.
3. Will the proposed basement development result in a change in the proportion of hard surfaced / paved external areas?	No	There will be a marginal change to the area of garden that is impermeable
4. Will the proposed basement result in changes to the profile of the inflows (instantaneous and long-term) of surface water being received by adjacent properties or downstream watercourses?	No	There will be negligible change to the drainage pattern on site.
5. Will the proposed basement result in changes to the quality of surface water being received by adjacent properties or downstream watercourses?	No	There will be negligible change to the drainage pattern on site.

6. Is the site in an area identified to have surface water flood risk according to either the Local Flood Risk Management Strategy or the Strategic Flood Risk Assessment or is it at risk from flooding, for example because the proposed basement is below the static water level of nearby surface water feature.	No	The site is indicated to be at low to medium flood risk from surface water flooding. However, there have been no floods recorded at the site historically. Furthermore, the strategic flood risk assessment does not record the site as being at risk from flooding.
--	----	--

**Table 4.4**

## **4.5. Non-technical summary of screening process**

4.5.1 The screening process has identified the following issues to be carried forward to scoping for further assessment:

- Potential damage to neighbouring properties
- Potential impact on the railway tunnel that passes beneath the site

## **5 Scoping**

### **5.1. Introduction**

- 5.1.1 A scoping assessment has been undertaken to satisfy Stage 2 of Camden Planning Guidance – Basements; this section of the report provides an assessment and discussion of each of the issues that have arisen from the screening process.

### **5.2. Potential damage to neighbouring properties**

- 5.2.1 Construction of the proposed basement will cause ground movements that have the potential to cause damage to existing neighbouring structures.
- 5.2.2 It is considered that the scheme can be suitably designed and constructed to maintain stability therefore minimise damage. A detailed ground movement analysis is presented in Section 7.3

### **5.3. Potential impact on railway tunnel beneath the site**

- 5.3.1 The proposed building has the potential to result in an increased stress on the existing Network Rail tunnel. The tunnel crown is situated circa 11m below the underside of the basement. Accordingly, it is considered that the impact to the tunnel from the scheme will be negligible. Nevertheless, Network Rail will be consulted, and approval sought, as the project progresses.



## 6 Ground Investigations

### 6.1. Scope

6.1.1 A ground investigation was undertaken in October 2020 and comprised:

- 3 no. boreholes undertaken using dynamic windowless sampling techniques to a maximum depth of 6m to confirm underlying ground conditions
- 1 no. hand excavated trial pit to expose the existing foundations of the garages

6.1.2 It should be noted that Network Rail would not permit a borehole extending beyond 6m unless the existing tunnel was surveyed. Given the anticipated ground conditions coupled with the cost and programme constraints of the project, the boreholes terminated at 6m.

### 6.2. Ground conditions encountered

6.2.1 Ground conditions in the vicinity of the proposed basement comprised Made Ground sequentially overlying Head and the London Clay Formation.

6.2.2 The Made Ground was notably thicker in exploratory hole WS01 (2.80m) in comparison to WS02 (0.50m) and WS03 (0.88m). Anecdotal evidence suggests that there is an existing drainage pipe from the middle of the two garages discharging to the sewer in the road. Accordingly, it is conjectured that WS01 was undertaken down the side of this existing drainage run.

6.2.3 Head was encountered in all of the exploratory holes to a depth of circa 4.20m. It was described as a soft to stiff brown occasionally mottled grey Clay with occasional gravels of flint and shells.

6.2.4 From 4.20m BGL, no flint was observed in the samples recovered from the borehole. Secondly, there was a notable increase in shear strength. Accordingly, it is interpreted that London Clay was encountered at circa 4.20m BGL to the base of the boreholes. It was typically described as a firm to stiff brown mottled grey silty Clay.

6.2.5 Groundwater was encountered at 3m BGL in WS01 but not encountered in WS02 or WS03. Subsequent monitoring recorded groundwater at 2.34m BGL and 3.20m BGL in WS01 and WS03 respectively. It is interpreted that flow rates will be relatively minor given the predominantly clayey nature of the soil.

### 6.3. Ground model

6.3.1 The following table summarises the ground model proposed for the site:

Stratum	Depth to top (m BGL)	Depth to base (m BGL)
Made Ground	0	1.00
Head	1.00	4.20
London Clay	4.20	>>6

**Table 6.3**

### 6.4. Existing foundations

6.4.1 The main dwellings at Nos. 12 and 14 Hampstead Hill Gardens have lower ground floors. It is estimated that the foundations for those buildings are at approximately 2.5m below ground level.

## 7 Engineering

### 7.1. Outline geotechnical design parameters

7.1.1 Relevant geotechnical parameters for London Clay have been derived from laboratory testing, technical standards, industry publications and wider literature. The following table summarises those parameters:

Parameter / property	Value	Derivation
Characteristic unit weight, $\gamma$ (kN/m <sup>3</sup> )	19	BS8004
Characteristic constant volume angle of shearing resistance, $\phi$ (°)	21	Literature
Characteristic undrained shear strength, $c_u$ (kN/m <sup>2</sup> )	40 + 8Z where z = depth below 4.2	In situ testing
Undrained modulus, $E_u$ (MN/m <sup>2</sup> )	17 + 3.4Z where z = depth below 4.2	Correlation with $c_u$ ( $E_u = 425c_u$ )

**Table 7.1a**

7.1.2 Head was encountered at the site and will be retained by the basement walls. The following parameters will be adopted:

Parameter / property	Value	Derivation
Characteristic unit weight, $\gamma$ (kN/m <sup>3</sup> )	18	BS8004
Characteristic constant volume angle of shearing resistance, $\phi$ (°)	20	Correlation with plasticity index

**Table 7.1b**

7.1.3 Made Ground associated with the general development of the site is anticipated to be encountered at shallow depth and would therefore be retained by the basement walls. It was typically encountered as Clay material and is conjectured to be derived from the Head and London Clay. Therefore the following parameters will be adopted for design of the retaining wall:

Parameter / property	Value	Derivation
Characteristic unit weight, $\gamma$ (kN/m <sup>3</sup> )	18	BS8004
Characteristic constant volume angle of shearing resistance, $\phi$ (°)	20	Assumed from to be derived from the Head / London Clay.

**Table 7.1c**

### 7.2. Outline temporary and permanent works proposals

7.2.1 The proposed development comprises demolition of the existing garages followed by the construction of a three storey building including single storey basement.

7.2.2 The proposed construction will adopt an underpinning technique to construct reinforced concrete L shaped retaining walls around the perimeter of the basement. A reinforced suspended concrete slab will then be constructed between the toes of the L shaped retaining wall sections.

7.2.3 The L shaped retaining walls will be founded on London Clay. Ultimate limit state analyses (bearing capacity) have been undertaken in accordance with BS EN 1997-1 (Eurocode 7) to derive the following values:


- Combination 1 – 230 kN/m<sup>2</sup>
- Combination 2 – 170 kN/m<sup>2</sup>

- 7.2.4 Excavation of the basement will cause an unloading of stress on the soil and consequently heave is likely to occur towards the centre of the basement and diminishing towards the perimeter walls. Ignoring boundary effects and therefore adopting a worst case scenario it is estimated that total heave will be less than 30mm, which comprises immediate heave of circa 10mm and long-term heave of 20mm. Accordingly, the structural design of the slab will account for this heave.

### **7.3. Ground movement and damage impact assessment**

- 7.3.1 Camden Planning Guidance – Basements, require that basement construction does not cause structural damage to neighbouring buildings. The risk of structural damage should be assessed using the Burland Scale and the classification must be no higher than Category 1 – very slight.
- 7.3.2 Ground movement analyses have been undertaken with the aid of computer software package XDisp Version 20.1 developed by OASYS. The software estimates the ground movements induced by basement excavation using the movement profile curves presented within CIRIA Report C760 or user specified movement profiles. The building damage is then assessed within the software against the damage criteria presented by Burland.
- 7.3.3 Construction of the basement will induce ground movements within the soil that have the potential to cause damage to neighbouring properties. Ground movement will occur due to the following activities:
- Construction of the underpins
  - Excavation of the basement leading to inward yield
  - Long term settlement of the soil due to the loads acting on the underpins
- 7.3.4 There is very limited published information on ground movements due to construction of underpins. However, assuming good construction practice and workmanship it is estimated that ground movement will be limited to 5mm of vertical movement and 5mm of horizontal movement per lift. It is further assumed that this will affect a zone extending 45° from the base of the underpin layer
- 7.3.5 It is assumed that the underpins will be founded on the London Clay at a depth of circa 4.50m BGL. It is assumed that the existing lower ground floors for Nos. 12 and 14 Hampstead Hill Gardens are at 2.50m BGL. On this basis the 'effective' depth of the excavation that has the potential to induce ground movement is 2.00m.
- 7.3.6 Benefits due to corner stiffening effects have been ignored in the analyses; accordingly, full plane strain conditions have been assumed at the corners as well.
- 7.3.7 Following discussion with Campbell Reith on previous projects ground movement due to excavation of the basement has been estimated with the aid of computer software package PDisp Version 20.0 developed by OASYS. Pre-defined ground movement curves within XDisp have not been used as this would then result in double counting the effects of the excavation.
- 7.3.8 Long term settlement of the soil due to the loads on the underpins has also been estimated with the aid of PDisp. Settlement beneath the neighbouring properties (Nos. 12 and 14 Hampstead Hill Gardens) has been assessed. These calculated displacements have been imported into XDisp and combined with the estimated ground movements due to underpin construction to determine a worst-case assessment.

- 7.3.9 The results are illustrated below and presented in detail in Appendix E alongside the input data:



- 7.3.10 The analysis indicates that damage will be limited to Burland Category 1. Nevertheless the excavation will be propped during excavation and the neighbouring properties monitored with appropriate trigger levels and control measures agreed prior to commencement of works.

## 7.4. Construction works controls

- 7.4.1 A detailed construction methodology, including appropriate control measures, has been developed by the structural engineer and is presented separately.

## **8 Basement Impact Assessment**

### **8.1. Ground Stability**

- 8.1.1 The basement will be founded on London Clay.
- 8.1.2 Ground movement analyses have been undertaken in accordance with CIRIA Report C760 with the aid of computer software package XDisp. Damage to surrounding structures has been assessed using the Burland scale and concluded that, with appropriate controls, the damage will be limited to Burland Category 1.
- 8.1.3 The site is generally flat. Ground levels fall to the east and therefore away from the proposed basement. Accordingly, the proposed works will not impact upon the current stability of the slope.

### **8.2. Hydrogeology and groundwater flooding**

- 8.2.1 The proposed development will have negligible impact to the wider hydrogeological environment.
- 8.2.2 Groundwater monitoring indicates that perched groundwater is present within the depth of the basement at about 2.8m below ground level. It is anticipated that groundwater flow rates will be relatively minimal given the clayey nature of materials encountered. Accordingly, groundwater flows encountered during construction, if any, will be collected via a sump and suitably discharged.


### **8.3. Hydrology, surface water flooding and sewer flooding**

- 8.3.1 The proposed development will have negligible impact to the wider hydrological environment.
- 8.3.2 The proposed development will not increase the likelihood of surface water or sewer flooding.






Neighbourhood extract from Ordnance Survey map



Town extract from Ordnance Survey map



Detail extract from Ordnance Survey map

Title	Scale	Drawing number
Site location plan	Not to scale	01





**Key**

WS

Approximate location of proposed borehole formed by Dynamic Sampling techniques

HP

Approximate location of hand pit excavation

P

Approximate location and orientation of photographic record

Approximate site boundary

**Notes**

Base drawing from topographical survey undertaken by Warner Surveys

A	First issue	AM	SC	ID	14.12.2020
REV	DESCRIPTION	PRODUCED BY	CHECKED BY	REVIEWED BY	DATE

soiltechnics

environmental • geotechnical • building fabric

PROJECT

14a Hampstead Hill Gardens, London

TITLE

Plan showing existing site features and approximate location of exploratory points

PROJECT NO.

STS5065

SCALE AT A3

1:125

DRAWING NO.

02

#### Qualifications

- Chartered Civil Engineer – Member of the Institution of Civil Engineers (2014)
- UK Registered Ground Engineering Professional (2014)
- National Grid G17 Civil Systems Approver – Geotechnics (2015)

#### Career History

Soiltechnics (2018 – Present)	<p>Position of Associate Technical Director with the following primary responsibilities:</p> <ul style="list-style-type: none"><li>• Provide technical direction to engineers throughout the life cycle of a project.</li><li>• Oversee engineers in the design and execution of ground investigations including scheduling of laboratory testing and subsequent derivation of ground model with geotechnical parameters.</li><li>• Supervise engineers undertaking calculations for a range of geotechnical problems including earth retaining structures, ground movement analyses and foundation assessments.</li><li>• Design and prepare specifications for earthworks control.</li><li>• Providing the role of Designer's Geotechnical Advisor in accordance with CD 622 Managing Geotechnical Risk.</li><li>• Preparing tenders for a range of Clients.</li><li>• Write and review Basement Impact Assessments, for submission as part of planning applications.</li></ul>
Jacobs (2009 – 2018)	<p>Position of graduate geotechnical engineer through to Principal Geotechnical Engineer held at Jacobs, Birmingham (UK). Attained competence and experience in the following areas:</p> <ul style="list-style-type: none"><li>• Deriving complex ground models combining topographical mapping, geological mapping and ground investigation data.</li><li>• Undertaking concept engineering through to detailed design for a number of geotechnical problems including slope stability, earthworks, foundation design, earth retaining structures and seepage related analyses.</li><li>• Designing and supervising ground investigations, scheduling laboratory testing and deriving geotechnical design parameters.</li><li>• Writing desk study reports, geotechnical interpretative and geotechnical design reports in accordance with Eurocode 7 and HD22/08 – Managing Geotechnical Risk.</li><li>• Contract management including tender submissions, producing fee estimates, programme of works, managing budgets and raising early warnings and compensation events.</li><li>• Acting as Client's representative to validate earthworks and other construction elements.</li><li>• Producing and maintaining geotechnical risk registers.</li><li>• Making presentations to technical and non-technical audiences.</li><li>• Management of incidents on site; including liaison with statutory bodies and the public.</li><li>• Discharging the duties of a Designer in accordance with CDM (2015) Regulations.</li></ul>

#### Project Experience (Key Roles)

A47 Highway Improvements	This project comprised the dualling of the A47 highway immediately west of Norwich and the realignment of a roundabout south west of Wisbech. As the GI Contractor's project manager Angus was responsible for the delivery of the ground investigation. Drawing upon his experiences as a designer Angus was able to advise the Client and designer the best ways of obtaining the GI data required for the design balancing cost, safety and geotechnical risk.
A46 Trenchless Crossing	The project comprises the installation of a new drainage pipe beneath the dual carriageway. Angus is the Designer's Geotechnical Advisor responsible for managing the geotechnical risks throughout the project and liaising with the Overseeing Organisation's Geotechnical Advisor and wider project team.
HS2 Gas Pipeline Diversions	Angus was the geotechnical project manager and, leading a team of engineers across three offices, he was responsible for the delivery of geotechnical design elements for each of the 23 diversions. The project faced a variety of ground conditions, environmental constraints and engineering challenges including trenchless crossing beneath watercourses, railways and highways. Angus provided technical consistency across the project incorporating lessons learned from other diversions where possible. Angus led the project from Desk Study phase through to ground investigation, interpretation and preparation of geotechnical design reports in accordance with National Grid Specification CE/2. He advised the Client throughout the commission with respect to geotechnical issues and frequently offered cost effective ways of optimising the design to improve buildability and safety.
Jackfield Stabilisation	<p>Angus was the lead Geotechnical Engineer for the stabilisation of a 1 million m<sup>3</sup> shallow translational landslide within a UNESCO World Heritage Site. He was responsible for reviewing geotechnical data, determining the failure mechanism, optioneering at outline design and supervising a team of graduate engineers during detailed design. Furthermore, he provided site supervision and validation of the design throughout the construction stage and reviewing Contractor's remediation proposals to address defects.</p> <p>Angus led a collaborative work effort with the Contractor's temporary works designer to ensure sufficient knowledge transfer between geotechnical specialists and ensuring safe working methods were proposed within an active landslide environment.</p>
Netherton Tunnel Remediation	This scheme involved the remediation of a 3km masonry lined canal tunnel. He was the Project Engineer responsible for reviewing of 150 years' worth of data before forensically engineering the tunnel to determine the failure mechanism. He led a survey team to establish construction joints within the tunnel and undertook outline design of remediation measures.

#### Publications

Wilson, A. K. & Ashton, J., 2012. An engineering geological model of the Conwy Valley, east of Dolgarrog, In, Nichol, D. & Bassett, M.G. (Eds), Urban Geology in Wales: 4. National Museum of Wales Geological Series No. 27, Cardiff, 2015

# Chord Environmental Ltd

Angus Wilson  
Soiltechnics Ltd  
Cedar Barn  
White Lodge  
Walgrave  
Northampton  
NN6 9PY

**Your Ref:** 14A Hampstead Hill Gardens  
**Our Ref:** 1127/LJE151220

For the attention of: Angus Wilson

15<sup>th</sup> December 2020

## **Proposed Basement at 14A Hampstead Hill Gardens, London, NW3 2PL: BIA Review**

Dear Angus,

Further to your instruction to proceed on behalf your client (Price and Myers on behalf of Mr Alon Mekel) I have undertaken a review of the Basement Impact Assessment (BIA) prepared by Soiltechnics Ltd for the proposed basement development at 14A Hampstead Hill Gardens, London NW3 2PL.

I have reviewed the design of the proposed basement development, together with the information presented within the above documents, against the requirements of the Camden BIA guidance set out within Policy A5 (Basements) of the Camden Local Plan (2017), Camden Planning Guidance on basements (adopted March 2018) and the Camden geological, hydrogeological and hydrological study report 'Guidance for subterranean development ', produced by Arup (2011) on behalf of the London Borough of Camden.

Chord Environmental Ltd specialise in the provision of hydrogeological services with extensive experience in the UK supporting both private and public sector clients. I am a geologist and hydrogeologist and have a BSc. in geology from the University of Bristol, a MSc. in hydrogeology from the University of East Anglia and am also a Chartered Geologist and fellow of the Geological Society. I am Managing Director at Chord Environmental and was previously a Technical Director with Paulex Environmental Consulting and managed Hyder Consulting (UK) Ltd's groundwater team.

I have been a hydrogeologist for over 20 years. During that time I have advised on over 150 basement developments. Much of my career has been spent assessing the impact of development on the quality and quantity of groundwater resources. I have worked for both promoters and regulators of schemes and have acted as an expert witness for the Highways Agency and on BIA schemes.

## **Development proposal**

The site is currently occupied by two single garages located between a four storey and three storey residential property. The site is located on the side of a hill at an elevation of 72 m above Ordnance Datum (OD) with the ground falling away to the east at a gradient of 1:15.

The surrounding area is dominated by residential properties of masonry construction, many of which have a basement or lower ground floor. Hampstead Hill Tunnel which carries the North London Line runs directly beneath the site at a depth of 14m.

The proposed project comprises the demolition of the existing garages followed by construction of a three storey property with a single level basement.

## **Environmental Site Setting**

The BIA screening assessment has identified 14A Hampstead Hill Gardens to be underlain by the Eocene London Clay as shown on the British Geological Survey 1:50,000 scale map (Sheet 256 – North London) to a depth of c.80m. The London Clay is classified as Unproductive Strata by the Environment Agency, strata with low permeability that have negligible significance for water supply or base flow to rivers. The very low permeability of the London Clay results in very low rates of rainfall infiltration and correspondingly, very high rates of rainfall runoff. The London Clay, together with the clays of the Eocene Lambeth Group, acts as an effectively impermeable confining layer over the Chalk which lies at a depth of over 100m beneath the site.

The closest surface water feature, based on the Ordnance Survey 1:25,000 scale map, is the southern-most Hampstead Pond which lies approximately 350m to the north east of the site. Figure 11 of the “Camden Geological, Hydrogeological and Hydrological Study”, shows 14A Hampstead Hill Gardens to lie between the former headwaters of the rivers Fleet and Tyburn which ran over 300m to the north east and 450m south west of the proposed development respectively. The Tyburn and Fleet are now culverted and discharge to the Thames.

The proposed 14A Hampstead Hill Gardens development does not lie within an area of fluvial or tidal flood risk as designated by the Environment Agency and was not identified as being on one of the roads affected by the surface water flooding events of the area which occurred during 1975 and 2002 (Figure 15 of the Arup report 2010).

Screening assessments have been undertaken to satisfy Stage 1 of Camden Planning Guidance – Basements

## Subterranean (Groundwater) Flow Screening Assessment

I have commented on the answer to each question below.

- **Question 1a: Is the site located directly above an aquifer?**

As the Site is mapped as being underlain by a significant thickness of London Clay, designated as Unproductive Strata by the Environment Agency, I agree it is not located above an aquifer and the hydrogeology of the area is well understood.

- **Question 1b: Will the proposed basement extend beneath the water table surface?**

No. The hydraulic properties of the very low permeability and cohesive London Clay do not allow it to support a water table and transmit groundwater in any significant quantities under normal hydraulic gradients.

- **Question 2: Is the site within 100m of a watercourse, well (used/disused) or potential spring line?**

No mapped surface water features are present within 100m of the site and the London Clay is not capable of providing groundwater baseflow to watercourses. The proposed basement would therefore not act to prevent groundwater flow to any watercourses, wells or spring lines.

- **Question 3: Is the site within the catchment of the pond chains on Hampstead Heath?**

The Site is located more than 300m south west, and down topographic gradient, of the Hampstead Heath ponds and therefore lies outside their hydrological catchment area (refer to Figure 14 of the Camden Geological, Hydrogeological and Hydrological Study).

- **Question 4: Will the proposed development result in a change in the proportion of hard surfaced / paved area?**

No. The basement would lie beneath the existing garage footprints and existing paved areas.

- **Question 5: As part of the site drainage, will more surface water (e.g. rainfall and run-off) than at present be discharged to ground (e.g. via soakaways and/or SUDS)?**

No. There will be negligible change to the existing drainage arrangement.

- **Question 6: Is the lowest point of the proposed excavation (allowing for any drainage and foundation space under the basement floor) close to, or lower than, the mean water level in any local pond (not just the pond chains on Hampstead Heath) or spring line?**

No - there are no mapped local groundwater dependent ponds or spring lines present within 100m of the Site. This is consistent with the geology and hydrogeology of the area.



## **Slope Stability Assessment**

The BIA screening, scoping and risk assessments have followed the Camden Planning Guidance - Basements criteria and screening questions. The potential ground movement issues raised by the screening and scoping exercises have been appropriately addressed by Angus Wilson (C.Eng) of Soiltechnics Ltd within the BIA report and no areas of concern relating to the proposed development were identified.

## **Surface Flow and Flooding Assessment**

The BIA screening, scoping and risk assessments have followed the Camden Planning Guidance - Basements criteria and screening questions. No potential surface flow or flooding issues were raised by the screening and scoping exercise and no areas of concern relating to the proposed development were identified.

## **Conclusions**

The BIA report has appropriately characterised 14A Hampstead Hill Gardens with respect to its geological and groundwater site setting. As the site is underlain by low permeability London Clay, the geological and hydrogeological setting of 14A Hampstead Hill Gardens is not sensitive with respect to groundwater resources or flow. Isolated pockets of groundwater may be encountered during excavation and some form of groundwater control may be required (e.g. sump pumping) however significant inflows of groundwater are not anticipated.


The purpose of the Basement Impact subterranean or groundwater flow assessment is to identify the potential for the proposed basement development to cause groundwater impacts and subsequently identify areas which require further investigation. The proposed development would be constructed within a significant thickness of London Clay and no potential adverse groundwater impacts have been established by these assessments.


Yours sincerely,



**John Evans BSc MSc CGeol.**

Director





LOCATION PLAN

1:1250 @A3



0      10      20      30      40      50

SCALE: 1:1250

BLOCK PLAN

1:500 @A3



SCALE: 1:1250

 **ECHLIN**

3RD FLOOR,  
NEWCOMBE HOUSE  
45 NOTTING HILL GATE  
LONDON W11 3LQ  
+44 (0) 20 7349 9610  
ECHLINLONDON.COM

DO NOT SCALE FROM THIS DRAWING. ALL DIMENSIONS TO BE CHECKED ON SITE PRIOR TO COMMENCEMENT OF ANY WORKS OR PREPARATION OF SHOP DRAWINGS. THE SIZING AND DIMENSIONS OF ALL STRUCTURAL AND SERVICE ELEMENTS MUST ALWAYS BE CHECKED AGAINST THE RELEVANT ENGINEERS DRAWINGS. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL OTHER CONSULTANTS INFORMATION. IF THIS DRAWING HAS BEEN TRANSMITTED ELECTRONICALLY, THE ABOVE STATEMENTS ALSO APPLY. © ECHLIN 2015

PROJECT	
---------	--

DRAWING TITLE

PROPOSED LOCATION & BLOCK PLAN


STATUS	PRE-PLANNING APPLICATION
--------	--------------------------

SCALE 1:100 @A3	JOB NUMBER 2112	DRAWN BY SC	CHECKED SC
--------------------	--------------------	----------------	---------------

DRAWING No 2112/PL/100	DATE 14.12.2019	REVISION -
---------------------------	--------------------	---------------



## 1:100 @A3



DRAWING No	DATE	REVISION
2112/PL/110	14.12.2019	-



1:100 @A3



71.8 M<sup>2</sup>  
772.8 SQ F

DO NOT SCALE FROM THIS DRAWING. ALL DIMENSIONS TO BE CHECKED ON SITE PRIOR TO COMMENCEMENT OF ANY WORKS OR PREPARATION OF SHOP DRAWINGS. THE SIZING AND DIMENSIONS OF ALL STRUCTURAL AND SERVICE ELEMENTS MUST ALWAYS BE CHECKED AGAINST THE RELEVANT ENGINEERS DRAWINGS. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL OTHER CONSULTANTS INFORMATION. IF THIS DRAWING HAS BEEN TRANSMITTED ELECTRONICALLY, THE ABOVE STATEMENTS ALSO APPLY. © ECHLIN 2005

PROJECT	14A HAMPSTEAD HILL GARDENS, NW3 2PL
---------	-------------------------------------

DRAWING TITLE

PROPOSED GROUND PLAN

STATUS	PRE-PLANNING APPLICATION
--------	--------------------------

SCALE 1:100 @A3	JOB NUMBER 2112	DRAWN BY SC	CHECKED SC
--------------------	--------------------	----------------	---------------

DRAWING No 2112/PL/III	DATE 14.12.2019	REVISION -
---------------------------	--------------------	---------------



DO NOT SCALE FROM THIS DRAWING. ALL DIMENSIONS TO BE CHECKED ON SITE PRIOR TO COMMENCEMENT OF ANY WORKS OR PREPARATION OF SHOP DRAWINGS. THE SIZING AND DIMENSIONS OF ALL STRUCTURAL AND SERVICE ELEMENTS MUST ALWAYS BE CHECKED AGAINST THE RELEVANT ENGINEERS DRAWINGS. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL OTHER CONSULTANTS INFORMATION. IF THIS DRAWING HAS BEEN TRANSMITTED ELECTRONICALLY, THE ABOVE STATEMENTS ALSO APPLY. © EDWIN 2015

SCALE 1:100 @A3	JOB NUMBER 2112	DRAWN BY SC	CHECKED SC
--------------------	--------------------	----------------	---------------

DRAWING No 2112/PL/112	DATE 14.12.2019	REVISION -
---------------------------	--------------------	---------------

SCALE: 1:100

61.5 M<sup>2</sup>  
662 SQ F







14A HAMPSTEAD HILL GARDENS



PROPOSED REAR ELEVATIONS

1:100 @A3

0 1 2 3 4 5  
SCALE: 1:100

14A HAMPSTEAD HILL GARDENS



PROPOSED SECTION CC

1:100 @A3

KEY

1. WHITE CONCRETE BAND
2. WHITE BRICK WITH FLUSH WHITE MORTAR
3. BRONZE WINDOW FRAME WITH STRUCTURAL GLAZING
4. BRONZE FRAME & STRUCTURAL GLAZING
5. GLASS BALUSTRADE
6. GREENWALL

REV DATE DESCRIPTION

NOTES:

**ECHLIN**

5RD FLOOR,  
NEWCOMBE HOUSE,  
45 NOTTING HILL, GATE  
LONDON W11 3LQ  
+44 (0) 20 7369 9610  
ECHLIN.LONDON.COM

DO NOT SCALE FROM THIS DRAWING. ALL DIMENSIONS TO BE CHECKED ON SITE PRIOR TO COMMENCEMENT OF ANY WORKS OR PREPARATION OF SHOP DRAWINGS. THE SIZING AND DIMENSIONS OF ALL STRUCTURAL AND SERVICE ELEMENTS MUST ALWAYS BE CHECKED AGAINST THE RELEVANT ENGINEER'S DRAWINGS. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL OTHER CONSULTANTS INFORMATION. IF THIS DRAWING HAS BEEN TRANSMITTED ELECTRONICALLY, THE ABOVE STATEMENTS ALSO APPLY. © ECHLIN 2015

PROJECT  
14A HAMPSTEAD HILL GARDENS, NW3 2PL

DRAWING TITLE  
PROPOSED REAR ELEVATION + SECTION CC

STATUS  
PRE-PLANNING APPLICATION

SCALE 1:100 @A3	JOB NUMBER 2112	DRAWN BY SC	CHECKED SC
--------------------	--------------------	----------------	---------------

DRAWING No 2112/PL/121	DATE 14.12.2019	REVISION -
---------------------------	--------------------	---------------

Architectural floor plan of a three-story house. The plan is divided into three horizontal sections representing different floors, indicated by dashed lines and labels on the right: SECOND FLOOR, FIRST FLOOR, and GROUND FLOOR. A fourth level, BASEMENT, is also indicated at the bottom right.

**Second Floor:**

- SI: BEDROOM (top left)
- SKYLIGHT (top center)
- S4: BEDROOM (top right)

**First Floor:**

- F1: MASTER BEDROOM (middle left)
- Stairs (middle center)
- F5: BEDROOM (middle right)

**Ground Floor:**

- PATIO (far left)
- G5: SUNROOM (left of center)
- VOID (between sunroom and dining)
- G4: DINING (center)
- Stairs (between dining and reception)
- G1: RECEPTION (right of center)

**Basement:**


- B7: ENSUITE (bottom left)
- B6: DRESSING (bottom left-center)
- B5: STUDY (bottom center-left)
- Stairs (bottom center)
- B1: FAMILY ROOM (bottom center-right)
- B4: BEDROOM (bottom right)

Other labels include "REAR GARDEN" on the far left and "HAMPSTEAD HILL GARDENS" on the far right.

1:100 @A3

[illegible]

## 14A HAMPSTEAD HILL GARDENS



## PROPOSED SECTION BB

1:100 @A3



SCALE: 1:100

[illegible]

# Asset location search



## Property Searches

Soiltechnics Limited  
Cedar Barn  
White Lodge  
WALGRAVE  
NN6 9PY

**Search address supplied**      NW3 2PL

**Your reference**                      STS5065

**Our reference**                      ALS/ALS Standard/2020\_4185339

**Search date**                          29 April 2020

### Knowledge of features below the surface is essential for every development

The benefits of this knowledge not only include ensuring due diligence and avoiding risk, but also being able to ascertain the feasibility of any development.

Did you know that Thames Water Property Searches can also provide a variety of utility searches including a more comprehensive view of utility providers' assets (across up to 35-45 different providers), as well as more focused searches relating to specific major utility companies such as National Grid (gas and electric).

Contact us to find out more.



Thames Water Utilities Ltd  
Property Searches, PO Box 3189, Slough SL1 4WW  
DX 151280 Slough 13



[searches@thameswater.co.uk](mailto:searches@thameswater.co.uk)  
[www.thameswater-propertysearches.co.uk](http://www.thameswater-propertysearches.co.uk)



0845 070 9148



**Search address supplied:** NW3 2PL

Dear Sir / Madam

**An Asset Location Search is recommended when undertaking a site development.** It is essential to obtain information on the size and location of clean water and sewerage assets to safeguard against expensive damage and allow cost-effective service design.

The following records were searched in compiling this report: - the map of public sewers & the map of waterworks. Thames Water Utilities Ltd (TWUL) holds all of these.

This search provides maps showing the position, size of Thames Water assets close to the proposed development and also manhole cover and invert levels, where available.

Please note that none of the charges made for this report relate to the provision of Ordnance Survey mapping information. The replies contained in this letter are given following inspection of the public service records available to this company. No responsibility can be accepted for any error or omission in the replies.

You should be aware that the information contained on these plans is current only on the day that the plans are issued. The plans should only be used for the duration of the work that is being carried out at the present time. Under no circumstances should this data be copied or transmitted to parties other than those for whom the current work is being carried out.

Thames Water do update these service plans on a regular basis and failure to observe the above conditions could lead to damage arising to new or diverted services at a later date.

### Contact Us

If you have any further queries regarding this enquiry please feel free to contact a member of the team on 0845 070 9148, or use the address below:

Thames Water Utilities Ltd  
Property Searches  
PO Box 3189  
Slough  
SL1 4WW

Email: [searches@thameswater.co.uk](mailto:searches@thameswater.co.uk)

Web: [www.thameswater-propertysearches.co.uk](http://www.thameswater-propertysearches.co.uk)

### Waste Water Services

**Please provide a copy extract from the public sewer map.**

Enclosed is a map showing the approximate lines of our sewers. Our plans do not show sewer connections from individual properties or any sewers not owned by Thames Water unless specifically annotated otherwise. Records such as "private" pipework are in some cases available from the Building Control Department of the relevant Local Authority.

Where the Local Authority does not hold such plans it might be advisable to consult the property deeds for the site or contact neighbouring landowners.

This report relates only to sewerage apparatus of Thames Water Utilities Ltd, it does not disclose details of cables and or communications equipment that may be running through or around such apparatus.

The sewer level information contained in this response represents all of the level data available in our existing records. Should you require any further Information, please refer to the relevant section within the 'Further Contacts' page found later in this document.

For your guidance:

- The Company is not generally responsible for rivers, watercourses, ponds, culverts or highway drains. If any of these are shown on the copy extract they are shown for information only.
- Any private sewers or lateral drains which are indicated on the extract of the public sewer map as being subject to an agreement under Section 104 of the Water Industry Act 1991 are not an 'as constructed' record. It is recommended these details be checked with the developer.

### Clean Water Services

**Please provide a copy extract from the public water main map.**

Enclosed is a map showing the approximate positions of our water mains and associated apparatus. Please note that records are not kept of the positions of individual domestic supplies.

For your information, there will be a pressure of at least 10m head at the outside stop valve. If you would like to know the static pressure, please contact our Customer Centre on 0800 316 9800. The Customer Centre can also arrange for a full flow and pressure test to be carried out for a fee.





For your guidance:

- Assets other than vested water mains may be shown on the plan, for information only.
- If an extract of the public water main record is enclosed, this will show known public water mains in the vicinity of the property. It should be possible to estimate the likely length and route of any private water supply pipe connecting the property to the public water network.

## **Payment for this Search**

A charge will be added to your suppliers account.

### Further contacts:

#### Waste Water queries

Should you require verification of the invert levels of public sewers, by site measurement, you will need to approach the relevant Thames Water Area Network Office for permission to lift the appropriate covers. This permission will usually involve you completing a TWOSA form. For further information please contact our Customer Centre on Tel: 0845 920 0800. Alternatively, a survey can be arranged, for a fee, through our Customer Centre on the above number.

If you have any questions regarding sewer connections, budget estimates, diversions, building over issues or any other questions regarding operational issues please direct them to our service desk. Which can be contacted by writing to:

Developer Services (Waste Water)  
Thames Water  
Clearwater Court  
Vastern Road  
Reading  
RG1 8DB


Tel: 0800 009 3921  
Email: [developer.services@thameswater.co.uk](mailto:developer.services@thameswater.co.uk)

#### Clean Water queries

Should you require any advice concerning clean water operational issues or clean water connections, please contact:

Developer Services (Clean Water)  
Thames Water  
Clearwater Court  
Vastern Road  
Reading  
RG1 8DB

Tel: 0800 009 3921  
Email: [developer.services@thameswater.co.uk](mailto:developer.services@thameswater.co.uk)



The width of the displayed area is 200 m and the centre of the map is located at OS coordinates 527035,185507  
The position of the apparatus shown on this plan is given without obligation and warranty, and the accuracy cannot be guaranteed. Service pipes are not shown but their presence should be anticipated. No liability of any kind whatsoever is accepted by Thames Water for any error or omission. The actual position of mains and services must be verified and established on site before any works are undertaken.

Based on the Ordnance Survey Map with the Sanction of the controller of H.M. Stationery Office, License no. 100019345 Crown Copyright Reserved.

NB. Levels quoted in metres Ordnance Newlyn Datum. The value -9999.00 indicates that no survey information is available

Manhole Reference	Manhole Cover Level	Manhole Invert Level
1404	n/a	n/a
1407	70.52	68.66
1501	68.17	64.89
0501	n/a	n/a
9501	75.45	n/a
1602	68.74	65.26
0602	69.01	65.28
0401	n/a	n/a
041C	n/a	n/a
041B	n/a	n/a
941A	n/a	n/a
9401	78.9	74.93
041A	n/a	n/a
9402	n/a	n/a
The position of the apparatus shown on this plan is given without obligation and warranty, and the accuracy cannot be guaranteed. Service pipes are not shown but their presence should be anticipated. No liability of any kind whatsoever is accepted by Thames Water for any error or omission. The actual position of mains and services must be verified and established on site before any works are undertaken.		



# ALS Sewer Map Key

## Public Sewer Types (Operated & Maintained by Thames Water)

	<b>Foul:</b> A sewer designed to convey waste water from domestic and industrial sources to a treatment works.		Trunk Foul
	<b>Surface Water:</b> A sewer designed to convey surface water (e.g. rain water from roofs, yards and car parks) to rivers or watercourses.		Trunk Surface Water
	<b>Combined:</b> A sewer designed to convey both waste water and surface water from domestic and industrial sources to a treatment works.		Trunk Combined
	Storm Relief		Bio-solids (Sludge)
	Vent Pipe		Proposed Thames Water Foul Sewer
	Proposed Thames Surface Water Sewer		Proposed Thames Water Foul Sewer
	Gallery		Foul Rising Main
	Surface Water Rising Main		Combined Rising Main
	Sludge Rising Main		Proposed Thames Water Rising Main
	Vacuum		

### Notes:

- 1) All levels associated with the plans are to Ordnance Datum Newlyn.
- 2) All measurements on the plans are metric.
- 3) Arrows (on gravity fed sewers) or flecks (on rising mains) indicate direction of flow.
- 4) Most private pipes are not shown on our plans, as in the past, this information has not been recorded.
- 5) 'na' or '0' on a manhole level indicates that data is unavailable.

## Sewer Fittings

A feature in a sewer that does not affect the flow in the pipe. Example: a vent is a fitting as the function of a vent is to release excess gas.

	Air Valve
	Dam Chase
	Fitting
	Meter
	Vent Column

## Operational Controls

A feature in a sewer that changes or diverts the flow in the sewer. Example: A hydrobrake limits the flow passing downstream.

	Control Valve
	Drop Pipe
	Ancillary
	Weir

## End Items

End symbols appear at the start or end of a sewer pipe. Examples: an Undefined End at the start of a sewer indicates that Thames Water has no knowledge of the position of the sewer upstream of that symbol, Outfall on a surface water sewer indicates that the pipe discharges into a stream or river.

	Outfall
	Undefined End
	Inlet

## Other Symbols

Symbols used on maps which do not fall under other general categories

	Public/Private Pumping Station
	Change of characteristic indicator (C.O.C.I.)
	Invert Level
	Summit

### Areas


Lines denoting areas of underground surveys, etc.

	Agreement
	Operational Site
	Chamber
	Tunnel
	Conduit Bridge

## Other Sewer Types (Not Operated or Maintained by Thames Water)

	Foul Sewer		Surface Water Sewer
	Combined Sewer		Gully
	Culverted Watercourse		Proposed
			Abandoned Sewer

- 6) The text appearing alongside a sewer line indicates the internal diameter of the pipe in millimetres. Text next to a manhole indicates the manhole reference number and should not be taken as a measurement. If you are unsure about any text or symbology present on the plan, please contact a member of Property Insight on 0845 070 9148.



The width of the displayed area is 200 m and the centre of the map is located at OS coordinates 527035, 185507.  
The position of the apparatus shown on this plan is given without obligation and warranty, and the accuracy cannot be guaranteed. Service pipes are not shown but their presence should be anticipated. No liability of any kind whatsoever is accepted by Thames Water for any error or omission. The actual position of mains and services must be verified and established on site before any works are undertaken.

Based on the Ordnance Survey Map with the Sanction of the controller of H.M. Stationery Office, License no. 100019345 Crown Copyright Reserved.





## ALS Water Map Key

### Water Pipes (Operated & Maintained by Thames Water)

4"	<b>Distribution Main:</b> The most common pipe shown on water maps. With few exceptions, domestic connections are only made to distribution mains.
16"	<b>Trunk Main:</b> A main carrying water from a source of supply to a treatment plant or reservoir, or from one treatment plant or reservoir to another. Also a main transferring water in bulk to smaller water mains used for supplying individual customers.
3" SUPPLY	<b>Supply Main:</b> A supply main indicates that the water main is used as a supply for a single property or group of properties.
3" FIRE	<b>Fire Main:</b> Where a pipe is used as a fire supply, the word FIRE will be displayed along the pipe.
3" METERED	<b>Metered Pipe:</b> A metered main indicates that the pipe in question supplies water for a single property or group of properties and that quantity of water passing through the pipe is metered even though there may be no meter symbol shown.
	<b>Transmission Tunnel:</b> A very large diameter water pipe. Most tunnels are buried very deep underground. These pipes are not expected to affect the structural integrity of buildings shown on the map provided.
	<b>Proposed Main:</b> A main that is still in the planning stages or in the process of being laid. More details of the proposed main and its reference number are generally included near the main.

PIPE DIAMETER	DEPTH BELOW GROUND
Up to 300mm (12")	900mm (3')
300mm - 600mm (12" - 24")	1100mm (3' 8")
600mm and bigger (24" plus)	1200mm (4')

### Valves

	General Purpose Valve
	Air Valve
	Pressure Control Valve
	Customer Valve

### Hydrants

	Single Hydrant
--	----------------

### Meters

	Meter
--	-------

### End Items

Symbol indicating what happens at the end of a water main.

	Blank Flange
	Capped End
	Emptying Pit
	Undefined End
	Manifold
	Customer Supply
	Fire Supply

### Operational Sites

	Booster Station
	Other
	Other (Proposed)
	Pumping Station
	Service Reservoir
	Shaft Inspection
	Treatment Works
	Unknown
	Water Tower

### Other Symbols

	Data Logger
--	-------------

### Other Water Pipes (Not Operated or Maintained by Thames Water)

	<b>Other Water Company Main:</b> Occasionally other water company water pipes may overlap the border of our clean water coverage area. These mains are denoted in purple and in most cases have the owner of the pipe displayed along them.
	<b>Private Main:</b> Indicates that the water main in question is not owned by Thames Water. These mains normally have text associated with them indicating the diameter and owner of the pipe.



## Terms and Conditions

All sales are made in accordance with Thames Water Utilities Limited (TWUL) standard terms and conditions unless previously agreed in writing.

1. All goods remain in the property of Thames Water Utilities Ltd until full payment is received.
2. Provision of service will be in accordance with all legal requirements and published TWUL policies.
3. All invoices are strictly due for payment 14 days from due date of the invoice. Any other terms must be accepted/agreed in writing prior to provision of goods or service, or will be held to be invalid.
4. Thames Water does not accept post-dated cheques-any cheques received will be processed for payment on date of receipt.
5. In case of dispute TWUL's terms and conditions shall apply.
6. Penalty interest may be invoked by TWUL in the event of unjustifiable payment delay. Interest charges will be in line with UK Statute Law 'The Late Payment of Commercial Debts (Interest) Act 1998'.
7. Interest will be charged in line with current Court Interest Charges, if legal action is taken.
8. A charge may be made at the discretion of the company for increased administration costs.

A copy of Thames Water's standard terms and conditions are available from the Commercial Billing Team (cashoperations@thameswater.co.uk).

We publish several Codes of Practice including a guaranteed standards scheme. You can obtain copies of these leaflets by calling us on 0800 316 9800

If you are unhappy with our service you can speak to your original goods or customer service provider. If you are not satisfied with the response, your complaint will be reviewed by the Customer Services Director. You can write to her at: Thames Water Utilities Ltd. PO Box 492, Swindon, SN38 8TU.

If the Goods or Services covered by this invoice falls under the regulation of the 1991 Water Industry Act, and you remain dissatisfied you can refer your complaint to Consumer Council for Water on 0121 345 1000 or write to them at Consumer Council for Water, 1st Floor, Victoria Square House, Victoria Square, Birmingham, B2 4AJ.

### Ways to pay your bill

Credit Card	BACS Payment	Telephone Banking	Cheque
Call <b>0845 070 9148</b> quoting your invoice number starting CBA or ADS / OSS	Account number <b>90478703</b> Sort code <b>60-00-01</b> A remittance advice must be sent to: <b>Thames Water Utilities Ltd., PO Box 3189, Slough SL1 4WW.</b> or email <a href="mailto:ps.billing@thameswater.co.uk">ps.billing@thameswater.co.uk</a>	By calling your bank and quoting: Account number <b>90478703</b> Sort code <b>60-00-01</b> and your invoice number	Made payable to ' <b>Thames Water Utilities Ltd</b> ' Write your Thames Water account number on the back. Send to: <b>Thames Water Utilities Ltd., PO Box 3189, Slough SL1 4WW</b> or by DX to <b>151280 Slough 13</b>

Thames Water Utilities Ltd Registered in England & Wales No. 2366661 Registered Office Clearwater Court, Vastern Rd, Reading, Berks, RG1 8DB.


**Enquirer**

Name	Miss Alexa Band	Phone	01604 781877
Company	Soiltechnics	Mobile	Not Supplied
Address	Cedar Barn White Lodge Walgrave Northamptonshire NN6 9PY		
Email	Alexa.Band@soiltechnics.net		

**Enquiry Details**

Scheme/Reference	STS5065		
Enquiry type	Initial Enquiry	Work category	Development Projects
Start date	30/04/2020	Work type	Commercial/industrial
End date	30/04/2020	Site size	50 metres diameter
Searched location	XY= 527040, 185515	Work type buffer*	25 metres
Confirmed location	527040 185515		
Site Contact Name	Not Supplied	Site Phone No	Not Supplied
Description of Works	Not Supplied		

\* The WORK TYPE BUFFER is a distance added to your search area based on the Work type you have chosen.

**Site Map**


## Asset Owners

**Terms and Conditions.** Please note that this enquiry is subject always to our standard terms and conditions available at [www.lineasearchbeforeudig.co.uk](http://www.lineasearchbeforeudig.co.uk) ("Terms of Use") and the disclaimer at the end of this document. Please note that in the event of any conflict or ambiguity between the terms of this Enquiry Confirmation and the Terms of Use, the Terms of Use shall take precedence.

**Notes.** Please ensure your contact details are correct and up to date on the system in case the LSBUD Members need to contact you.

**Validity and search criteria.** The results of this enquiry are based on the confirmed information you entered and are valid only as at the date of the enquiry. It is your responsibility to ensure that the Enquiry Details are correct, and LineasearchbeforeUdig accepts no responsibility for any errors or omissions in the Enquiry Details or any consequences thereof. LSBUD Members update their asset information on a regular basis so you are advised to consider this when undertaking any works. It is your responsibility to choose the period of time after which you need to resubmit any enquiry but the maximum time (after which your enquiry will no longer be dealt with by the LSBUD Helpdesk and LSBUD Members) is 28 days. If any details of the enquiry change, particularly including, but not limited to, the location of the work, then a further enquiry must be made.

**Asset Owners & Responses.** Please note the enquiry results include the following:

1. "LSBUD Members" who are asset owners who have registered their assets on the LSBUD service.
2. "Non LSBUD Members" are asset owners who have not registered their assets on the LSBUD service but LSBUD is aware of their existence. Please note that there could be other asset owners within your search area.

Below are three lists of asset owners:

1. LSBUD Members who have assets registered within your search area. ("Affected")
  - a. These LSBUD Members will either:
    - i. Ask for further information ("Email Additional Info" noted in status). The additional information includes: Site contact name and number, Location plan, Detailed plan (minimum scale 1:2500), Cross sectional drawings (if available), Work Specification.
    - ii. Respond directly to you ("Await Response"). In this response they may either send plans directly to you or ask for further information before being able to do so, particularly if any payments or authorisations are required.
2. LSBUD Members who do not have assets registered within your search area. ("Not Affected")
3. Non LSBUD Members who may have assets within your search area. Please note that this list is not exhaustive and all details are provided as a guide only. It is your responsibility to identify and consult with all asset owners before proceeding.

**National Grid.** Please note that the LSBUD service only contains information on National Grid's Gas above 7 bar asset, all National Grid Electricity Transmission assets and National Grid's Gas Distribution Limited above 2 bar asset.

For National Grid Gas Distribution Ltd below 2 bar asset information please go to [www.beforeyoudig.nationalgrid.com](http://www.beforeyoudig.nationalgrid.com)

**LSBUD Members who have assets registered on the LSBUD service within the vicinity of your search area.**

### List of affected LSBUD members

Asset Owner	Phone/Email	Emergency Only	Status
UK Power Networks	08000565866	08000565866	Await response

**LSBUD Members who do not have assets registered on the LSBUD service within the vicinity of your search area. Please be aware that LSBUD Members make regular changes to their assets and this list may vary for new enquiries in the same area.**

### List of not affected LSBUD members

AWE Pipeline	Balfour Beatty Investments Limited	BOC Limited (A Member of the Linde Group)
BP Exploration Operating Company Limited	BPA	Carrington Gas Pipeline
CATS Pipeline c/o Wood Group PSN	Cemex	Centrica Storage Ltd
Chrysaor Production (UK) Limited	CLH Pipeline System Ltd	CNG Services Ltd
Concept Solutions People Ltd	ConocoPhillips (UK) Teesside Operator Ltd	Diamond Transmission Corporation
DIO (MOD Abandoned Pipelines)	Drax Group	E.ON UK CHP Limited
EirGrid	Electricity North West Limited	ENI & Himor c/o Penspen Ltd
EnQuest NNS Limited	EP Langage Limited	ESP Utilities Group
ESSAR	Esso Petroleum Company Limited	Fulcrum Pipelines Limited
Gamma	Gateshead Energy Company	Gigaclear Ltd
Gtt	Heathrow Airport LTD	Humbly Grove Energy
IGas Energy	INEOS FPS Pipelines	INEOS Manufacturing (Scotland and TSEP)
INOVYN Enterprises Limited	Intergen (Coryton Energy or Spalding Energy)	Mainline Pipelines Limited
Manchester Jetline Limited	Manx Cable Company	Marchwood Power Ltd (Gas Pipeline)
Melbourn Solar Limited	Murphy Utility Assets	National Grid Gas (Above 7 bar), National Grid Gas Distribution Limited (Above 2 bar) and National Grid Electricity Transmission
Northumbrian Water Group	NPower CHP Pipelines	Oikos Storage Limited
Ørsted	Perenco UK Limited (Purbeck Southampton Pipeline)	Perenco UK Limited (Purbeck Southampton Pipeline)
Petroineos	Phillips 66	Portsmouth Water
Premier Transmission Ltd (SNIP)	Redundant Pipelines - LPDA	RWE - Great Yarmouth Pipeline (Bacton to Great Yarmouth Power Station)
RWEnpower (Little Barford and South Haven)	SABIC UK Petrochemicals	Scottish and Southern Electricity Networks
Scottish Power Generation	Seabank Power Ltd	SES Water
SGN	Shell	Shell NOP
SSE (Peterhead Power Station)	SSE Enterprise Telecoms	SSE Utility Solutions Limited
Tata Communications (c/o JSM Construction Ltd)	Total (Colnbrook & Colwick Pipelines)	Total Finaline Pipelines
Transmission Capital	Uniper UK Ltd	Vattenfall
Veolia ES SELCHP Limited	Veolia ES Sheffield Ltd	Wales and West Utilities
West of Duddon Sands Transmission Ltd	Western Power Distribution	Westminster City Council





The following Non-LSBUD Members may have assets in your search area. It is YOUR RESPONSIBILITY to contact them before proceeding. Please be aware this list is not exhaustive and it is your responsibility to identify and contact all asset owners within your search area.

Non-LSBUD members (Asset owners not registered on LSBUD)			
Asset Owner	Preferred contact method	Phone	Status
BT	<a href="https://www.swns.bt.com/pls/mbe/welcome.home">https://www.swns.bt.com/pls/mbe/welcome.home</a>	08009173993	Not Notified
Cadent Gas	<a href="mailto:plantprotection@cadentgas.com">plantprotection@cadentgas.com</a>	0800688588	Not Notified
CenturyLink Communications UK Limited	<a href="mailto:plantenquiries@instalcom.co.uk">plantenquiries@instalcom.co.uk</a>	02087314613	Not Notified
CityFibre	<a href="mailto:asset.team@cityfibre.com">asset.team@cityfibre.com</a>	033 3150 7282	Not Notified
Colt	<a href="mailto:plantenquiries@catelecomuk.com">plantenquiries@catelecomuk.com</a>	01227768427	Not Notified
Energetics Electricity	<a href="mailto:plantenquiries@lastmile-uk.com">plantenquiries@lastmile-uk.com</a>	01698404646	Not Notified
ENGIE	<a href="mailto:nrswa@cofely-gdfsuez.com">nrswa@cofely-gdfsuez.com</a>	01293 549944	Not Notified
GTC	<a href="https://pe.gtc-uk.co.uk/PlantEnqMembership">https://pe.gtc-uk.co.uk/PlantEnqMembership</a>	01359240363	Not Notified
KPN (c/-Instalcom)	<a href="mailto:kpn.plantenquiries@instalcom.co.uk">kpn.plantenquiries@instalcom.co.uk</a>	n/a	Not Notified
Mobile Broadband Network Limited	<a href="mailto:mbnlplantenquiries@turntown.com">mbnlplantenquiries@turntown.com</a>	01212 621 100	Not Notified
Sky UK Limited	<a href="mailto:nrswa@sky.uk">nrswa@sky.uk</a>	02070323234	Not Notified
Sota	<a href="mailto:SOTA.plantenquiries@instalcom.co.uk">SOTA.plantenquiries@instalcom.co.uk</a>		Not Notified
Teliasonera	<a href="mailto:telentelia.plantenquiries@telent.com">telentelia.plantenquiries@telent.com</a>	0800526015	Not Notified
Thames Water	<a href="http://www.digdat.co.uk">http://www.digdat.co.uk</a>	08450709145	Not Notified
Utility assets Ltd	<a href="mailto:assetrecords@utilityassets.co.uk">assetrecords@utilityassets.co.uk</a>		Not Notified
Verizon Business	<a href="mailto:osp-team@uk.verizonbusiness.com">osp-team@uk.verizonbusiness.com</a>	01293611736	Not Notified
Virgin Media	<a href="http://www.digdat.co.uk">http://www.digdat.co.uk</a>	08708883116	Not Notified
Vodafone	<a href="mailto:osm.enquiries@atkingglobal.com">osm.enquiries@atkingglobal.com</a>	01454662881	Not Notified


## Disclaimer

Please refer to LineasearchbeforeUdig's Terms of Use for full terms of use available at [www.lineasearchbeforeudig.co.uk](http://www.lineasearchbeforeudig.co.uk)

The results of this Enquiry are personal to the Enquirer and shall not be shared with or relied upon by any other party. The asset information on which the Enquiry results are based has been provided by LSBUD Members, therefore LineasearchbeforeUdig will provide no guarantee that such information is accurate or reliable nor does it monitor such asset information for accuracy and reliability going forward. There may also be asset owners which do not participate in the enquiry service operated by LineasearchbeforeUdig, including but not exclusively those set out above. Therefore, LineasearchbeforeUdig cannot make any representation or give any guarantee or warranty as to the completeness of the information contained in the enquiry results or accept any responsibility for the accuracy of the mapping images used. LineasearchbeforeUdig and its employees, agents and consultants accept no liability (save that nothing in this Enquiry Confirmation excludes or limits our liability for death or personal injury arising from our negligence, or our fraud or fraudulent misrepresentation, or any other liability that cannot be excluded or limited by English law) arising in respect thereof or in any other way for errors or omissions including responsibility to any person by reason of negligence.



# Maps by email Plant Information Reply



## IMPORTANT WARNING

Information regarding the location of BT apparatus is given for your assistance and is intended for general guidance only. No guarantee is given of its accuracy. It should not be relied upon in the event of excavations or other works being made near to BT apparatus which may exist at various depths and may deviate from the marked route.



**openreach**

### CLICK BEFORE YOU DIG

FOR PROFESSIONAL FREE ON SITE ASSISTANCE PRIOR TO COMMENCEMENT OF EXCAVATION WORKS INCLUDING LOCATE AND MARKING SERVICE

email [cbyd@openreach.co.uk](mailto:cbyd@openreach.co.uk)

ADVANCE NOTICE REQUIRED  
(Office hours: Monday - Friday 08.00 to 17.00)  
[www.openreach.co.uk/cbyd](http://www.openreach.co.uk/cbyd)

### Accidents happen

If you do damage any Openreach equipment please let us know by calling 0800 023 2023 (opt 1 + opt 1) and we can get it fixed ASAP

## KEY TO BT SYMBOLS

	Planned	Live	Change Of State	+	Hatchings	
PCP			Split Coupling	×	Built	
Pole			Duct Tee	▲	Planned	
Box			Building		Inferred	
Manhole			Kiosk	K	Duct	
Cabinet			Other proposed plant is shown using dashed lines. BT Symbols not listed above may be disregarded. Existing BT Plant may not be recorded. Information valid at time of preparation. Maps are only valid for 90 days after the date of publication.			
	Pending Add	In Place	Pending Remove	Not In Use		
Power Cable						
Power Duct				N/A		

BT Ref : OEJ01231W

Map Reference : (centre) TQ2704085515


Easting/Northing : (centre) 527040,185515

Issued : 29/04/2020 13:23:45

Reproduced from the Ordnance Survey map by BT  
by permission of Ordnance Survey on behalf of the  
Controller of Her Majesty's Stationary Office  
(C) Crown Copyright British Telecommunications plc 100028040

**WARNING: IF PLANNED WORKS FALL INSIDE HATCHED AREA IT IS ESSENTIAL BEFORE PROCEEDING THAT YOU CONTACT THE NATIONAL NOTICE HANDLING CENTRE. PLEASE SEND E-MAIL TO: [nnhc@openreach.co.uk](mailto:nnhc@openreach.co.uk)**





Dig Sites Area: ---- Line: ----

The quality and accuracy of any print will depend on your printer, your computer and its print settings. Measurements scaled from this plan may not match measurements between the same points on the ground.



This plan must be used with the attached 'Symbols' document.

Date Requested: 29/04/2020  
Job Reference: 18271576  
Site Location: 526991 185478  
Requested by: Miss Alexa Band

Your Scheme/Reference:  
STS0065  
Scale: 1:500 (When plotted at A4)

1. The position of the apparatus shown on this drawing is believed to be correct but the original landmarks may have been altered since the apparatus was installed.
2. The exact position of the apparatus should be verified - use approved cable avoidance tools prior to excavation using suitable hand tools.
3. It is essential that trial holes are carefully made avoiding the use of mechanical tools or picks until the exact location of all the cables have been determined.
4. It must be assumed that there is a service cable into each property, lamp column and street sign, etc.
5. All cables must be treated as being live unless proved otherwise by UK Power Networks.
6. The information proved must be given to all people working near UK Power Networks plant and equipment. Do not use plans more than 3 months after the issue date for excavation purposes.
7. Please be aware that electric cables/lines belonging to other owners of licensed electricity distribution systems may be present and it is your responsibility to identify their location.
8. Please be aware the Low Voltage Overhead power lines are not currently displayed for the Eastern Region via this service, if you require records on the location of these please contact our Plan Provision team directly via [plans@ukpowernetworks.co.uk](mailto:plans@ukpowernetworks.co.uk).


1. UK Power Networks does not warrant that the information provided to you is correct. You rely upon it at your own risk.
2. UK Power Networks does not exclude or limit its liability if it causes the death of any persons or causes personal injury to a person.
3. Subject to paragraph 2 UK Power Networks has no liability to you in contract, in tort (including negligence), for breach of statutory duty or otherwise for any loss, damage, cost, claims, demands, or expenses that you or any third party may suffer or incur as a result of using the information provided whether for physical damage to property or for any economic loss (including without limitation loss of profit, loss of opportunity, loss of savings, loss of goodwill, loss of business, loss of use) or any special or consequential loss or damage whatsoever.
4. This plan has been provided to you on the basis of the terms of use set out in the covering letter that accompanies this plan. If you do not accept and/or do not understand the terms of use set out in the covering letter you must not use the plan and must return it to the sender of the letter.
5. You are responsible for the security of the information provided to you. It must not be given, sold or made available upon payment of a fee to a third party.
6. Please Note: The Overview map does not display UK Power Networks electricity network and should not be used for the location of UK Power Networks assets. For detail of the electricity network please view the relevant page as highlighted in the Overview map.

IF IN DOUBT - ASK! PHONE  
0800 056 5866  
EMERGENCY - If you damage a  
cable or line  
Phone 0800 783 8838 (24hrs)  
URGENTLY



ALWAYS LOOK UP  
BEFORE  
YOU START WORK  
Refer to HSE Guidance  
note GS6

Maps produced at 1:2500 scale are Geo-Schematics which show LV mains cables and overhead lines (in some cases all voltages). Prior to carrying out excavations you must refer to the 1:500 records to determine the location of all known underground plant and equipment.



SCALE: Not to scale		<div>LP MAINS MP MAINS IP MAINS LHP MAINS</div> <div><div><div></div><div></div><div></div><div></div></div><div><div></div><div></div><div></div><div></div></div><div><div></div><div></div><div></div><div></div></div><div><div></div><div></div><div></div><div></div></div></div>	<p>This plan shows those pipes owned by Cadent Gas Ltd in their role as a Licensed Gas Transporter (GT). Gas pipes owned by other GTs, or otherwise privately owned, may be present in this area. Information with regard to such pipes should be obtained from the relevant owners. The information shown on this plan is given without warranty, the accuracy thereof cannot be guaranteed. Service pipes, valves, syphons, stub connections, etc. are not shown but their presence should be anticipated. No liability of any kind whatsoever is accepted by Cadent Gas Ltd or their agents, servants or contractors for any error or omission. Safe digging practices, in accordance with HS(G)47, must be used to verify and establish the actual position of mains, pipes, services and other apparatus on site before any mechanical plant is used. It is your responsibility to ensure that this information is provided to all persons (either direct labour or contractors) working for you on or near gas apparatus. The information included on this plan should not be referred to beyond a period of 28 days from the date of issue. Further information on all DR4s can be determined by calling the DR4 hotline on 01455 892426 (9am-5pm) A DR4 is where a potential error has been identified within the asset record and a process is currently underway to investigate and resolve the error as appropriate.</p>	MAPS Viewer Version 5.8.0.1
USER ID: LaurenW				<p>Local Machine</p> <p>This plan is reproduced from or based on the OS map by Cadent Gas Ltd, with the sanction of the controller of HM Stationery Office. Crown Copyright Reserved.</p>
DATE: 29/04/2020				
EXTRACT DATE: 03/03/2020				
MAP REF: TQ2785				
CENTRE: 527040, 185515				
<p>Some examples of Plant Items:</p> <div><div>Valve</div><div>Depth of Cover</div><div>Syphon</div><div>Diameter Change</div><div>Material Change</div><div>Out of Standard Service</div></div>				



# SOILTECHNICS LIMITED

14A Hampstead Hill Gardens

Job No.	Sheet No.	Rev.
STS5065		
Drg. Ref.		
Made by AKW	Date	Checked

## Titles

Job No.: STS5065  
Job Title: 14A Hampstead Hill Gardens  
Sub-title:  
Calculation Heading:  
Initials: AKW  
Checker:  
Date Saved:  
Date Checked:  
Notes:  
File Name: Underpin and excavation.pdd  
File Path: \\st-dc01\Soiltechnics\ST PROJECTS\Schemes 2020 (S)\STS5065  
- 14 Hampstead Hill Gardens, London\Geotechnical

## History

Date	Time	By	Notes
15-Dec-2020	07:05	AngusW	New
15-Dec-2020	10:41	AngusW	
15-Dec-2020	14:38	AngusW	
15-Dec-2020	15:41	AngusW	
16-Dec-2020	07:44	AngusW	
16-Dec-2020	11:50	AngusW	

## Analysis Options

### General

Global Poisson's ratio: 0.20  
Maximum allowable ratio between values of E: 1.5  
Horizontal rigid boundary level: 88.50 [m OD]  
Displacements at load centroids: Yes  
GSA piled raft data : No

### Elastic

Elastic : Yes  
Analysis: Boussinesq  
Stiffness for horizontal displacement calculations: Weighted average  
Using legacy heave correction factor: Yes

### Consolidation

Consolidation : Yes  
Time Period : 50.000000 years.  
Time Step : 0.200000 years.  
Cv or k : Cv  
Rigid Boundary : Impermeable

### Water

Level : 99.500000 [m].  
Unit Weight : 10.000000 [kN/m³].

## Soil ProfilesSoil Profile 1

layer	Name	Level at	Number of	Youngs	Youngs	Poissons	Cons. :	Cons. :	Cons. :	Cons. :	Cons. :	Cons. :	Cons. :	Cons. :	C <sub>v</sub>	Bulk	C <sub>a</sub>	C <sub>ae</sub>	Non-	
linear		top	intermediate	Modulus	Modulus	ratio	Method	m <sub>v</sub>	e <sub>0</sub>	C <sub>c</sub>	C <sub>r</sub>	Over	Pre	OCR	OCM					
ref.																				
curve		displacement	levels	: Top	: Btm.							Cons. Calc.	Cons. Press.			weight				
		[mOD]		[kN/m <sup>2</sup> ]	[kN/m <sup>2</sup> ]			[m <sup>3</sup> /kN]					[kN/m <sup>2</sup> ]			[kN/m <sup>2</sup> ]	[m <sup>3</sup> /year]	[kN/m <sup>3</sup> ]		
1	Head	100.00	5	10000.	10000.	0.20000	mv	300.00E-6	N/A	N/A	N/A	N/A	N/A	N/A	N/A	20.000	18.000	N/A	10.000E-6	None
2	London Clay	98.300	15	17000.	50320.	0.20000	mv	90.000E-6	N/A	N/A	N/A	N/A	N/A	N/A	N/A	15.000	19.000	N/A	10.000E-6	None

### Soil Zones

Zone	Name	X min	X max	Y min	Y max	Profile
1	Soil Zone 1	-30.000	30.000	-20.000	40.000	Soil Profile 1

## Rectangular Load Data

Load ref.	Name	Orientation of Plane	Centre (Global) : x	Centre (Global) : y	Centre (Global) : z	Position : Angle of local x from x	Position : Width x or Radius	Position : Length y	Value : Normal (local z)	Value : Tangential (local x)	Value : Tangential (local y)
			[m]	[m]	[m]	[Degrees]	[m]	[m]	[kN/m²]	[kN/m²]	[kN/m²]
1	Rect Load 1	Horizontal	0.50000	12.21000	98.30000	0.0	1.0000	17.000	111.25	0.0	0.0
2	Rect Load 2	Horizontal	3.21500	21.21000	98.30000	0.0	6.4300	1.0000	111.25	0.0	0.0
3	Rect Load 3	Horizontal	5.93000	10.85500	98.30000	0.0	1.0000	19.710	111.25	0.0	0.0
4	Rect Load 4	Horizontal	4.00000	0.50000	98.30000	0.0	4.8600	1.0000	111.25	0.0	0.0
5	Rect Load 5	Horizontal	2.07000	1.85500	98.30000	0.0	1.0000	1.7100	111.25	0.0	0.0
6	Rect Load 6	Horizontal	1.28500	3.21000	98.30000	0.0	2.5700	1.0000	111.25	0.0	0.0

## Polygonal Load Data

Load ref.	Name	Position : Level	Position : Polygon : Coords.	Position : Polygon Rectangles : Rect. tolerance [%]	No. of Rectangles	Value : Normal (local z)
		[m]	[m]	[%]		[kN/m²]
1	Basement excavation	98.30000	(1.57,0) (6.43,0) (0,2.71) (1.57,2.71) (0,2.71) (1.57,0)	(6.43,21.7) (0,2.71) (1.57,2.71)	2	-63.000

## Polygonal Loads' Rectangles

No.	Centre : x	Centre : y	Centre : Angle of local x from global X [Degrees]	Width x [m]	Depth y [m]
Load 1 : Basement excavation (Edge 1 optimal)					
1	4.00000	10.85500	0.0	4.8600	21.710
2	0.78500	12.21000	0.0	1.5700	19.000

## Displacement Lines

Name	X1	Y1	Z1	X2	Y2	Z2	Intervals	Calculate	Detailed Results
	[m]	[m]	[m]	[m]	[m]	[m]	[No.]		
No. 14 Hampstead Hill Gardens 1	-19.42000	1.29000	100.00000	-3.92000	1.29000	100.00000	10	Yes	Yes
No. 14 Hampstead Hill Gardens 2	-3.92000	1.29000	100.00000	-3.92000	3.57000	100.00000	3	Yes	Yes
No. 14 Hampstead Hill Gardens 3	-3.92000	3.57000	100.00000	-1.43000	3.57000	100.00000	1	Yes	Yes
No. 14 Hampstead Hill Gardens 4	-1.43000	3.57000	100.00000	-1.43000	12.14000	100.00000	4	Yes	Yes
No. 14 Hampstead Hill Gardens 5	-1.43000	12.14000	100.00000	-19.42000	12.14000	100.00000	10	Yes	Yes
No. 12 Hampstead Hill Gardens 1	19.10000	1.37000	100.00000	11.70000	1.37000	100.00000	10	Yes	Yes
No. 12 Hampstead Hill Gardens 2	11.70000	1.37000	100.00000	11.70000	2.00000	100.00000	1	Yes	Yes
No. 12 Hampstead Hill Gardens 3	11.70000	2.00000	100.00000	8.86000	2.00000	100.00000	3	Yes	Yes
No. 12 Hampstead Hill Gardens 4	8.86000	2.00000	100.00000	8.86000	14.43000	100.00000	10	Yes	Yes
No. 12 Hampstead Hill Gardens 5	8.86000	14.43000	100.00000	9.29000	14.43000	100.00000	1	Yes	Yes
No. 12 Hampstead Hill Gardens 6	9.29000	14.43000	100.00000	9.29000	17.86000	100.00000	3	Yes	Yes
No. 12 Hampstead Hill Gardens 7	9.29000	17.86000	100.00000	10.43000	19.14000	100.00000	2	Yes	Yes
No. 12 Hampstead Hill Gardens 8	10.43000	19.14000	100.00000	12.00000	19.14000	100.00000	2	Yes	Yes
No. 12 Hampstead Hill Gardens 9	12.00000	19.14000	100.00000	13.00000	17.86000	100.00000	2	Yes	Yes
No. 12 Hampstead Hill Gardens 10	13.00000	17.86000	100.00000	13.00000	14.43000	100.00000	3	Yes	Yes







14A Hampstead Hill Gardens

# SOILTECHNICS LIMITED

Job No.	Sheet No.	Rev.
STS5065		
Drg. Ref.		
Made by AKW	Date	Checked

## Results : Total : Displacement Data : Lines

Ref.	Name	TimeStep : No	TimeStep : Value	x	y	z	Sett. :	Sett. :	Sett. :	Total
							Immediate	Primary	Secondary	
				[m]	[m]	[mm]	[mm]	[mm]	[mm]	
1	No. 14 Hampstead Hill Gardens 1	0	0.00000	-19.42000	1.29000	100.00000	0.00868	0.00000	0.00000	0.00868
		200	40.00000	-19.42000	1.29000	100.00000	0.00868	-0.02088	0.07233	0.06014
		250	50.00000	-19.42000	1.29000	100.00000	0.00868	-0.02088	0.08299	0.07080
1	No. 14 Hampstead Hill Gardens 1	0	0.00000	-17.87000	1.29000	100.00000	0.00940	0.00000	0.00000	0.00940
		200	40.00000	-17.87000	1.29000	100.00000	0.00940	-0.02713	0.07233	0.05461
		250	50.00000	-17.87000	1.29000	100.00000	0.00940	-0.02713	0.08299	0.06527
1	No. 14 Hampstead Hill Gardens 1	0	0.00000	-16.32000	1.29000	100.00000	0.01004	0.00000	0.00000	0.01004
		200	40.00000	-16.32000	1.29000	100.00000	0.01004	-0.03560	0.07233	0.04677
		250	50.00000	-16.32000	1.29000	100.00000	0.01004	-0.03560	0.08299	0.05743
1	No. 14 Hampstead Hill Gardens 1	0	0.00000	-14.77000	1.29000	100.00000	0.01047	0.00000	0.00000	0.01047
		200	40.00000	-14.77000	1.29000	100.00000	0.01047	-0.04721	0.07233	0.03559
		250	50.00000	-14.77000	1.29000	100.00000	0.01047	-0.04721	0.08299	0.04625
1	No. 14 Hampstead Hill Gardens 1	0	0.00000	-13.22000	1.29000	100.00000	0.01050	0.00000	0.00000	0.01050
		200	40.00000	-13.22000	1.29000	100.00000	0.01050	-0.06325	0.07233	0.01959
		250	50.00000	-13.22000	1.29000	100.00000	0.01050	-0.06325	0.08299	0.03025
1	No. 14 Hampstead Hill Gardens 1	0	0.00000	-11.67000	1.29000	100.00000	0.00984	0.00000	0.00000	0.00984
		200	40.00000	-11.67000	1.29000	100.00000	0.00984	-0.08559	0.07233	-0.00034
		250	50.00000	-11.67000	1.29000	100.00000	0.00984	-0.08559	0.08299	0.00712
1	No. 14 Hampstead Hill Gardens 1	0	0.00000	-10.12000	1.29000	100.00000	0.00801	0.00000	0.00000	0.00801
		200	40.00000	-10.12000	1.29000	100.00000	0.00801	-0.11689	0.07233	-0.03654
		250	50.00000	-10.12000	1.29000	100.00000	0.00801	-0.11689	0.08299	-0.02588
1	No. 14 Hampstead Hill Gardens 1	0	0.00000	-8.57000	1.29000	100.00000	0.00434	0.00000	0.00000	0.00434
		200	40.00000	-8.57000	1.29000	100.00000	0.00434	-0.16077	0.07233	-0.08329
		250	50.00000	-8.57000	1.29000	100.00000	0.00434	-0.16077	0.08299	-0.07344
1	No. 14 Hampstead Hill Gardens 1	0	0.00000	-7.02000	1.29000	100.00000	-0.00201	0.00000	0.00000	-0.00201
		200	40.00000	-7.02000	1.29000	100.00000	-0.00201	-0.22189	0.07233	-0.15157
		250	50.00000	-7.02000	1.29000	100.00000	-0.00201	-0.22189	0.08299	-0.14091
1	No. 14 Hampstead Hill Gardens 1	0	0.00000	-5.47000	1.29000	100.00000	-0.01169	0.00000	0.00000	-0.01169
		200	40.00000	-5.47000	1.29000	100.00000	-0.01169	-0.30505	0.07233	-0.24441
		250	50.00000	-5.47000	1.29000	100.00000	-0.01169	-0.30505	0.08299	-0.23375
2	No. 14 Hampstead Hill Gardens 2	0	0.00000	-3.92000	1.29000	100.00000	-0.02343	0.00000	0.00000	-0.02343
		200	40.00000	-3.92000	1.29000	100.00000	-0.02343	-0.41129	0.07233	-0.36238
		250	50.00000	-3.92000	1.29000	100.00000	-0.02343	-0.41129	0.08299	-0.35172
2	No. 14 Hampstead Hill Gardens 2	0	0.00000	-3.92000	2.05000	100.00000	-0.03736	0.00000	0.00000	-0.03736
		200	40.00000	-3.92000	2.05000	100.00000	-0.03736	-0.49464	0.07233	-0.45966
		250	50.00000	-3.92000	2.05000	100.00000	-0.03736	-0.49464	0.08299	-0.44900
2	No. 14 Hampstead Hill Gardens 2	0	0.00000	-3.92000	2.81000	100.00000	-0.05474	0.00000	0.00000	-0.05474
		200	40.00000	-3.92000	2.81000	100.00000	-0.05474	-0.59088	0.07233	-0.53329
		250	50.00000	-3.92000	2.81000	100.00000	-0.05474	-0.59088	0.08299	-0.56263
3	No. 14 Hampstead Hill Gardens 3	0	0.00000	-3.92000	3.57000	100.00000	-0.07560	0.00000	0.00000	-0.07560
		200	40.00000	-3.92000	3.57000	100.00000	-0.07560	-0.69901	0.07233	-0.70228
		250	50.00000	-3.92000	3.57000	100.00000	-0.07560	-0.69901	0.08299	-0.69162
4	No. 14 Hampstead Hill Gardens 4	0	0.00000	-1.43000	3.57000	100.00000	-0.09885	0.00000	0.00000	-0.09885
		200	40.00000	-1.43000	3.57000	100.00000	-0.09885	-1.15763	0.07021	-1.18627
		250	50.00000	-1.43000	3.57000	100.00000	-0.09885	-1.15763	0.08087	-1.17561
4	No. 14 Hampstead Hill Gardens 4	0	0.00000	-1.43000	5.71250	100.00000	-0.37293	0.00000	0.00000	-0.37293
		200	40.00000	-1.43000	5.71250	100.00000	-0.37293	-2.21230	0.07233	-2.51290
		250	50.00000	-1.43000	5.71250	100.00000	-0.37293	-2.21230	0.08299	-2.50224
4	No. 14 Hampstead Hill Gardens 4	0	0.00000	-1.43000	7.85500	100.00000	-0.56874	0.00000	0.00000	-0.56874
		200	40.00000	-1.43000	7.85500	100.00000	-0.56874	-2.97785	0.07343	-3.47315
		250	50.00000	-1.43000	7.85500	100.00000	-0.56874	-2.97785	0.08409	-3.46249
4	No. 14 Hampstead Hill Gardens 4	0	0.00000	-1.43000	9.97500	100.00000	-0.65181	0.00000	0.00000	-0.65181
		200	40.00000	-1.43000	9.97500	100.00000	-0.65181	-3.33122	0.07343	-3.90960
		250	50.00000	-1.43000	9.97500	100.00000	-0.65181	-3.33122	0.08409	-3.89894
5	No. 14 Hampstead Hill Gardens 5	0	0.00000	-1.43000	12.14000	100.00000	-0.66886	0.00000	0.00000	-0.66886
		200	40.00000	-1.43000	12.14000	100.00000	-0.66886	-3.40531	0.07343	-4.00073
		250	50.00000	-1.43000	12.14000	100.00000	-0.66886	-3.40531	0.08409	-3.99007
5	No. 14 Hampstead Hill Gardens 5	0	0.00000	-3.22900	12.14000	100.00000	-0.33007	0.00000	0.00000	-0.33007
		200	40.00000	-3.22900	12.14000	100.00000	-0.33007	-1.89254	0.07343	-2.14917
		250	50.00000	-3.22900	12.14000	100.00000	-0.33007	-1.89254	0.08409	-2.13852
5	No. 14 Hampstead Hill Gardens 5	0	0.00000	-5.02800	12.14000	100.00000	-0.14959	0.00000	0.00000	-0.14959
		200	40.00000	-5.02800	12.14000	100.00000	-0.14959	-1.05807	0.07343	-1.13422
		250	50.00000	-5.02800	12.14000	100.00000	-0.14959	-1.05807	0.08409	-1.12356
5	No. 14 Hampstead Hill Gardens 5	0	0.00000	-6.82700	12.14000	100.00000	-0.06259	0.00000	0.00000	-0.06259
		200	40.00000	-6.82700	12.14000	100.00000	-0.06259	-0.60900	0.07343	-0.59816
		250	50.00000	-6.82700	12.14000	100.00000	-0.06259	-0.60900	0.08409	-0.58750
5	No. 14 Hampstead Hill Gardens 5	0	0.00000	-8.62600	12.14000	100.00000	-0.02136	0.00000	0.00000	-0.02136
		200	40.00000	-8.62600	12.14000	100.00000	-0.02136	-0.36246	0.07343	-0.31038
		250	50.00000	-8.62600	12.14000	100.00000	-0.02136	-0.36246	0.08409	-0.29972
5	No. 14 Hampstead Hill Gardens 5	0	0.00000	-10.42500	12.14000	100.00000	-0.00216	0.00000	0.00000	-0.00216
		200	40.00000	-10.42500	12.14000	100.00000	-0.00216	-0.22305	0.07233	-0.15287
		250	50.00000	-10.42500	12.14000	100.00000	-0.00216	-0.22305	0.08299	-0.14121
5	No. 14 Hampstead Hill Gardens 5	0	0.00000	-12.22400	12.14000	100.00000	0.00640	0.00000	0.00000	0.00640
		200	40.00000	-12.22400	12.14000	100.00000	0.00640	-0.14167	0.07233	-0.06294
		250	50.00000	-12.22400	12.14000	100.00000	0.00640	-0.14167	0.08299	-0.05228
5	No. 14 Hampstead Hill Gardens 5	0	0.00000	-14.02300	12.14000	100.00000	0.00981	0.00000	0.00000	0.00981
		200	40.00000	-14.02300	12.14000	100.00000	0.00981	-0.09267	0.07233	-0.08983
		250	50.00000	-14.02300	12.14000	100.00000	0.00981	-0.09267	0.08299	0.00013
5	No. 14 Hampstead Hill Gardens 5	0	0.00000	-15.82200	12.14000	100.00000	0.01074	0.00000	0.00000	0.01074
		200	40.00000	-15.82200	12.14000	100.00000	0.01074	-0.06226	0.07233	0.02081
		250	50.00000	-15.82200	12.14000	100.00000	0.01074	-0.06226	0.08299	0.03147
5	No. 14 Hampstead Hill Gardens 5	0	0.00000	-17.62100	12.14000	100.00000	0.01051	0.00000	0.00000	0.01051
		200	40.00000	-17.62100	12.14000	100.00000	0.01051	-0.04287	0.07233	0.03397
		250	50.00000	-17.62100	12.14000	100.00000	0.01051	-0.04287	0.08299	0.05063
6	No. 12 Hampstead Hill Gardens 1	0	0.00000	19.10000	1.37000	100.00000	0.01004	0.00000	0.00000	0.01004
		200	40.00000	19.10000	1.37000	100.00000	0.01004	-0.07511	0.07233	0.00726
		250	50.00000	19.10000	1.37000	100.00000	0.01004	-0.07511	0.08299	0.01392



# SOILTECHNICS LIMITED

14A Hampstead Hill Gardens

Job No.	Sheet No.	Rev.
STS5065		
Drg. Ref.		
Made by AKW	Date	Checked

Ref.	Name	TimeStep : No	TimeStep : Value [m]	x [m]	y [m]	z [mm]	Sett. : Immediate [mm]	Sett. : Primary [mm]	Sett. : Secondary [mm]	Sett. : Total
9 No. 12 Hampstead Hill Gardens 4		250	50.00000	8.86000	4.48600	100.00000	-0.25950	-1.55762	0.08409	-1.73303
		0	0.00000	8.86000	5.72900	100.00000	-0.33485	0.00000	0.00000	-0.33485
		200	40.00000	8.86000	5.72900	100.00000	-0.33485	-1.88401	0.07343	-2.14543
9 No. 12 Hampstead Hill Gardens 4		250	50.00000	8.86000	5.72900	100.00000	-0.33485	-1.88401	0.08409	-2.13477
		0	0.00000	8.86000	6.97200	100.00000	-0.39069	0.00000	0.00000	-0.39069
		200	40.00000	8.86000	6.97200	100.00000	-0.39069	-2.13539	0.07343	-2.45265
9 No. 12 Hampstead Hill Gardens 4		250	50.00000	8.86000	6.97200	100.00000	-0.39069	-2.13539	0.08409	-2.44199
		0	0.00000	8.86000	8.21500	100.00000	-0.42895	0.00000	0.00000	-0.42895
		200	40.00000	8.86000	8.21500	100.00000	-0.42895	-2.31427	0.07343	-2.66979
9 No. 12 Hampstead Hill Gardens 4		250	50.00000	8.86000	8.21500	100.00000	-0.42895	-2.31428	0.08409	-2.65913
		0	0.00000	8.86000	9.45800	100.00000	-0.45260	0.00000	0.00000	-0.45260
		200	40.00000	8.86000	9.45800	100.00000	-0.45260	-2.42865	0.07343	-2.80782
9 No. 12 Hampstead Hill Gardens 4		250	50.00000	8.86000	9.45800	100.00000	-0.45260	-2.42865	0.08409	-2.79716
		0	0.00000	8.86000	10.70100	100.00000	-0.46416	0.00000	0.00000	-0.46416
		200	40.00000	8.86000	10.70100	100.00000	-0.46416	-2.48606	0.07343	-2.87679
9 No. 12 Hampstead Hill Gardens 4		250	50.00000	8.86000	10.70100	100.00000	-0.46416	-2.48606	0.08409	-2.86613
		0	0.00000	8.86000	11.94400	100.00000	-0.46495	0.00000	0.00000	-0.46495
		200	40.00000	8.86000	11.94400	100.00000	-0.46495	-2.49064	0.07343	-2.88215
9 No. 12 Hampstead Hill Gardens 4		250	50.00000	8.86000	11.94400	100.00000	-0.46495	-2.49064	0.08409	-2.87149
		0	0.00000	8.86000	13.18700	100.00000	-0.45478	0.00000	0.00000	-0.45478
		200	40.00000	8.86000	13.18700	100.00000	-0.45478	-2.44164	0.07343	-2.82298
10 No. 12 Hampstead Hill Gardens 5		250	50.00000	8.86000	13.18700	100.00000	-0.45478	-2.44164	0.08409	-2.81232
		0	0.00000	8.86000	14.43000	100.00000	-0.43182	0.00000	0.00000	-0.43182
		200	40.00000	8.86000	14.43000	100.00000	-0.43182	-2.33303	0.07343	-2.69142
11 No. 12 Hampstead Hill Gardens 6		250	50.00000	8.86000	14.43000	100.00000	-0.43182	-2.33303	0.08409	-2.68076
		0	0.00000	9.29000	14.43000	100.00000	-0.36159	0.00000	0.00000	-0.36159
		200	40.00000	9.29000	14.43000	100.00000	-0.36159	-2.02357	0.07343	-2.31173
11 No. 12 Hampstead Hill Gardens 6		250	50.00000	9.29000	14.43000	100.00000	-0.36159	-2.02357	0.08409	-2.30107
		0	0.00000	9.29000	15.57333	100.00000	-0.33148	0.00000	0.00000	-0.33148
		200	40.00000	9.29000	15.57333	100.00000	-0.33148	-1.88267	0.07343	-2.14072
11 No. 12 Hampstead Hill Gardens 6		250	50.00000	9.29000	15.57333	100.00000	-0.33148	-1.88267	0.08409	-2.13006
		0	0.00000	9.29000	16.71667	100.00000	-0.28795	0.00000	0.00000	-0.28795
		200	40.00000	9.29000	16.71667	100.00000	-0.28795	-1.68579	0.07343	-1.90031
12 No. 12 Hampstead Hill Gardens 7		250	50.00000	9.29000	16.71667	100.00000	-0.28795	-1.68579	0.08409	-1.88965
		0	0.00000	9.29000	17.86000	100.00000	-0.23036	0.00000	0.00000	-0.23036
		200	40.00000	9.29000	17.86000	100.00000	-0.23036	-1.43338	0.07343	-1.59031
12 No. 12 Hampstead Hill Gardens 7		250	50.00000	9.29000	17.86000	100.00000	-0.23036	-1.43338	0.08409	-1.57965
		0	0.00000	9.86000	18.50000	100.00000	-0.15385	0.00000	0.00000	-0.15385
		200	40.00000	9.86000	18.50000	100.00000	-0.15385	-1.07420	0.07343	-1.15463
13 No. 12 Hampstead Hill Gardens 8		250	50.00000	9.86000	18.50000	100.00000	-0.15385	-1.07420	0.08409	-1.14397
		0	0.00000	10.43000	19.14000	100.00000	-0.09992	0.00000	0.00000	-0.09992
		200	40.00000	10.43000	19.14000	100.00000	-0.09992	-0.80686	0.07343	-0.83335
13 No. 12 Hampstead Hill Gardens 8		250	50.00000	10.43000	19.14000	100.00000	-0.09992	-0.80687	0.08409	-0.82269
		0	0.00000	11.21500	19.14000	100.00000	-0.07141	0.00000	0.00000	-0.07141
		200	40.00000	11.21500	19.14000	100.00000	-0.07141	-0.65041	0.07343	-0.64839
14 No. 12 Hampstead Hill Gardens 9		250	50.00000	11.21500	19.14000	100.00000	-0.07141	-0.65041	0.08409	-0.63773
		0	0.00000	12.00000	19.14000	100.00000	-0.04947	0.00000	0.00000	-0.04947
		200	40.00000	12.00000	19.14000	100.00000	-0.04947	-0.52596	0.07343	-0.50200
14 No. 12 Hampstead Hill Gardens 9		250	50.00000	12.00000	19.14000	100.00000	-0.04947	-0.52596	0.08409	-0.49134
		0	0.00000	12.50000	18.50000	100.00000	-0.04600	0.00000	0.00000	-0.04600
		200	40.00000	12.50000	18.50000	100.00000	-0.04600	-0.50459	0.07343	-0.47716
15 No. 12 Hampstead Hill Gardens 10		250	50.00000	12.50000	18.50000	100.00000	-0.04600	-0.50459	0.08409	-0.46650
		0	0.00000	13.00000	17.86000	100.00000	-0.04108	0.00000	0.00000	-0.04108
		200	40.00000	13.00000	17.86000	100.00000	-0.04108	-0.47624	0.07343	-0.44389
15 No. 12 Hampstead Hill Gardens 10		250	50.00000	13.00000	17.86000	100.00000	-0.04108	-0.47624	0.08409	-0.43323
		0	0.00000	13.00000	16.71667	100.00000	-0.05109	0.00000	0.00000	-0.05109
		200	40.00000	13.00000	16.71667	100.00000	-0.05109	-0.53600	0.07343	-0.51366
15 No. 12 Hampstead Hill Gardens 10		250	50.00000	13.00000	16.71667	100.00000	-0.05109	-0.53600	0.08409	-0.50300
		0	0.00000	13.00000	15.57333	100.00000	-0.05963	0.00000	0.00000	-0.05963
		200	40.00000	13.00000	15.57333	100.00000	-0.05963	-0.58710	0.07343	-0.57330
		250	50.00000	13.00000	15.57333	100.00000	-0.05963	-0.58710	0.08409	-0.56264



14A Hampstead Hill Gardens

# SOILTECHNICS LIMITED

Job No. Sheet No. Rev.

STS5065

Drg. Ref.

Made by  
AKW Date  
16-Dec-2020

Checked Date

## Titles

Job No.: STS5065  
Job Title: 14A Hampstead Hill Gardens  
Sub-title:  
Calculation Heading:  
Initials: AKW  
Checker:  
Date Saved: 16-Dec-2020  
Date Checked:  
Notes:  
File Name: Ground movement.xdd  
File Path: \\st-dc01\Soiltechnics\ST PROJECTS\Schemes 2020 (S)\STS5065  
- 14 Hampstead Hill Gardens, London\Geotechnical

## History

Date	Time	By	Notes
15-Dec-2020	10:43	AngusW	New
15-Dec-2020	13:44	AngusW	
15-Dec-2020	15:48	AngusW	
16-Dec-2020	09:21	AngusW	
16-Dec-2020	12:00	AngusW	

## Displacement Lines

Ref.	Name	x1	y1	z1	x2	y2	z2	Intervals	Surface type for tunnels	Interpolate imported displacements	Calculate
		[m]	[m]	[m]	[m]	[m]	[m]	[No.]			
1	No. 14 Hampstead Hill Gardens 1	-19.42000	1.29000	100.00000	-3.92000	1.29000	100.00000	10	Surface No		Yes
2	No. 14 Hampstead Hill Gardens 2	-3.92000	1.29000	100.00000	-3.92000	3.57000	100.00000	3	Surface No		Yes
3	No. 14 Hampstead Hill Gardens 3	-3.92000	3.57000	100.00000	-1.43000	3.57000	100.00000	1	Surface No		Yes
4	No. 14 Hampstead Hill Gardens 4	-1.43000	3.57000	100.00000	-1.43000	12.14000	100.00000	4	Surface No		Yes
5	No. 14 Hampstead Hill Gardens 5	-1.43000	12.14000	100.00000	-19.42000	12.14000	100.00000	10	Surface No		Yes
6	No. 12 Hampstead Hill Gardens 1	19.10000	1.37000	100.00000	11.70000	1.37000	100.00000	10	Surface No		Yes
7	No. 12 Hampstead Hill Gardens 2	11.70000	1.37000	100.00000	11.70000	2.00000	100.00000	1	Surface No		Yes
8	No. 12 Hampstead Hill Gardens 3	11.70000	2.00000	100.00000	8.86000	2.00000	100.00000	3	Surface No		Yes
9	No. 12 Hampstead Hill Gardens 4	8.86000	2.00000	100.00000	8.86000	14.43000	100.00000	10	Surface No		Yes
10	No. 12 Hampstead Hill Gardens 5	8.86000	14.43000	100.00000	9.29000	14.43000	100.00000	1	Surface No		Yes
11	No. 12 Hampstead Hill Gardens 6	9.29000	14.43000	100.00000	9.29000	17.86000	100.00000	3	Surface No		Yes
12	No. 12 Hampstead Hill Gardens 7	9.29000	17.86000	100.00000	10.43000	19.14000	100.00000	2	Surface No		Yes
13	No. 12 Hampstead Hill Gardens 8	10.43000	19.14000	100.00000	12.00000	19.14000	100.00000	2	Surface No		Yes
14	No. 12 Hampstead Hill Gardens 9	12.00000	19.14000	100.00000	13.00000	17.86000	100.00000	2	Surface No		Yes
15	No. 12 Hampstead Hill Gardens 10	13.00000	17.86000	100.00000	13.00000	14.43000	100.00000	3	Surface No		Yes

## Displacement Grids

Ref.	Name	Extrusion: Direction	Base line start: X	Base line start: Y	Base line start: Z(level)	Base line end: X	Base line end: Y	Base line end: Z(level)	Base line: Intervals	Extrusion: Distance	Extrusion: Intervals	Surface type for tunnels	Calculate
			[m]	[m]	[m]	[m]	[m]	[m]	[No.]	[m]	[No.]		
1	Displacement Grid 1	Global X	-20.00000	-10.00000	100.00000	-	30.00000	100.00000	40	50.00000	50	Surface Yes	

## Imported Displacements

Set: Ref.	Set: Name	Result: Ref.	Coordinates: x [m]	Coordinates: y [m]	Coordinates: z [m]	Displacements: x [mm]	Displacements: y [mm]	Displacements: z [mm]
1	Underpin and excavation - Consolidation	1	-19.42000	1.29000	100.00000	0.00000	0.00000	0.07080 1,2,6
		2	-17.89700	1.29000	100.00000	0.00000	0.00000	2.06527 1,2,6
		3	-16.32000	1.29000	100.00000	0.00000	0.00000	0.05743 1,2,6
		4	-14.77000	1.29000	100.00000	0.00000	0.00000	0.04625 1,2,6
		5	-13.22000	1.29000	100.00000	0.00000	0.00000	0.03025 1,2,6
		6	-11.67000	1.29000	100.00000	0.00000	0.00000	0.00724 1,2,6
		7	-10.12000	1.29000	100.00000	0.00000	0.00000	-0.02588 1,2,6
		8	-8.57000	1.29000	100.00000	0.00000	0.00000	-0.07344 1,2,6
		9	-7.02000	1.29000	100.00000	0.00000	0.00000	-0.14091 1,2,6
		10	-5.47000	1.29000	100.00000	0.00000	0.00000	-0.23375 1,2,6
		11	-3.92000	1.29000	100.00000	0.00000	0.00000	-0.35172 1,2,6
		12	-3.92000	1.29000	100.00000	0.00000	0.00000	-0.35172 1,2,6
		13	-3.92000	2.05000	100.00000	0.00000	0.00000	-0.44900 1,2,6
		14	-3.92000	2.81000	100.00000	0.00000	0.00000	-0.56263 1,2,6
		15	-3.92000	3.57000	100.00000	0.00000	0.00000	-0.69162 1,2,6
		16	-3.92000	3.57000	100.00000	0.00000	0.00000	-0.69162 1,2,6
		17	-1.43000	3.57000	100.00000	0.00000	0.00000	-1.17561 1,2,6
		18	-1.43000	3.57000	100.00000	0.00000	0.00000	-1.17561 1,2,6
		19	-1.43000	5.71250	100.00000	0.00000	0.00000	-2.50224 1,2,6
		20	-1.43000	7.85500	100.00000	0.00000	0.00000	-3.46249 1,2,6
		21	-1.43000	9.99750	100.00000	0.00000	0.00000	-3.89894 1,2,6
		22	-1.43000	12.14000	100.00000	0.00000	0.00000	-0.99007 1,2,6
		23	-1.43000	12.14000	100.00000	0.00000	0.00000	-3.99007 1,2,6
		24	-3.22900	12.14000	100.00000	0.00000	0.00000	-2.13852 1,2,6
		25	-5.02800	12.14000	100.00000	0.00000	0.00000	-1.12356 1,2,6
		26	-6.82700	12.14000	100.00000	0.00000	0.00000	-0.58750 1,2,6
		27	-8.62600	12.14000	100.00000	0.00000	0.00000	-0.29972 1,2,6
		28	-10.42500	12.14000	100.00000	0.00000	0.00000	-0.14221 1,2,6
		29	-12.22400	12.14000	100.00000	0.00000	0.00000	-0.05228 1,2,6
		30	-14.02300	12.14000	100.00000	0.00000	0.00000	0.00013 1,2,6
		31	-15.82200	12.14000	100.00000	0.00000	0.00000	0.03147 1,2,6
		32	-17.62100	12.14000	100.00000	0.00000	0.00000	0.05063 1,2,6
		33	-19.42000	12.14000	100.00000	0.00000	0.00000	0.06259 1,2,6
		34	19.10000	1.37000	100.00000	0.00000	0.00000	0.01792 1,2,6
		35	18.36000	1.37000	100.00000	0.00000	0.00000	0.00536 1,2,6
		36	17.62000	1.37000	100.00000	0.00000	0.00000	-0.00970 1,2,6
		37	16.88000	1.37000	100.00000	0.00000	0.00000	-0.02776 1,2,6
		38	16.14000	1.37000	100.00000	0.00000	0.00000	-0.04941 1,2,6
		39	15.40000	1.37000	100.00000	0.00000	0.00000	-0.07538 1,2,6
		40	14.66000	1.37000	100.00000	0.00000	0.00000	-0.10647 1,2,6
		41	13.92000	1.37000	100.00000	0.00000	0.00000	-0.14360 1,2,6
		42	13.18000	1.37000	100.00000	0.00000	0.00000	-0.18771 1,2,6
		43	12.44000	1.37000	100.00000	0.00000	0.00000	-0.23965 1,2,6
		44	11.70000	1.37000	100.00000	0.00000	0.00000	-0.29985 1,2,6
		45	11.70000	1.37000	100.00000	0.00000	0.00000	-0.29985 1,2,6
		46	11.70000	2.00000	100.00000	0.00000	0.00000	-0.36511 1,2,6
		47	11.70000	2.00000	100.00000	0.00000	0.00000	-0.36511 1,2,6
		48	10.75333	2.00000	100.00000	0.00000	0.00000	-0.48286 1,2,6
		49	9.80667	2.00000	100.00000	0.00000	0.00000	-0.62066 1,2,6
		50	8.86000	2.00000	100.00000	0.00000	0.00000	-0.75903 1,2,6
		51	8.86000	2.00000	100.00000	0.00000	0.00000	-0.75903 1,2,6
		52	8.86000	3.24300	100.00000	0.00000	0.00000	-1.25430 1,2,6
		53	8.86000	4.48600	100.00000	0.00000	0.00000	-1.73303 1,2,6
		54	8.86000	5.72900	100.00000	0.00000	0.00000	-2.13477 1,2,6
		55	8.86000	6.97200	100.00000	0.00000	0.00000	-2.44199 1,2,6
		56	8.86000	8.21500	100.00000	0.00000	0.00000	-2.65913 1,2,6
		57	8.86000	9.45800	100.00000	0.00000	0.00000	-2.79716 1,2,6
		58	8.86000	10.70100	100.00000	0.00000	0.00000	-2.86613 1,2,6
		59	8.86000	11.94400	100.00000	0.00000	0.00000	-2.87149 1,2,6
		60	8.86000	13.18700	100.00000	0.00000	0.00000	-2.81232 1,2,6
		61	8.86000	14.43000	100.00000	0.00000	0.00000	-2.68076 1,2,6
		62	8.86000	14.43000	100.00000	0.00000	0.00000	-2.68076 1,2,6
		63	9.29000	14.43000	100.00000	0.00000	0.00000	-2.30107 1,2,6
		64	9.29000	14.43000	100.00000	0.00000	0.00000	-2.30107 1,2,6

1 - Data point coincident with displacement location. Its displacement has been added to those calculated by Xdisp.

2 - Data point coincident with horizontal movement calculation point for a specific building. Its displacement has been added before performing building damage calculations.

6 - Data point coincident with vertical movement calculation point for a specific building. Its displacement has been added before performing building damage calculations.

Ref.					1							
Excavation Name:					Underpins							
Surface level [m]:					100.00							
Contribution:					Positive							
Corner	x	y	Base Level	Arc Enabled	Stiffened	Prev. Side:	Prev. Side:	Prev. Side:	Next Side:	Next Side:	Next Side:	
	[m]	[m]	[m]			d [m]	pl [%]	p2* [%]	d [m]	pl [%]	p2* [%]	
1	1.5700	0.0	98.000	Yes	No	-	-	-	-	-	-	
2	6.4300	0.0	98.000	Yes	No	-	-	-	-	-	-	
3	6.4300	21.710	98.000	Yes	No	-	-	-	-	-	-	
4	0.0	21.710	98.000	Yes	No	-	-	-	-	-	-	
5	0.0	2.7100	98.000	Yes	No	-	-	-	-	-	-	
6	1.5700	2.7100	98.000	Yes	No	-	-	-	-	-	-	

Side	x1 [m]	y1 [m]	x2 [m]	y2 [m]	G.M. Curve: Vertical	G.M. Curve: Horizontal
1	1.5700	0.0	6.4300	0.0	Underpin - ver	Underpin - hor
2	6.4300	0.0	6.4300	21.710	Underpin - ver	Underpin - hor
3	6.4300	21.710	0.0	21.710	Underpin - ver	Underpin - hor
4	0.0	21.710	0.0	2.7100	Underpin - ver	Underpin - hor
5	0.0	2.7100	1.5700	2.7100	Underpin - ver	Underpin - hor
6	1.5700	2.7100	1.5700	0.0	Underpin - ver	Underpin - hor

```

Curve Name: underpin - ver
Coordinates: [Distance from wall / wall depth or max. excavation depth (x), Depth / wall
              depth or max. excavation depth (y), Settlement / wall depth or max. excavation
              depth (z) (%)
              [0.000,0.000,0.250][1.000,0.000,0.000]

Curve Fitting Method: Polynomial
x Order: 1
y Order: 0
Polynomial: z = -2.50000E-1x + 2.50000E-1
Coeff. of Determination: 1.00000

```

```

Curve Name: Underpin - hor
Coordinates: [Distance from wall / wall depth or max. excavation depth (x), Depth / wall
depth or max. excavation depth (y), Horizontal movement / wall depth or max.
excavation depth (z) (%)
[0.000,0.000,0.250][1.000,0.000,0.000]
Curve Fitting Method: Polynomial
x Order: 1
y Order: 0
Polynomial: z = -2.50000E-1x + 2.50000E-1
Coeff. of Determination: 1.00000

```

Ref.	Name	0 (Negligible) to 1 (Very Slight)	1 (Very Slight) to 2 (Slight)	2 (Slight) to 3 (Moderate)	3 (Moderate) to 4 (Severe)
1	Burland Strain Limits	0.0	500.00E-6	750.00E-6	0.0015000

Ref.	Building Name	Sub-Building Name	Displacement Line			Distance Along Line: Start	Distance Along Line: End	Vertical Offsets from Line for Vertical Movement Calculations	Vertical Displacement Limit Sensitivity	Damage Category Strains	Poisson's Ratio	E/G
						[m]	[m]	[m]	[mm]			
1	14 Hampstead Hill	Sub 1	No.	14	Hampstead Hill Gardens 1	0.00000	15.50000	0.0	0.10000	Burland Strain Limits	0.20000	2.60000
2	14 Hampstead Hill	Sub 2	No.	14	Hampstead Hill Gardens 2	0.00000	2.98000	0.0	0.10000	Burland Strain Limits	0.20000	2.60000
3	14 Hampstead Hill	Sub 3	No.	14	Hampstead Hill Gardens 3	0.00000	2.49000	0.0	0.10000	Burland Strain Limits	0.20000	2.60000
4	14 Hampstead Hill	Sub 4	No.	14	Hampstead Hill Gardens 4	0.00000	8.57000	0.0	0.10000	Burland Strain Limits	0.20000	2.60000
5	14 Hampstead Hill	Sub 5	No.	14	Hampstead Hill Gardens 5	0.00000	17.99000	0.0	0.10000	Burland Strain Limits	0.20000	2.60000
6	12 Hampstead Hill	Sub 6	No.	12	Hampstead Hill Gardens 1	0.00000	7.42000	0.0	0.10000	Burland Strain Limits	0.20000	2.60000
7	12 Hampstead Hill	Sub 7	No.	12	Hampstead Hill Gardens 2	0.00000	0.69000	0.0	0.10000	Burland Strain Limits	0.20000	2.60000
8	12 Hampstead Hill	Sub 8	No.	12	Hampstead Hill Gardens 3	0.00000	2.84000	0.0	0.10000	Burland Strain Limits	0.20000	2.60000
9	12 Hampstead Hill	Sub 9	No.	12	Hampstead Hill Gardens 4	0.00000	12.43000	0.0	0.10000	Burland Strain Limits	0.20000	2.60000
10	12 Hampstead Hill	Sub 10	No.	12	Hampstead Hill Gardens 5	0.00000	0.42900	0.0	0.10000	Burland Strain Limits	0.20000	2.60000
11	12 Hampstead Hill	Sub 11	No.	12	Hampstead Hill Gardens 6	0.00000	3.42900	0.0	0.10000	Burland Strain Limits	0.20000	2.60000
12	12 Hampstead Hill	Sub 12	No.	12	Hampstead Hill Gardens 7	0.00000	1.71400	0.0	0.10000	Burland Strain Limits	0.20000	2.60000
13	12 Hampstead Hill	Sub 13	No.	12	Hampstead Hill Gardens 8	0.00000	1.57000	0.0	0.10000	Burland Strain Limits	0.20000	2.60000
14	12 Hampstead Hill	Sub 14	No.	12	Hampstead Hill Gardens 9	0.00000	1.62400	0.0	0.10000	Burland Strain Limits	0.20000	2.60000
15	12 Hampstead Hill	Sub 15	No.	12	Hampstead Hill Gardens 10	0.00000	3.42900	0.0	0.10000	Burland Strain Limits	0.20000	2.60000

Ref.	Building Name	Sub-Bldg Name	Height	Default	Hogging:	Hogging:	Hogging:	Sagging:	Sagging:	Sagging:
					2nd Mom. of Area (per unit width)	Dist. of Bending Strain from N.A.	Dist. of N.A. from Edge of Beam in Tension	2nd Mom. of Area (per unit width)	Dist. of Bending Strain from N.A.	Dist. of N.A. from Edge of Beam in Tension
			[m]		[m <sup>3</sup> ]	[m]	[m]	[m <sup>3</sup> ]	[m]	[m]
1	14 Hampstead Hill	Sub 1	12.000	Yes	576.00	12.000	12.000	144.00	6.0000	6.0000
2	14 Hampstead Hill	Sub 2	12.000	Yes	576.00	12.000	12.000	144.00	6.0000	6.0000
3	14 Hampstead Hill	Sub 3	12.000	Yes	576.00	12.000	12.000	144.00	6.0000	6.0000
4	14 Hampstead Hill	Sub 4	12.000	Yes	576.00	12.000	12.000	144.00	6.0000	6.0000
5	14 Hampstead Hill	Sub 5	9.000	Yes	576.00	12.000	12.000	144.00	6.0000	6.0000
6	12 Hampstead Hill	Sub 6	9.000	Yes	243.00	9.000	9.000	60.750	4.5000	4.5000



# SOILTECHNICS LIMITED

14A Hampstead Hill Gardens

Job No.	Sheet No.	Rev.
STS5065		
Drg. Ref.		
Made by AKW	Date 16-Dec-2020	Checked Date

Ref.	Building Name	Sub-Building Name	Height	Default	Hogging:	Hogging:	Hogging:	Sagging:	Sagging:	Sagging:
					2nd Mom. of Area	Dist. of Bending	Dist. of N.A. from	2nd Mom. of Area	Dist. of Bending	Dist. of N.A. from
7	12 Hampstead Hill	Sub 7	9.0000	Yes	243.00	9.0000	9.0000	60.750	4.5000	4.5000
8	12 Hampstead Hill	Sub 8	9.0000	Yes	243.00	9.0000	9.0000	60.750	4.5000	4.5000
9	12 Hampstead Hill	Sub 9	9.0000	Yes	243.00	9.0000	9.0000	60.750	4.5000	4.5000
10	12 Hampstead Hill	Sub 10	9.0000	Yes	243.00	9.0000	9.0000	60.750	4.5000	4.5000
11	12 Hampstead Hill	Sub 11	9.0000	Yes	243.00	9.0000	9.0000	60.750	4.5000	4.5000
12	12 Hampstead Hill	Sub 12	9.0000	Yes	243.00	9.0000	9.0000	60.750	4.5000	4.5000
13	12 Hampstead Hill	Sub 13	9.0000	Yes	243.00	9.0000	9.0000	60.750	4.5000	4.5000
14	12 Hampstead Hill	Sub 14	9.0000	Yes	243.00	9.0000	9.0000	60.750	4.5000	4.5000
15	12 Hampstead Hill	Sub 15	9.0000	Yes	243.00	9.0000	9.0000	60.750	4.5000	4.5000


### Legend

Excavation

### Building Results


- < Sensitivity
- Cat. 0 (Negligible)
- Cat. 1 (Very Slight)
- Cat. 2 (Slight)
- Cat. 3 (Moderate)
- Cat. 4 (Severe)

- Displacement Grids
- Displacement Lines
- Imp. Displacements






Job No.	Sheet No.	Rev.
STS5065		
Drg. Ref.		
Made by AKW	Date 16-Dec-2020	Checked Date



Job No.	Sheet No.	Rev.
STS5065		
Drg. Ref.		
Made by AKW	Date 16-Dec-2020	Checked Date



### Legend

Excavation


### Building Results

< Sensitivity  
Cat. 0 (Negligible)  
Cat. 1 (Very Slight)  
Cat. 2 (Slight)  
Cat. 3 (Moderate)  
Cat. 4 (Severe)

### Displacement - Resultant - Elastic

1.000 mm  
2.000 mm  
3.000 mm  
4.000 mm  
5.000 mm  
6.000 mm  
7.000 mm  
8.000 mm

Displacement Grids  
Displacement Lines  
Imp. Displacements





**SOILTECHNICS  
LIMITED**

14A Hampstead Hill Gardens

Job No.	Sheet No.	Rev.
STS5065		
Drg. Ref.		
Made by AKW	Date 16-Dec-2020	Checked Date

**Specific Building Damage Results - Critical Values for All Segments within Each Sub-Building**

Stage Ref.	Stage Name	Specific Building Ref.	Specific Building Name	Sub-building Name	Vertical Offset from Line for Vertical Movement Calculations [m]	Deflection Ratio [%]	Average Horizontal Strain [%]	Max Slope [mm]	Max Settlement [%]	Max Tensile Strain [%]	Max Gradient of Horizontal Displacement Curve	Max Gradient of Vertical Displacement Curve	Min Radius of Curvature (Hogging) [m]	Min Radius of Curvature (Sagging) [m]	Damage Category
0	Base Model	1	14 Hampstead Hill	Sub 1	0.0	0.0060168	0.0	303.03E-6	0.0	0.0059156	0.0	303.03E-6	-	-	0 (Negligible)
		2	14 Hampstead Hill	Sub 2	0.0	0.026053	0.0	0.0010797	0.0	0.025814	0.0	0.0010797	-	-	0 (Negligible)
		3	14 Hampstead Hill	Sub 3	0.0	0.0	0.057229	-183.44E-6	0.0	0.057229	-571.96E-6	-183.44E-6	-	-	1 (Very Slight)
		4	14 Hampstead Hill	Sub 4	0.0	0.031087	0.0	0.0019049	0.0	0.030206	0.0	0.0019049	-	979.39	0 (Negligible)
		5	14 Hampstead Hill	Sub 5	0.0	0.034799	0.015842	-0.0024531	0.0	0.050919	-791.48E-6	-0.0024531	-	784.27	1 (Very Slight)
		6	12 Hampstead Hill	Sub 6	0.0	0.0079735	0.0	486.54E-6	0.0	0.0077583	0.0	486.54E-6	-	-	0 (Negligible)
		7	12 Hampstead Hill	Sub 7	0.0	0.0	0.0	207.18E-6	0.0	35.763E-9	0.0	207.18E-6	-	-	0 (Negligible)
		8	12 Hampstead Hill	Sub 8	0.0	0.022352	0.0	947.96E-6	0.0	0.021795	0.0	947.96E-6	-	-	0 (Negligible)
		9	12 Hampstead Hill	Sub 9	0.0	0.046684	0.0	0.0020508	0.0	0.044837	0.0	0.0020508	-	471.54	0 (Negligible)
		10	12 Hampstead Hill	Sub 10	0.0	0.0	0.0	-0.0017660	0.0	35.763E-9	0.0	-0.0017660	-	-	0 (Negligible)
		11	12 Hampstead Hill	Sub 11	0.0	0.058036	0.0	-0.0021622	0.0	0.055953	0.0	-0.0021622	-	541.98	1 (Very Slight)
		12	12 Hampstead Hill	Sub 12	0.0	0.072676	0.0	-0.0023515	0.0	0.072007	0.0	-0.0023515	-	291.83	1 (Very Slight)
		13	12 Hampstead Hill	Sub 13	0.0	0.042642	0.0	-0.0012836	0.0	0.042312	0.0	-0.0012836	-	-	0 (Negligible)
		14	12 Hampstead Hill	Sub 14	0.0	0.027921	0.0	-635.57E-6	0.0	0.027690	0.0	-635.57E-6	-	-	0 (Negligible)
		15	12 Hampstead Hill	Sub 15	0.0	0.0088007	0.0	-317.90E-6	0.0	0.0085890	0.0	-317.90E-6	-	-	0 (Negligible)



Job No.	Sheet No.	Rev.
STS5065		
Drg. Ref.		
Made by AKW	Date 16-Dec-2020	Checked Date

