

16a Lyndhurst Gardens, Hampstead, London, NW3 5NS Entrance piers



1. Existing pier at No 16 adjacent to 16a.



2. Existing pier at No 18 adjacent to 16a.



3. Existing pier at No16a adjacent to No 16.



New pier in progress at No16a adjacent to No 18, before being cleaned.



5. New capping piece, dimensioned exactly to dimensioned to the existing column cap.



Intermediate capping piece, exactly to the existing column.



7. New intermediate terracotta piece.



8. New wall capping piece.



9. Existing low-level wall between No16a & No18



10. New terracotta & new brick in Position on No 18 pier .The new brick is a Saxon Red Multi.





crease, terracotta band and replacement brick,

Saxon Red Multi.

11. Pier adjacent to No18 showing replacement 12. Existing brick wall between 16 & 16a.

The above photographs show the intended replacement pier elements in comparison with the existing surrounding piers & wall at No16 & No18 Lyndhurst Gardens.

All replacement elements were carefully chosen to match in with the existing ones by Tooley Foster a RIBA architect who considered the overall makeup of the brick, colour and surface texture when choosing a replacement.

The terracotta was colour matched with the existing caps and will in time assume the same patina as the current install.

The bricks have been made as bespoke to suit this install, they are a Saxon Red Multi and have been measured and manufactured to the same squint as those currently installed within the remaining sections of the existing pier adjacent to No18.

We intend to install the elements using a lime mortar as they would have been originally and then finished with weather struck pointing, again to match the existing piers.

Both piers will be built to the same height as those currently adjacent.