

Tree Work Specifications

For
Beechwood Estate
Hampstead Lane
London
N6 4RT

The trees were viewed from East - West starting at the main gate.
The trees are numbered as I walked around – I did not use the old tags

T1 Lime

Remove all major deadwood from the crown

T2 Lime - previously reduced due to storm damage

Crown reduce the height and spread by 33%

Remove all major deadwood from the crown

T3 Sycamore

No action required at present

T4 Sycamore

Remove one low branch over the road

Remove all major deadwood from the crown

T5 Sycamore

Remove one low branch over the road

Reduce the second low branch over the road by 3m-3.5m

Remove all major deadwood from the crown

T6 Yew

No action required at present

T7 Lime

Reduce the low branches over the road by 2m-2.5m

Remove all major deadwood from the crown

T8 Yew

Reduce the unruly branches over the pavement to shape

T9 Yew

Reduce the unruly branches over the pavement to shape

T10 Lime

Reduce the height by 6m-7m

Reduce the remaining spread to shape

Remove all major deadwood from the crown

T11 Lime

No action required at present

T12 Yew

No action required at present

T13 Lime

Remove all major deadwood from the crown

T14 Yew

No action required at present

T15 Lime

Remove all major deadwood from the crown

T16 Lime

No action required at present

T17 Lawson Cypress

No action required at present

T18 Lime

Remove the low branches over the pavement and road to give a clearance of 3m & 6m respectively

Remove all major deadwood from the crown

T19 Yew

Remove the low branches overhanging the pavement to give a clearance of 3m

T20 Sycamore

Remove all major deadwood from the crown

T21 Lime

Remove all major deadwood from the crown

T22 Sycamore

Remove all major deadwood from the crown

T23, T24 & T25 Limes

Remove the low branches overhanging the pavement and road to give a clearance of 3m & 6m respectively

Remove all major deadwood from the crown

T26, T27 & T28 Cherries - these trees are in a poor condition

Cut entire trees to ground level

Grind out the stumps

T 29 - T37 Limes

Remove the low branches overhanging the pavement and road to give a clearance of 3m & 6m respectively

Remove all major deadwood from the crown

Reduce the branches overhanging the bungalow by 3m-3.5m

T38 Cherry - this tree is 70-80% dead

Cut entire tree to ground level

Grind out the stump