

20056

38 Chester Terrace

Schedule of Proposed Works

May 2021 (Revision C)

General Demolition

- All ceilings, skirtings and cornices are not original and will be replaced where required;
- Internal doors are not original and will be replaced where required*;
- All floor finishes are not original and will be replaced;
- Existing plumbing, mechanical and electrical installations (where not owned or maintained by the landlord) will be removed and replaced.

Method for the replacement of the non-original ceiling

- The ceilings are not original: they are comprised of plasterboard, on a metal lathe substrate;
- Where ceilings are proposed to be demolished, they will be removed using hand power tools and removed from site:
- A new plasterboard ceiling will be installed on a proprietary metal suspended ceiling frame.

Existing Room		Works
rELG.01 Wine Cellar	Proposals	 Reinstate or repair existing masonry floor. Install joinery Install ventilation
rELG.08 Vault	Demolition	Remove existing plant and earth down to level of original screed.
	Proposals	 Reinstate or repair existing masonry floor. Install steps to suit; Install plant; Install new louvered door.
rELG 09 Vault	Demolition	 Remove existing plant and earth down to level of original screed.
	Proposals	 Reinstate or repair existing masonry floor. Install steps to suit; Install plant; Install new louvered door.
rELG.02 Utility Room	Demolition	Demolish non-original partition walls and joinery;Remove existing plant.
	Proposals	 Install new partition wall; Install porcelain floor with underfloor heating; Install new suspended ceiling; Install new skirtings; Fit new kitchen (re-using existing hob extraction rout)



		Install new plant.
rELG.03 Hallway	Demolition	 Demolish non-original partition walls and joinery; Remove mechanical and electrical installations.
	Proposals	 Install new partition walls; Install porcelain floor with underfloor heating; Install suspended ceiling; Install new skirtings; Install new lift car and doors to existing lift shaft.
		Install new powder room including: Natural stone floor with electric underfloor heating; Suspended ceilings; Sanitary fitting; Bathroom cabinetry with mirrored doors.
rELG.04 Lobby	Demolition	Demolish non-original partition walls and joinery.
	Proposals	 Install new partition wall; Install porcelain floor with underfloor heating; Install suspended ceiling; Install new skirtings; Fit new utility joinery.
rELG.05 Staff En-suite	Demolition	 Demolish non-original partition walls and joinery; Remove sanitary, mechanical and electrical installations.
	Proposals	Install porcelain floor with underfloor heating;Install suspended ceiling;
rELG.06 Staff Bedroom	Demolition	Demolish non-original partition walls and joinery.
	Proposals	 Install porcelain floor with underfloor heating; Install suspended ceiling; Install new sanitary and spa fittings; Fit floor-to-ceiling joinery.
rELG.07 Media/ Family Room	Demolition	 Remove existing slab and floor finishes; non-original partition walls and joinery; Remove mechanical installations.
	Proposals	 Install vinyl floor with underfloor heating; Install new skirtings, Install suspended ceiling; Fit floor-to-ceiling joinery.

Upper Ground Floor		
Existing Room		Works
rEUG.01 Entrance Hall	Proposals	Install new natural stone floor with underfloor heating; • Refurbish and redecorate existing ceiling and moulded plaster cornice;



		Refurbish and redecorate existing skirtings.
rEUG.02 Hallway	Demolition	Remove non-original lift door.
	Proposals	 Install new natural stone floor with underfloor heating; Refurbish and redecorate existing ceiling and cornice; Refurbish and redecorate existing skirtings; Make good existing staircase, spindles, handrail and new carpet runner; Install new lift car and doors to existing lift shaft.
rEUG.03 WC	Demolition	Demolish part non-original partition wall; • Remove sanitary, mechanical and electrical installations.
	Proposals	Install new powder room including:
rEUG.04 Kitchen	Demolition	Demolish non-original partition walls; • Remove non-original suspended ceiling.
	Proposals	 Install new partition wall; Install natural stone floor with underfloor heating; Install suspended ceiling with moulded plaster cornice; Fit new kitchen (re-using existing hob extraction route).
rEUG.05 Dining Room	Demolition	Remove non-original fireplace surround, hearth and basket.
	Proposals	 Install natural stone floor with underfloor heating; Refurbish and redecorate existing ceiling and cornice; Refurbish and redecorate existing skirtings; Install new fireplace surround, hearth and basket.

First Floor		
Existing Room		Works
rE1.01 Drawing Room	Demolition	Remove non-original fireplace surround, hearth and basket.
	Proposals	 Install new natural stone floor with underfloor heating; Refurbish and redecorate existing ceiling and cornice; Refurbish and redecorate existing skirtings; Install new fireplace surround, hearth and basket; Install partition wall between drawing room and study
rE1.02 Hallway	Demolition	Remove non-original lift door.
	Proposals	Install new natural stone floor with underfloor heating;Refurbish and redecorate existing ceiling;



		 Refurbish and redecorate existing skirtings; Make good existing staircase, spindles, handrail and new carpet runner; Install new moulded plaster cornice
rE1.03 Study	Proposals	 Install new hardwood floor with underfloor heating; Refurbish and redecorate existing skirtings; Install new partition wall; Install suspended ceiling with moulded plaster cornice and recessed ceiling coffer Install new powder room including: Natural stone floor with electric underfloor heating; Suspended ceilings with moulded plaster cornice; Sanitary fitting; Bathroom cabinetry with mirrored doors.

Second Floor		
Existing Room		Works
rE2.01 Master Bedroom	Demolition	Demolish non-original partition walls and joinery.
	Proposals	 Install carpet floor with underfloor heating; Install new skirtings, Install suspended ceiling with moulded plaster cornice; Install new partition walls between master bedroom and hallway and master bedroom and ensuite; Fit floor-to-ceiling joinery.
rE2.02 Hallway	Demolition	Remove non-original lift door.
	Proposals	 Refurbish and redecorate existing ceiling; Install new natural stone floor with underfloor heating; Install new moulded plaster cornice; Install new skirtings; Make good existing staircase, spindles, handrail and new carpet runner; Install new lift car and doors to existing lift shaft.
rE2.03 WC	Demolition	Demolish part non-original partition walls; • Remove sanitary, mechanical and electrical installations.
rE2.04 Master En-suite	Demolition	Demolish part non-original partition walls; • Remove sanitary, mechanical and electrical installations.
	Proposals	 Install new partition wall; Install Master En-Suite including; Natural stone floor with electric underfloor heating; Suspended ceilings with new moulded plaster cornice; Sanitary fittings; Bathroom cabinetry with mirrored doors.



rE2.05 Walk-through- wardrobe	Demolition	Demolish non-original partition walls and joinery.
	Proposals	 Install new partition wall; Install carpet floor with underfloor heating; Fit floor-to-ceiling joinery.

Third Floor		
Existing Room		Works
rE3.01 Bedroom IV	Demolition	Demolish non-original joinery.
	Proposals	 Install carpet floor with underfloor heating; Install suspended ceiling with moulded plaster cornice; Install new skirtings; Fit floor-to-ceiling joinery.
rE3.02 Hallway	Demolition	Remove non-original lift door;
	Proposals	 Install new carpet floor with underfloor heating; Install suspended ceiling with moulded plaster cornice; Install new skirtings; Make good existing staircase, spindles, handrail and new carpet runner; Install new lift car and doors to existing lift shaft; Install new timber staircase, new spindles, handrail to match below staircase to roof level; Install new loft access hatch; Install new hinged access rooflight.
rE3.03 Bedroom V	Demolition	Demolish non-original partition walls and joinery.
	Proposals	 Install carpet floor with underfloor heating; Install suspended ceiling with moulded plaster cornice; Install new skirtings; Fit floor-to-ceiling joinery.
rE3.04 Bedroom II	Demolition	Demolish non-original wall partitions and joinery.
	Proposals	 Install carpet floor with underfloor heating; Install suspended ceiling with moulded plaster cornice; Install new skirtings; Fit floor-to-ceiling joinery.



rE3.05 En-suite	Demolition	Demolish non-original wall partitions; Remove rooflight; Demove sanitary, mechanical and electrical installations.
	Proposals	 Remove sanitary, mechanical and electrical installations. Install En-Suite including: Porcelain floor with electric underfloor heating; Suspended ceilings; Sanitary fitting; Bathroom cabinetry with mirrored doors; Install new conservation rooflight.
rE3.06 Bathroom	Demolition Proposals	Demolish non-original wall partitions; Remove rooflight; Remove sanitary, mechanical and electrical installations. Install En-Suite including: Porcelain floor with electric underfloor heating; Suspended ceilings; Sanitary fitting; Bathroom cabinetry with mirrored doors; Install new conservation rooflight.
rE3.07 Bedroom III	Demolition Proposals	 Demolish non-original wall partitions and joinery. Install carpet floor with underfloor heating; Install suspended ceiling with moulded plaster cornice; Install new skirtings; Fit floor-to-ceiling joinery.

Roof		
Existing Room		Works
Roof	Demolition Proposals	 Demolish non-original flat section of roof; Install new timber roof structure and waterproofing; Install raised timber deck and timber cladding to vertical faces of mansard; Install new joinery units and worktop; Clad existing lift car overrun and install worktop on top;

^{*} Refer to Door and Window Schedule for proposed works to doors and windows

^{**}For the location of the rooms refer to the Existing Plans P1000 series.

^{***}Refer to the Design and Access Statement Section 3.5 for proposed internal details.