

Tree protection plan

Location of trees, categorisation & protection/management proposals

146-150 Royal College Street, Camden, London

Barrell Plan Ref: 19268-4

barrell

TREE CONSULTANCY

Permission is granted to scale from this drawing for Local Authority Planning Approval purposes relating to tree protection measures only. Where applicable this drawing is to be read in conjunction with the arboricultural report. This drawing is the copyright of Barrell Tree Consultancy 2021. ©

This drawing to be reproduced in colour only.

www.barrelltreecare.co.uk

TX

BS category B

Tree of moderate quality

TX

BS category C

Trees of low quality

TX

Trees to be removed

Proposed layout

Estimated tree positions not included on original land survey and/or adjusted crown spreads

Proposed new extra heavy standard Dawn redwood.

Attention LPA Tree Officer - if you would like a 'to scale' printed version of this plan please contact us on 01425 651470 or email 'enquiries@barrelltreecare.co.uk'

Drawing References
Site topo = (April-23-2021) 1929_P_00_100 Rev A
Layout = (April-23-2021) 1929_P_00_100 Rev A

0 Metres 1 2 3 4 5 6 7 8 9 10

Scale: 1:100 @ A2

N

For detailed landscaping refer to the Gluckmansmith Landscape Scheme.

G1

T2

Eagle Mews

How to use plan

More detailed guidance on each Site Guidance Note (SGN) can be found in a printed hard copy compilation of all the SGNs, **Manual for Managing Trees On Development Sites version 2.1**, issued to the Site Manager at the pre-commencement site meeting (**Note:** This should be retained on site throughout the duration of works). Additionally, an electronic pdf compilation of all the SGNs, was submitted with this drawing to the local planning authority and the client. Alternatively, a pdf of each SGN can be downloaded by:

- clicking the image links in the electronic pdf version of this plan;
- holding a mobile phone QR (Quick Response) code reader over the QR code in the paper version of this plan; or,
- visiting our website at <https://www.barrelltreecare.co.uk/resources/technical-guidance>

| Tree No | Species | Category | RPA Radius | Tree Works |
|--------------------|-------------------------------------|----------|------------|---|
| All retained trees | | | | Carry out safety check and lift over site to 3–4m as necessary. |
| G1 | Birch, ash, cherry, Portugal laurel | C | 3.0 | Fell |
| T2 | Birch | B | 4.8 | Fell |

SGN 1

Monitoring tree protection

Always:

✓

have a pre-commencement meeting with the tree consultant before development starts

✓

use the tree consultant to regularly check that protection remains fit for purpose

✓

use the tree consultant to supervise work in RPAs

✓

keep a written record of supervision