

- KEY
- ①

Existing 570mm projecting sign to be removed and make good.

②

Existing ATM surround - black blue alucobond to be removed. Frosted vinyl to windows

③

Existing ADT alarm box

④

Existing external grade security camera with dome to be removed and make good.

⑤

Existing frosted vinyl applied on windows

⑥

Existing night safe to be removed. Existing night safe cut out hole to be infilled to match existing black marble

⑦

Existing handrail

⑧

Existing branch nameplate to be removed and make good.

⑨

Existing push/pull vinyl

⑩

Existing 200mm individual letter signage to be removed and make good.

⑪

Existing external ATM to be removed. Existing ATM cut out hole to be infilled to match existing black marble

STATUTORY STATUS	
LISTED	NO
CONSERVATION	NO

NOTE
This drawing has been prepared from historical information that cannot be guaranteed accurate.
Responsibility is not accepted for errors made by others in scaling from this drawing. All construction information should be taken from figured dimensions only. All dimensions should be checked on site prior to the manufacture of any components. No services should pass through or over the Boxes & Parcels room. No sprinklers to be located in the Comms Room

HATCHING

New Secure Partition wall

New Partition wall

Book Room Secure wall

Existing Partition wall

Structural wall

Area not in scope

Barrier Matting

Banking Hall Vinyl Flooring

Staff Room Vinyl Flooring

20.05.2021 A ICT Blue Alucobond to be removed as requested by Planning.

DATE : REV DRAWN CHECKED NOTES.

ISG
Boleyn House,
St Augustines
Business Park,
Whitstable,
Kent CT5 2QJ

Project

KENTISH TOWN

230/234 KENTISH TOWN,
LONDON
NW5 2BU
PIM No.

Drawing Title

FRONT ELEVATION

AS PROPOSED

CLOSURE 2021

Branch Sort Code	Branch ID	Supplier Project No	
20-44-86	04	BY106570	
Scale	Drawn	Checked	Date
1:100@A3	PC	-	18/02/2021
Drg.No			Revision
BY106570_031			A
Architectural Practice: ISG Design Hub			

SCALE

0

1m

5m

10m

PLANNING