


Indicative only

**Issue:** Proposed garden room situated within the RPA of trees T04-T06.  
**Solution:** Foundations are to be designed to an engineering specification in conjunction with arboricultural advice and site investigations.



**Arboricultural Impacts**

Impacts	No. of trees
Trees to be removed	0
Group 1 hedges to be removed (Partial removal of groups)	0 (0)
Trees with proposed retention into RPA	3
Group 1 hedges with proposed retention into RPA	0
Trees that will require pruning	1
Group 1 hedges that will require pruning	0
Trees to be transplanted	0
Group 1 hedges to be transplanted	0

No.	Species	Proposed structure	Inclusion
T04	London Plane	Garden Room	RPA
T05	Common Pear	Garden Room	RPA
T08	Myrsine Plum	Garden Room	RPA

**Arboricultural Impacts - RPAs (Area)**

No.	Species	RPA (m <sup>2</sup> )	Inclusion (%)
T04	London Plane	102.9	18.7
T05	Common Pear	40.7	2.1
T08	Myrsine Plum	16.3	8.2

**Tree Work Schedule**

No.	Species	Works	Category
T08	Myrsine Plum	Prune Crown W to achieve 3m clearance adjacent to wall	C1

All tree work is to be undertaken in accordance with British Standard BS 5822:2010 Tree work - Recommendations.

All tree work is to be undertaken in accordance with British Standard BS 5822:2010 Tree work - Recommendations.

Design for foundations that would minimise the adverse impact upon trees should include particular attention to the existing levels, proposed finished levels and cross sectional details. Site specific and specialist advice should be sought from the project engineers and arboriculturist.

Root damage can be minimised by using:

- Files with site investigation used to be determined their optimal location whilst avoiding damage to roots important for the stability of the tree, by means of hand tools or compressed air soil displacement, to a minimum depth of 600mm.
- Ground screws (or similar) with site investigation used to be determined their optimal location whilst avoiding damage to roots important for the stability of the tree, by means of hand tools or compressed air soil displacement, to a minimum depth of 600mm.
- Beams, laid at or above ground level, and cambered as necessary to avoid tree roots identified by site investigation.
- Multidimensional confinement system such as CelwebTRP creating a no-dig subbase bearing upon the existing soil level.

**Piling/ground screws**

Where piling or ground screws are to be installed near to trees, the smallest practical pile diameter should be used, as this reduces the possibility of cutting major tree roots, and reduces the size of the rig required to sink the piles. If a piling mat is required, this should conform to the parameters for ground bearing. Use of the smallest practical piling rig is also important where piling within the branch spread is proposed, as this can reduce the need for access facilitation pruning. The pile type should be selected bearing in mind the need to protect the soil and adjacent roots from the potentially toxic effects of unconsolidated concrete, e.g. sleeved bored piles or screw piles.

**Multidimensional confinement system**

Existing vegetation may be removed with hand tools or sprayed with an approved non residual herbicide such as 'Glyphosate'. The new hard surfacing will be constructed using a 'No Dig' surfacing situated entirely above the existing soil surface and where needed using a proprietary cellular confinement system (Geoweb or similar) laid over a 30mm geogrid (Densa TriAx or similar). Prior to this any small hollows on the surface may be filled with clean sharp sand (not builders sand) to a maximum depth of 50mm. The Geoweb will be back filled by hand with a no fines aggregate of 20mm - 30mm. The area of Geoweb will be covered with a permeable geotextile fabric, and the finished wearing course laid on top. Edge supports of an appropriate size and strength should be set above ground level and secured with haunching or steel pins driven into the ground, the outer edge of the supports may be backfilled with clean top soil.

**Utility apparatus**

**Underground utility apparatus**

Mechanical trenching for the installation of underground apparatus and drainage severs any roots present and can change the local hydrology in a way that adversely affects the health of the tree. For this reason, particular care should be taken in the route and methods of installation of all underground apparatus. Wherever possible, apparatus should be routed outside of RPAs. Where this is not possible, it is preferable to keep apparatus together in common ducts, all inspection chambers should be sited outside of the RPAs.

Where underground apparatus is to pass within the RPAs, details plans showing the proposed route should be drawn up in conjunction with the project arboriculturist. In such cases trenchless insertion methods should be used with entry and retrieval pits being located outside of the RPAs. If this option is not feasible and providing roots can be retained and protected excavations should be undertaken using hand held tools (e.g. spades, forks, shovels) or a combination of trenchless and manual excavation (broken trench).

Any design and installation should be undertaken in accordance with the National and Utilities Guidelines (NAG).

**Above-ground utility apparatus**

Above-ground apparatus including CCTV cameras and lighting) should be sited to avoid the need for detrimental tree pruning, as such the current and future crown size of the tree should be assessed. Tree branches can be pruned back with care to provide space, though it is not appropriate for regular and significant tree work to be undertaken unless this is a suitable management outcome for the tree. Any pruning should be undertaken in accordance with BS3998:2010.

Rev.	Date	Notes
A	18/09/21	Amended proposal drawing

**ARBTECH**  
Unit 3, Well House Barns, Chester, CH4 0DH  
https://arbtech.co.uk, 01244 661170

Project: 63 Aberdare Gardens, Camden, London, NW6 3AN

Client: Mr Paul

Drawing: Arboricultural Impact Assessment

Based on: P2103-A1004


Drawing No: Arbtch AIA 01 Rev: A  
Date: June 2021 Scale: 1:100 @ A0 Drawn: JCH

Key:

Tree No.	Tree Category	Trunk	Category
T01	Tree	Trunk	Category 1 trees

Inclusion	Category
Garden	Category 1 trees
Roots	Category 2 trees



61  
71  
ABERDARE GARDENS