

Project No  
**955**  
Document  
PL05

Project  
22 Cumberland Terrace  
Title  
**Schedule of Works**

Date  
30/06/2021  
Issue  
P01  
Author  
SK



<b>1 Demolition Works</b>	
1.1	Bedrooms: Fitted wardrobes to be removed.
1.2	Master Ensuite: Door to be removed. Sanitaryware to be removed.
1.3	Master Bedroom: Fitted wardrobes and joinery doors to be removed. Dropped ceiling detail to be removed and opening to be adjusted.
1.4	Dressing Room: Door to be removed. Fitted wardrobes to be removed.
1.5	Breakfast Room: Door to dressing room to be removed. Fixed seating to be removed.
1.6	Kitchen: Kitchen to be removed. Doors from corridor to be removed.
1.7	Kitchen and Bedroom Corridors: Ceilings to be removed.
1.8	Bathroom: Sanitaryware to be removed.
1.9	Dining Room: Dropped Ceiling detail to be removed. Doors to reception room to be removed and opening to be adjusted.
1.10	Reception Room: Dropped ceiling detail to be removed.
<b>2 Proposed Works</b>	
2.1	Bedrooms: New fitted wardrobes to be installed.
2.2	Master Ensuite: Door from corridor to be infilled with lightweight partition. New sanitaryware to be installed.
2.4	Master Bedroom: Existing ceiling to be exposed and made good.
2.5	Dressing Room: Door from corridor to be infilled. New fitted wardrobes to be installed.
2.6	Breakfast Room: Door to Dressing Room be infilled. New fixed seating to be installed.
2.7	Kitchen: New kitchen to be installed. Opening to be altered to suit new kitchen layout and new door to be installed.
2.8	Kitchen and Bedroom Corridors: New ceiling to be installed.
2.9	Dining Room: Existing ceiling to be exposed and made good. New traditional hinged timber framed glazed doors to be installed. Door Opening to be infilled. New fireplace to be installed subject to flue investigation.
2.10	Reception Room: Existing ceilings to be exposed and made good.
2.11	Utility Room: New obscured glazed screen to be introduced and new guest WC to be created.