Abbey Road North:
2 bays lost due to
proposed access

Bus cage markings to be
moved 2m south

21.0

Islands to be removed

Proposed diagonal crossing
layout

Dropped kerb for accessible

Belsize Road East:
Single yellow line added for loading
2.5 bays lost

Belsize Road East:
1 bay converted to Disabled bay

Belsize Road East:
KEEP CLEAR marking for emergency access
1 bay lost

Belsize Road East:
3 bays retained

Belsize Road East:
1 Ambulance bay gained
1.5 bays lost

4.9

KEY:

- SITE BOUNDARY
- EXISTING KERB
- EXISTING ROAD MARKINGS
- KERB TO BE REMOVED
- ROAD MARKING TO BE REMOVED
- PROPOSED KERB
- PROPOSED ROAD MARKINGS
- NEW DROPPED KERBS
- NEW DOUBLE YELLOW LINES
- BUILT OUT

Mark	Revision	Date	Drawn	Chkd	Appd

SCALING NOTE: Do not scale this drawing - any errors or omissions shall be reported to Stantec without delay.

UTILITIES NOTE: The position of any existing public or private sewers, utility services, plant or apparatus shown on this drawing is believed to be correct, but no warranty to this is expressed or implied. Other such plant or apparatus may also be present but not shown. The Contractor is therefore advised to undertake their own investigation where the presence of any existing sewers, services, plant or apparatus may affect their operations.

Drawing Issue Status

FOR INFORMATION

ABBEY ROAD, PHASE 2
EXISTING AND PROPOSED LAYOUT

Client

WATES

Date of 1st Issue	Designed	Drawn
01.07.2021	-	JAD
A3 Scale	Checked	Approved
1:500	ML	MD
Drawing Number		Revision
46830/5501/013		-

Stantec

stantec.com/uk

Copyright reserved
The copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorised by Stantec is forbidden.

LONDON
Tel: 020 3824 6600