

**Project**  
**BEDFORD PASSAGE DEVELOPMENT**

UK & IRELAND  
 Client

**MIDDLESEX ANNEXE LLP**

**Consultant**

**AECOM**  
 Aldgate Tower  
 2 Leman Street  
 London E1 8FA  
 United Kingdom  
 Tel +44 (0) 20 7061 7000  
 www.aecom.com

**Notes**

- Do not scale from this drawing. Work to figured dimensions only.
- This drawing is to be read in conjunction with:
  - AECOM Structural Specifications
  - Design reports
  - Survey and Interpretative Reports
  - Project Specifications and Performance Specifications
  - Health and Safety Hazard Register
  - Relevant drawings and documentation issued by the architect, engineers and specialists.
  - Building Information Model (BIM)
  - Movements and Tolerances Report
- All dimensions are in mm except levels which are in metres and relate to [ordnance datum].
- Any discrepancies shall be referred to the Designer before work commences.

**Issue/Revision**

Rev.	Date	Description	Dm/Chk/Apr
T1	23.10.20	ISSUED FOR TENDER	RHKSF/DW
C2	10.07.20	STAGE 4 REDESIGN UPDATED TO REFLECT NEW LAYOUT	MNDW/DW
C1	27.04.20	CONTRACTORS PROPOSAL ADDED INDICATIVELY TO DRAWING	MNDW/DW
A	25.11.19	ISSUED FOR INFORMATION	MNDW/DW

**Purpose Of Issue**

STAGE 4 TENDER

**Project Number**

60516144

**Sheet Title**

NORTH BOUNDARY WALL WITH THE WELLCOME BUILDING.


**Sheet Number**

MHA-ACM-BW.2-XX-DR-S-1001


Scale: 1 : 25@A1

Rev: T1

This drawing has been prepared for the use of AECOM's client. It may not be used, modified, reproduced or relied upon by third parties, except as agreed by AECOM or as required by law. AECOM accepts no responsibility, and denies any liability whatsoever, to any party that uses or relies on this drawing without AECOM's express written consent. Do not scale this document. All measurements must be obtained from the scaled dimensions.



**Existing Section 1-1**  
 1 : 25



**Proposed Section 1-1 (BW1)**  
 1 : 25

MAIN CONTRACTORS FOR NEW BUILD SITE AND EXISTING BUILDINGS SITE WORKS TO COORDINATE INTERFACES BETWEEN NEW AND EXISTING BUILDINGS, INCLUDING BUT NOT LIMITED TO WATERPROOFING, DRAINAGE CONNECTIONS, UNDERGROUND TANKS, UNDERPINNING ETC.

FOR TYPICAL NOTES, PLEASE REFER TO DRAWING 01001

FOR PROPOSED WATERPROOFING OF CAPPING BEAM AND LINING WALL TO SUIT PROPOSED BASEMENT CONSTRUCTION METHODOLOGY REFER TO DRG: MHA-ACM-00-XX-DR-SE-05001 AND SPECIALISTS DETAILS

REFER TO TYPICAL SLAB, PILE CAP AND GROUND BEAM DETAILS FOR HEAVE PROTECTION AS INDICATED ON DRAWING MHA-ACM-00-XX-DR-SE-05005

FOR BASEMENT GA'S REFER TO THE FOLLOWING DRAWINGS:  
 MHA-ACM-00-B2-DR-SE-01000  
 MHA-ACM-00-B1-DR-SE-01001

FOR BASEMENT SECTIONS, ELEVATIONS AND DETAILS REFER TO THE FOLLOWING DRAWINGS:  
 MHA-ACM-00-XX-DR-SE-03000  
 MHA-ACM-00-XX-DR-SE-03001  
 MHA-ACM-00-XX-DR-SE-04001  
 MHA-ACM-00-XX-DR-SE-04002  
 MHA-ACM-00-XX-DR-SE-04003  
 MHA-ACM-00-XX-DR-SE-04004  
 MHA-ACM-00-XX-DR-SE-04005  
 MHA-ACM-00-XX-DR-SE-04008  
 MHA-ACM-00-XX-DR-SE-04010  
 MHA-ACM-00-XX-DR-SE-04030

REFER TO THE STRUCTURAL CONCRETE SPECIFICATION FOR AREAS OF WATERPROOF CONCRETE.

REFER TO PUDDO DETAILS FOR WATERPROOFING DETAILS.

WATERPROOFING TO FACE OF PILE

1000 THK SUSPENDED SLAB

CORDEK CELLCORE HEAVE PROTECTION ON 50mm BLINDING (REFER TO TABLE ON DRG 05005 FOR CODE/TYPER)

600mm DIAMETER SECANT PILING.