

Regis Road - C&I NHS Trust Kentish Town

85472-01-CFM-A-XX-SH-0012 Schedule of Changes

06.05.2021

	CHANGE	LOCATION
1	New internal lining consisting of a layer of non combustible insulation and two layers of plasterboard to comply with Part L2B	All facades
2	New layer of insulation and external cladding will be installed on top of the existing roof to achieved the required U-value as per Part L2B	Roof
3	Roller shutter is to be removed. New windows and glass door will be installed to allow natural light to the workspace.	North façade
4	New plant equipment to the rear of the building	North façade
5	Existing grilles removed	North façade
6	Double doors replaced, single door opening relocated and new doorset to be installed.	South façade
7	New internal finishes to floors and walls	Interiors
8	Renovation of front external area to accommodate 2 car parking bays, an accessible parking bay, 5 new sheffield stands, a new bin enclosure that includes a separate commercial waste compartment and 2 separate clinical waste compartments, as well as 2 transformers.	Front external area
9	New Planting to the external front area	Front external area
10	New pavers matching existing ones	Front external area
11	New signagne to front elevation	South façade
12	Front doors replaced matching existing materials	South façade