Planting Schedule

Trees

Number	Species	Girth	Height	Specification
5 No.	Acer platanoides 'Emerald Queen'	20-25cm	4.5-5.5m	Semi-Mature :Clear Stem min. 200 :BR
1 No.	Tilia cordata 'Green Spire'	20-25cm	4.5-5.5m	Semi-Mature :Clear Stem min. 200 :BR
5 No.	Prunus avium 'Plena'	20-25cm	4.5-5.5m	Semi-Mature :Clear Stem min. 200 :BR
3 No.	Betula utilis jacquemontii	16-18cm	4.0-4.5m	Extra Heavy Standard :Clear Stem 175-200 :BR
5 No.	Acer rubrum	20-25cm	4.5-5.5m	Semi-Mature :Clear Stem min. 200 :BR
6 No.	Betula pendula Fastigiata 'Obelisk'	20-25cm	4.5-5.5m	Semi-Mature :Clear Stem min. 200 :BR
5 No.	Sorbus aucuparia	20-25cm	4.5-5.5m	Semi-Mature :Clear Stem min. 200 :BR
4 No.	Liquidambar styraciflua	20-25cm	4.5-5.5m	Semi-Mature :Clear Stem min. 200 :BR
1 No.	Sorbus aria 'Lutescens'	20-25cm	4.5-5.5m	Semi-Mature :Clear Stem min. 200 :BR
4 No.	Pyrus communis 'Louise Bonne of Jersey'	10-12cm	2.5-3.0m	Grafted onto dwarf rooting stock :Selected Standard :BR
4 No.	Amelanchier lamarckii	18-20cm	450-500cm	Extra Heavy Standard :Clear Stem 150-175 :BR
2 No.	Alnus glutinosa 'Imperialis'	20-25cm	4.5-5.5m	Semi-Mature :Clear Stem min. 200 :BR
1 No.	Acer saccharinum	20-25cm	4.5-5.5m	Semi-Mature :Clear Stem min. 200 :BR
3 No.	Pinus sylvestris	20-25cm	4.5-5.5m	Semi-Mature :Clear Stem min. 200 :BR
1 No.	Liriodendron tulipifera	20-25cm	4.5-5.5m	Semi-Mature :Clear Stem min. 200 :BR
3 No.	Prunus serrulata	20-25cm	4.5-5.5m	Semi-Mature :Clear Stem min. 200 :BR
3 No.	Malus 'Rudolph'	20-25cm	4.5-5.5m	Semi-Mature :Clear Stem min. 200 :BR

Shrubs

Number	Species	Pot (L)	Height	Specification	Density
220 No.	Carpinus betulus	5L	40-60cm	Branched :4/6 brks :Dense Bushy Growth :C	4/m²
894 No.	Cornus alba 'Aurea'	5L	40-60cm	Bushy :3/4 brks	5/m²
383 No.	Cornus stolonifera 'Flaviramea'	5L	60-80cm	Branched :5 brks :C	5/m²
301 No.	Crataegus monogyna	5L	40-60cm	Branched :4/6 brks :Dense Bushy Growth :C	4/m²
220 No.	Ilex aquifolium 'Alaska'	5L	40-60cm	Leader With Laterals :C	4/m²
60 No.	Lavandula angustifolia	5L	40-60cm	Bushy :5/7 brks :C	5/m²
220 No.	Rosa canina	5L	40-60cm	Branched :4/6 brks :Dense Bushy Growth :C	4/m²
53 No.	Rosmarinus officinalis	5L	40-60cm	Bushy :5/6 brks :C	5/m²
220 No.	Viburnum opulus	5L	40-60cm	Bushy :4/6 brks :C	4/m²

Herbaceous

Number	Species	Pot (L)	Specification	Density
481 No.	Euphorbia amygdaloides var. robbiae	3L	Full pot: fully rooted pot: healthy crown	5/m²
117 No.	Anemone hybrida 'Honorine Jobert'	2L	Full pot: fully rooted pot: healthy crown	6/m²
130 No.	Sedum 'Autumn Joy'	3L	Full pot: fully rooted pot: healthy crown	6/m²
136 No.	Rudbeckia fulgida sullivantii 'Goldsturm'	2L	Full pot: fully rooted pot: healthy crown	8/m²
504 No.	Alchemilla mollis	2L	Full pot: fully rooted pot: healthy crown	6/m²
436 No.	Anemone hybrida 'Whirlwind'	2L	Full pot: fully rooted pot: healthy crown	6/m²
563 No.	Hakonechloa macra 'Aureola'	2L	Full pot: fully rooted pot: healthy clump	6/m²
387 No.	Vinca minor 'Alba'	2L	Full pot: fully rooted pot: healthy crown	8/m²
160 No.	Anemone nemorosa	2L	Full pot: fully rooted pot: healthy crown	8/m²
140 No.	Geranium 'Phaeum'	2L	Full pot: fully rooted pot: healthy crown	6/m²
82 No.	Origanum vulgare	2L	Full pot: fully rooted pot: healthy crown	5/m²
159 No.	Alchemilla mollis	2L	Full pot: fully rooted pot: healthy crown	7/m²
105 No.	Perovskia 'Blue spire'	2L	Full pot: fully rooted pot: healthy crown	6/m²
46 No.	Verbena bonariensis	2L	Full pot: fully rooted pot: healthy crown	5/m²

Bulbs

Number	Species	Specification	Density
564 No.	Narcissus cultivar	Grade 7/8 :Planted in groups of 5-10 in between plants	30/m²
251 No.	Allium 'Globemaster'	Grade 7/8 :Planted in groups of 5-10 in between plants	15/m²
684 No.	Galanthus nivalis	Grade 5/6 :Planted in groups of 5-10 in between plants	35/m²

Ferns

Number	Species	Pot (L)	Specification	Density
388 No.	Polystichum aculeatum	2L	Full Pot :Healthy clump	6/m²
297 No.	Asplenium scolopendrium	2L	Full Pot :Healthy clump	6/m²
426 No.	Dryopteris filix-mas	2L	Full Pot :Healthy clump	6/m²
338 No.	Dryopteris affinis 'Cristata'	2L	Full Pot :Healthy clump	6/m²

Grasses

Number	Species	Pot (L)	Specification	Density
205 No.	Stipa tenuissima	3L	Full Pot :Healthy clump	6/m²
281 No.	Deschampsia caespitosa	3L	Full Pot :Healthy clump	6/m²
156 No.	Luzula sylvatica 'Marginata'	2L	Full Pot :Healthy clump	6/m²
82 No.	Stipa tenuissima	2L	Full Pot :Healthy clump	6/m²
73 No.	Miscanthus sinensis 'Kleine Fontane'	2L	Full Pot :Healthy clump	6/m²

Climbing Plants

Number	Species	Pot (L)	Specification	Density
20 No.	Parthenocissus henryana	3L	3/4 brks :Caned	4/m²
59 No.	Hedera helix 'Pedata'	3L	Branched :5 brks	4/m²
32 No.	Hydrangea petiolaris	5-7.5L	3/4 brks :Caned	4/m²
32 No.	Lonicera japonica 'Halliana'	3L	3/4 brks :Caned	4/m²

Lawn

Species	Specification	Area
Standard lawn	Rolawn Medallion® Turf (or equal and approved) :to BS3969	166.7m²

Meadow planting, Standard General Purpose Meadow Mixture
- EM2 by Emorsgate Seeds or equal

To contain the following species:

Wildflowers:
Achillea millefolium
Centaurea nigra
Daucus carota
Wild Carrot
Galium verum
Lady's Bedstraw
Knautia arvensis
Leontodon hispidus
Leucanthemum vulgare
Malva moschata
Plantago lanceolata
Poterium sanguisorba - (Sanguisorba minor)
Primula veris
Prunella vulgaris
Ranunculus acris
Rhinanthus minor
Rumex acetosa

Grasses:
Agrostis capillaris
Cynosurus cristatus
Festuca rubra
Phleum bertolonii
Poa pratensis

NOTE:

All trees to comply with the latest biosecurity standards.

LINKED MODEL SCHEDULE

1. Drawing to be read in conjunction with MPR-TMA-ZZ-GF-GA-L-100005, MPR-TMA-ZZ-GF-GA-L-100006 and MPR-TMA-ZZ-GF-GA-L-100007.

STATUS	REV	DATE	DESCRIPTION	DSG | DRW | CHK | APP
S3	P04	02/08/2021	Amendments to layout	AC | TS
S3	P03	24/04/2021	Amendments to specification	AC | TS
S3	P02	25/09/2020	Updated Planting Schedule	AC | TS
S3	P01	22/05/2020	Stage 4 Issue	AC | TS

ALL REVISIONS

MAIN CONTRACTOR

Bouygues UK
Becket House
1 Lambeth Palace Rd
Lambeth, London SE1 7EU
Tel: 020 7401 0020

CLIENT LOGO

Camden

KEY PLAN



ORIGINATOR MPR01

turkington martin
Studio 3.04 Chester House, Kennington Park
1-3 Brixton Road, London, SW9 6DE
T: (+44) 020 3567 1050
E: studio@turkingtonmartin.com

PROJECT NAME
Maitland Park Redevelopment

DRAWING TITLE
Planting Schedule

SCALE @ A1	MODEL FILE NAME - REVISION	
N/A	N/A	
FIRST ISSUE DATE	PROJECT STAGE	STATUS CODE
22/05/2020	Stage 4	S3 - Suitable for Review and Comment

PROJECT	ORIGINATOR	VOLUME	LEVEL	TYPE	ROLE	NUMBER	REV
MPR	TMA	ZZ	GF	SH	L	100008	P04