



Please refer to the specification for information on materials specified and workmanship.

All lead details and codes used are to be in accordance with those shown in the USA Handbook 2016 edition.

Backwork to the parapets is to be examined and if required, replaced by new parapet concrete. The concrete to be removed or cast against must be sound and free from reinforcement corrosion. If detached from the substrate it is to be hacked off and then replaced with lime render - see spec for details of the mix.

Zones panel 1 is to be removed and then all painted using Keim Solignum.

Clink emulsion g/yed green to be applied to the underside of the lead prior to installation. This will help prevent corrosion of the underside of the lead.

See:-
<https://historicengland.org.uk/whats-new/research/back-issues/lead-roots-and-statuary-understanding-monitoring-and-conservation>

P03	6-8-21	RET	Further notes added Walkway size reduced . Planning issue	HW
P02	4-5-21	RET	Roof void ventilation added	HW
P01	15-3-21	RET	Tender Issue	HW
	rev date	by	description	chgd



Nottingham	13 St Peter's Gate, Nottingham NG1 2JF	0115 558 5500
London	31 / 35 Kirby Street, London EC1N 8TE	0207 492 1805
Birmingham	The Lewis Building, Bull Street, Birmingham B4 6EQ	0121 481 2082
www.apmg-architects.com		enquiries@apmg-architects.com

Dr Williams's Library

drawing title

Roof section central bay

B-B

PLANNING SUBMISSION

drawn by	date	chk'd by	scale
RET	03-02-21	HW	1:20
job no.	drawing no.	revision	media
8655	W82-CPM-ZZ-DR-A-250	02_P03	A1

Copyright of CPMG Architects Limited 2021.

All rights reserved. No part of this publication may be reproduced, stored in any retrieval system or transmitted in any form or by any means without prior permission of CPMG Architects Limited.

All dimensions to be checked on site.

ISO 9001: 2015 Quality Management
ISO 14001: 2015 Environmental Management
PAS 1192-2: 2013 Building Information Modelling