



DIMMING SCHEDULE

PROJECT NAME		30 Percy Street				BOARD REFERENCE		LG	
PROJECT NO		-				NUMBER OF WAYS		-	
ENGINEER NAME		CM				BOARD LOCATION		Cupboard - LG	
DATE		25/05/2021				SUPPLY CABLE		Refer to DB Schedules	
	NO	WAY DESCRIPTON	DIMMING TYPE	MCB	CABLE	DIMMING GROUP		CONTROLLER LOCATION	
	1	Basement Office Track	DALI	6A	1.5mm² LSF T&E			In Room	
	2	Basement Office Track	DALI	6A	1.5mm² LSF T&E			In Room	
	3	Basement Office Track	DALI	6A	1.5mm² LSF T&E			In Room	
	4	Basement WC	DALI	6A	1.5mm² LSF T&E			In Room	
	5	Basement Corridor	DALI	6A	1.5mm² LSF T&E			In Room	
	6	Basement Corridor	DALI	6A	1.5mm² LSF T&E			In Room	
	7	Basement WC	DALI	6A	1.5mm² LSF T&E			In Room	
	8	Basement WC	DALI	6A	1.5mm² LSF T&E			In Room	
	9	Basement WC	DALI	6A	1.5mm² LSF T&E			In Room	
	10	Basement WC	DALI	6A	1.5mm² LSF T&E			In Room	
	11	Basement WC	DALI	6A	1.5mm² LSF T&E			In Room	
	12	Basement WC	DALI	6A	1.5mm² LSF T&E			In Room	
	13	Basement WC	DALI	6A	1.5mm² LSF T&E			In Room	
	14	Basement Office Track	DALI	6A	1.5mm² LSF T&E			In Room	
	15	Basement Office Track	DALI	6A	1.5mm² LSF T&E			In Room	
	16	Basement Office Track	DALI	6A	1.5mm² LSF T&E			In Room	
	17	Basement Office Track	DALI	6A	1.5mm² LSF T&E			In Room	
	18	Basement Office Track	DALI	6A	1.5mm² LSF T&E			In Room	

<div><div>TPS</div><div>TAYLOR PROJECT SERVICES LLP</div><div>BUILDING SERVICES CONSULTANTS</div></div>		DIMMING SCHEDULE					
PROJECT NAME		30 Percy Street			BOARD REFERENCE		G
PROJECT NO		-			NUMBER OF WAYS		-
ENGINEER NAME		CM			BOARD LOCATION		Cupboard - LG
DATE		03/09/2021			SUPPLY CABLE		Refer to DB Schedules
	NO	WAY DESCRIPTON	DIMMING TYPE	MCB	CABLE	DIMMING GROUP	CONTROLLER LOCATION
	1	Kitchen Track (Double Spotlights)	DALI	6A	1mm² LSF T&E		In Room
	2	Kitchen Track (Double Spotlights)	DALI	6A	1mm² LSF T&E		In Room
	3	Kitchen Track (Double Spotlights)	DALI	6A	1mm² LSF T&E		In Room
	4	Kitchen Track (Double Spotlights)	DALI	6A	1mm² LSF T&E		In Room
	5	Kitchen Track (Double Spotlights)	DALI	6A	1mm² LSF T&E		In Room
	6	Kitchen Track (Double Spotlights)	DALI	6A	1mm² LSF T&E		In Room
	7	Spotlights - Kitchen	DALI	6A	1.5mm² LSF T&E		In Room
	8	Spotlights - Kitchen	DALI	6A	1.5mm² LSF T&E		In Room
	9	Pendants - Kitchen and spotlights	Switched / DALI	6A	1.5mm² LSF T&E		In Room
	10	Spotlights - Kitchen	DALI	6A	1.5mm² LSF T&E		In Room
	11	Reception - Lighting 1	DALI	6A	1.5mm² LSF T&E		In Room
	12						
	13	Library - 5A and wall lights	DALI	6A	1.5mm² LSF T&E		In Room
	14	Reception - Lighting 3	DALI	6A	1.5mm² LSF T&E		In Room
	15	Boardroom - Wall lights	DALI	6A	1.5mm² LSF T&E		In Room
	16	Boardroom - 5A	DALI	6A	1.5mm² LSF T&E		In Room
	17	Boardroom - Wall lights	DALI	6A	1.5mm² LSF T&E		In Room
	18	Kitchen - 5A	Switched	6A	1.5mm² LSF T&E		In Room
	19	Boardroom - Picture Light	Switched	6A	1.5mm² LSF T&E		In Room



DIMMING SCHEDULE

PROJECT NAME		30 Percy Street				BOARD REFERENCE		1	
PROJECT NO		-				NUMBER OF WAYS		-	
ENGINEER NAME		CM				BOARD LOCATION		Cupboard - 1	
DATE		25/05/2021				SUPPLY CABLE		Refer to DB Schedules	
	NO	WAY DESCRIPTON	DIMMING TYPE	MCB	CABLE	DIMMING GROUP		CONTROLLER LOCATION	
	1	Office - Rear	Switched	6A	1.5mm² LSF T&E			In Room	
	2	Office - Front	Switched	6A	1.5mm² LSF T&E			In Room	
	3	Office - Front	DALI	6A	1.5mm² LSF T&E			In Room	
	4	Office - Wall Lights	DALI	6A	1.5mm² LSF T&E			In Room	
	5	Office - Wall Lights	DALI	6A	1.5mm² LSF T&E			In Room	
	6	Office - Rear	DALI	6A	1.5mm² LSF T&E			In Room	
	7	Office - Front	DALI	6A	1.5mm² LSF T&E			In Room	
	8	Stair - Wall Lights	DALI	6A	1.5mm² LSF T&E			In Room	
	9	Rear Courtyard - External	DALI	6A	1.5mm² LSF T&E			In Room	
	10	Rear Courtyard - External	DALI	6A	1.5mm² LSF T&E			In Room	
	11	Rear Courtyard - External	DALI	6A	1.5mm² LSF T&E			In Room	
	12	Rear Courtyard - External	DALI	6A	1.5mm² LSF T&E			In Room	
	13	Rear Office	DALI	6A	1.5mm² LSF T&E			In Room	
	14	Rear Office	DALI	6A	1.5mm² LSF T&E			In Room	
	15	Front office	DALI	6A	1.5mm² LSF T&E			In Room	
	16	Front office	DALI	6A	1.5mm² LSF T&E			In Room	
	17	WC	DALI	6A	1.5mm² LSF T&E			In Room	
	18	Front Office	DALI	6A	1.5mm² LSF T&E			In Room	
	19	Front Office	DALI	6A	1.5mm² LSF T&E			In Room	
	20	5A switched	DALI	6A	1.5mm² LSF T&E			In Room	
	21	5A switched	DALI	6A	1.5mm² LSF T&E			In Room	



DIMMING SCHEDULE

PROJECT NAME		30 Percy Street				BOARD REFERENCE		2	
PROJECT NO		-				NUMBER OF WAYS		-	
ENGINEER NAME		CM				BOARD LOCATION		Cupboard - 2	
DATE		25/05/2021				SUPPLY CABLE		Refer to DB Schedules	
	NO	WAY DESCRIPTON	DIMMING TYPE	MCB	CABLE	DIMMING GROUP		CONTROLLER LOCATION	
	1	Third - WC	DALI	6A	1.5mm² LSF T&E			In Room	
	2	Third - Lobby	DALI	6A	1.5mm² LSF T&E			In Room	
	3	Third - Lobby to Roof	DALI	6A	1.5mm² LSF T&E			In Room	
	4	Third - Staircore LED	DALI	6A	1.5mm² LSF T&E			In Room	
	5	Third - Office 1	DALI	6A	1.5mm² LSF T&E			In Room	
	6	Third - Office 2	DALI	6A	1.5mm² LSF T&E			In Room	
	7	Third - Brainstorming Room	DALI	6A	1.5mm² LSF T&E			In Room	
	8	Third - Brainstorming Room	DALI	6A	1.5mm² LSF T&E			In Room	
	9	Third - meeting Room	DALI	6A	1.5mm² LSF T&E			In Room	
	10	Third - meeting Room	DALI	6A	1.5mm² LSF T&E			In Room	
	11								
	12								
	13	Roof	DALI	6A	1.5mm² LSF T&E			In Room	
	14	Roof	DALI	6A	1.5mm² LSF T&E			In Room	