30 Percy Street Extract Fan Schedule Revision A

| Ref No. | Duty (I/s) | Static Pressure (Pa) | Breakout Sound (dBA) | Model | Inlet Attenuator | Outlet Attenuator | Control | Area Served | Notes |
|---------|------------|-------------------------|-------------------------|------------------|------------------|-------------------|----------------|-----------------------------|----------------------------------------------------|
| EF/1 | 50 | 150 | 24dBA @ 3m | Vent Axia ACM125 | N/A | N/A | PIR Activation | 2nd & 3rd Floor WC / Shower | Continuous Trickle to Boost upon PIR Activation |
| EF/2 | 60 | 100 | 32dBA @ 3m | Vent Axia ACM125 | N/A | N/A | Manual Control | Kitchen Extract | - |
| EF/3 | 30 | 25 | 16dBA @ 3m | Vent Axia ACM100 | N/A | N/A | Manual Control | Server Room | Linked to thermostat in cupboard |

Notes

- 1. Fans to be supplied with vibration isolation mounts.
- 2. Roof Fans to terminate to tile vent grille.