

NOTES:

1. If in doubt please ask.

2. Do not scale this drawing

3. This drawing is to be read in conjunction with all Engineer's, Architect's or other relevant drawings and specifications. Any discrepancy is to be reported to the engineer immediately

4. The contractor must ensure and will be held responsible for the overall stability of the building/structure/ /excavation at all stages of the work

All existing details shown are based on limited opening up. Assumptions have been made regarding existing construction.
Framing and spans of existing slab joist and walls to be confirmed on site.

6. To be Read with General Notes GN-001

RJ

 \bigcirc

DENOTES:

Demolition, refer to architects plans

New timber walls

New Timber Roof/Floor Joists

New Steel beam

New Columns

Column Under

Foundation

Read in conjunction with GN-001 and all other architects and engineers information

STEEL COLUMN SCHEDULE: ALL S355

C1: 80x80x8 SHS

Refer to GN-001 for general notes

galvanised fixed to floor with 5 No. 5.5 dia wood screws via solid noggings and built-in wall with min. 150 return

STEEL BEAM SCHEDULE: ALL S355

GB1: 203x133x25 UB GB2: 203x133x25 UB

Allow for 10thk S275 plate to support wall over.

 (A) Use minimum 4M16 8.8 bolts and 6mm fillet welds to any steelwork connection subject to design. UNO

 (M) Rigid Connection

 -All beam to beam connections to be end plate connected, Min. 10mm MS plate. Refer to plans and schedule for mass concrete padstones locations and sizes. Alternative to concrete padstones use steel plate. Consult

engineer for plate thickness.

Refer to notes drawing GN-001 for further specification.

Screw piles to be used to mitigate impact of foundations on existing root structures.

/					
R/R	00	E S	СНЕ	ווס	ILE.

- FJ1 (Floor Joists): 50x150 C24 at 400 c/c

TB1 (Timber Beam): 2 No. 75x200 C24

- RJ1 (Roof Joists): 50x150 C24 at 400 c/c

- TW1 (Timber Stud Wall): 50x100 C24 Studs at 400mm crs, with 50x100 sole & header plates & 50x100 horizontal noggins at 600mm crs (all C24 grade timber). 12mm thk. plywood sheathing screwed to each face.

Min. 12mm thk ply decking to roofs (no access)

(SWL 5.9kN) to beam webs via timber plate bolted to steel

Refer to specification and GN-001 for further notes

PRELIMINARY							
Rev	Date	Amendments	By	Chk'd			
P1	27.07.2021	Issued for Information	RN	AB			
P2	12.08.2021	Issued for Information	RN	AB			

AXIOM

STRUCTURES

+44 (0)20 3637 2751 office@axiom-structures.co.uk

19 Provost Road, NW3 4ST London

GARDEN ROOM - GROUND FLOOR PLAN

Date: 07/2021	Scale at A2: 1:50	Scale at A4: 1:100				
Drawn by: RN	Designed by: RN	Chk'd by: AB				
Drawing No:	Revision:					
21080-AS	P2					

LRS

Lateral Restrain Straps 30x5x 150+1050 long L-strap