


Stack height to be a minimum of 1m above roof eaves, to ensure adequate dilution of odours to take place before the plume interacts with a receptor.


Extractor to have a minimum discharge velocity of at least 8m/s

The final discharge point needs to be vertically upwards and unhindered. The discharge point is directed to the rear.

All kitchen extract ducting must be fitted with access panels/hatches at approximately 3 metre intervals to enable cleaning and maintenance and must also comply with the safe access standards.



Roof Plan  
as Existing



Roof Plan  
as Proposed

**PPLX**  
Architects

58 Pine Grove  
Brookmans Park  
Herts  
AL9 7BW

t: 07886 526 081  
f: 01707 642 026  
e: papalexandrakos@hotmail.com


Site:  
181 York Way  
London  
N7 9LN

Client:  
Greek Coffee Ltd

Title:  
Roof Plans  
as Existing and Proposed

Drawn: NP | Drg. No. 307\_02

Date: Sept. 2021 | Rev. #



Scale: 1:100 | Drg. Size: A3

Key:

Existing Walls/Floors   
Boundary

Rev.	Date	Note

Rev.	Date	Note