



REV	DATE	DESCRIPTION
P06	2021-11-02	Drawing updated following conversations with Conservation Officer.
P05	2021-08-27	Drawing issued for Planning
P04	2020-03-09	Drawing updated for Planning, scheme adaptation submission.
P03	2019-11-08	Planning Issue
P02	2019-10-28	Drawings issued for Planning
P01	2019-08-30	Elevation updated in line with latest plan changes.

ORIGINATOR REF: 8555



CPMG Architects Ltd

Nottingham 13 St. Peters Gate, Nottingham, NG1 2JF tel: 0115 958 9500
 London 31/35 Kirby Street, London, EC1N 8TE tel: 0207 492 1805
 Birmingham The Lewis Building 35 Bull Street Birmingham B4 6EQ tel: 0121 481 2092

enquiries@cpmg-architects.com www.cpmg-architects.com

PROJECT

**Dr Williams's Library
Library Building**

DRAWING TITLE

**ELEVATIONS
Proposed GA Elevation - Rear**

DRAWING PURPOSE

PLANNING

DRAWN BY	DATE	CHK'D BY	SCALE	MEDIA
HW	2019-07-12	AP	As indicated	A2
PROJECT - ORIGINATOR - ZONE - LEVEL - TYPE - ROLE - NUMBER				REVISION

W82-CPM-Z1-ZZ-DR-A-20402 P06

Copyright of CPMG Architects Limited 2019. All rights reserved. No part of this publication may be reproduced, stored in any retrieval system or transmitted in any form or by any means without prior permission of CPMG Architects Limited. Do not scale from drawing for Construction or Setting-out purposes, use figured dimensions only. All dimensions to be checked on site.
 ISO 9001: 2015 Quality Management
 ISO 14001: 2015 Environmental Management
 PAS 1192-2: 2013 Building Information Modelling

Proposed GA Elevation - Rear

1 : 100

- | | | | | | |
|--|--|---|---|--|---|
| 01 Rebuilt York stone stair, refer to Structural Engineer's design. | 02 Existing entrance ramp steelwork to be cleaned and painted, drip detail to be allowed for. | 03 Chimney stack to be rebuilt / stabilised depending on structural integrity. | 04 Existing Cast Iron RWP to be retained, and made good. | 05 Half landing windows infilled with reclaimed bricks with 15mm recess and lead drip cill. | 06 Previously Approved Works-Roof finish replaced with new Welsh slate roof tiles. |
| 07 New timber security door, black finish | 08 New cast Iron rainwater pipe, hopper and overflow. PPC black. | 09 New aluminium weir/chute overflow. PPC black. | 10 Slimline access rooflight, frame PPC graphite grey. | 11 New cast iron soil stack, PPC black. | 12 Boarded windows reinstated. |

Drawing based on survey information, Revit model and CAD drawings produced by City Survey's and Survey Hub, refer to below files. CPMG cannot be held responsible for any discrepancies within the original Revit survey or CAD drawings.
 - 10410E_R (City Surveys)
 - CSDr 000765-DWL-SU-DRG-0001-A01.rvt (City Surveys)
 - 3916_Dr Williams Library_3D Model (Survey Hub)