

Tree works schedule

Cumberland Terrace

| Cumberiand remade | | | Priority | Date |
|-------------------|--|---|--------------------|-----------|
| ID | No. / Species | Works | Safety action date | completed |
| T261 | 1 x Salix babylonica Weeping Willow | End-weight reduction - Specified extent. Lateral branch reduction of 1.5-2 m from all aspects (3-4 m total crown diameter) to alleviate mechanical loading of heavy branch weight, specifically cracked lateral limb ("hazard beam"), while ensuring a balanced crown is retained. Height to be reduced where necessary to ensure good form, no greater than 1 m. | not set | |