

© This drawing remains the property of The Keen Partnership and shall not be copied without prior written consent. All dimensions to be checked on site and any discrepancies to be reported before work commences.

Rising Main **Escape Window** 30 Min fire door with intumescent strip. Door frame to be soft wood or fire proofed MDF Indicative boiler location CavityTray/lintel over and DPM behind Water \ Telecommunications————

Stub Stack fitted with OSMA Non return valve

Surface Water — · — · — — — Wall mounted Gas/ Electric meter box.

Heat Detector Smoke Detector Mechanical Vent Soil Vent Pipe

Tile vent Rain Water Pipe

Line of Input to HR Unit Line of Extract from HR Unit Foul Drainage - · — · — · — —

Air Brick

Heat Recovery Unit

Termination/Cutout Position

Consumer Unit

temporary Services Location

G.F. Outline socket of Support

system

E-WM-1

Shaver socket and light TP Telephone port Wall mounted light

Ramp Power Supply LS Light switch LSS Light sensor switch MSFS Multi switch fuse spur Cupboard Light AC Airconditioner unit EC Electric curten

Dense aggregate blocks ■ Wet plaster ■ Block density 1850 to 2300 kg/m³ "Tie type A" (see Appendix A) Block thickness 100mm (min), each leaf sand render with plaster skim (min 10 kg/m²), both Masonry (both leaves) with flanking) wall 50mm (min) cavity - clear, fully filled or partially filled

As Robust Detail E-WM-1. Ensure construction fully complies with all Robust

Robust Detail (RD) is an alternative to Pre-Completion Testing. If you are following the RD route, you must register each plot, with details of the details you intend to use, and pay a fee. You will then be given a registration certificate to hand to your building control authority before work starts.

As with any Robust Detail the correct external wall, separating wall internal wall and ceiling detail must be adhered to. The Robust Detail handbook should be consulted to ensure that the separating wall is compatible with the separating floor and vice versa. The Robust Detail checklist should be used to ensure that details are adhered to throughout each sequence of the build. If not using Robust Details Pre completion sound testing to be carried out by a suitably qualified person with appropriate third party accreditation. It is the Designer's responsibility to ensure all elements of construction are compliant with the standards given in

Separating wall to consist of 2 leaves of dense aggregate blocks (1850 to 2300 kg/m3) with a minimum 75mm cavity. Finish with 13mm plaster or cement: sand render with plaster skim (min 10 kg/m2) to both sides.

Ensure cavity stops are installed where required, and joints, voids around floor joists, chases, etc. have been fully filled or sealed. Where there is a separating floor a resilient flanking strip to be installed

Wall to be tied using Approved Document E Tie Type A - Butterfly ties as described in BS 1243: 1978 Metal ties for cavity wall construction, and spaced as required for structural purposes (BS 5628-3: 2001 Code of practice for use of

N PROGRESS

0 .5 1 1.5 2 2.5m

THE **KEEN PARTNERSHIP** The Courtyard Edinburgh Road Reading RG30 2UA Tel: 0118 9510 855 Fax: 0118 9510 866

RICS chris@keenpartnership.co.uk www.keenpartnership.co.uk

Goldfield Homes

Four-storey building of flats 3 Malden Rd London NW5 3HT

chartered association of building engineers

Drawing Title:

Proposed First Floor Rev E Drawing Date: 18-04-18

Building Regulations Drawn By: ||Scale: 1:50, 1:75, ssue Date: CP/DR 29/11/2021 1:100@A1 Drawing No:

BR-05

8746-17