



PROJECT 18&19 Southampton Place Holborn Links	DESCRIPTION Demolition Second Floor Plan	Sept '21 STATUS PLANNING
CLIENT		DRAWN
EDR		EM

DEMOLITION NOTES:

All asbestos to be removed as part of the enabling works package. Refer
to asbestos report for details of locations. New R&D survey to be
undertaken to confirm no remaining asbestos is present following
enabling package.

Existing external doors and frames carefully repaired and openings made good ready to receive new decoration.

Existing sanitary ware carefully removed and abutments / substrates made good ready to receive new finishes and equipment.

Existing tiled wall finish carefully removed and substrate made good ready to receive new finish.

Existing walls to be carefully removed and new lintels installed in accordance with structural engineers information. Provide temporary support as required.

Existing damaged suspended ceiling to be carefully removed and replaced

- — — Dotted line denote elements to be removed

Hatch denotes ceiling elements to be removed

Existing kitchens and associated services carefully removed with abutments and substrates capped off. Refer to MEP drawings for extents and locations of stripped out services.

3. Existing modern construction internal doors to be removed

7. Door/window to be replaced with AOV 8. Existing floor finishes carefully removed.

10. Existing WC cubicles carefully removed. 11. Existing cleaners cupboard to be retained



