



B-GF-CW04							
Mark	Height	Width	Manufacturer	U Value	Frame Finish	AcousticRating	Description
CW04	2400	2710	TBC	1.6	RAI 090 80 10	Glazing 41 dB Rw overall and an R125Hz value of 25 dB (sound reduction at a frequency of 125 Hz)	PAS24

- PART M1 Requirements**
- All entrance doors should have 1m clear width as per Part M1.



B-GF-CW05							
Mark	Height	Width	Manufacturer	U Value	Frame Finish	AcousticRating	Description
CW05	2625	2290	TBC	1.6	RAI 090 80 10	Glazing 41 dB Rw overall and an R125Hz value of 25 dB (sound reduction at a frequency of 125 Hz)	PAS24

B-GF-CW06							
Mark	Height	Width	Manufacturer	U Value	Frame Finish	AcousticRating	Description
CW06	2625	1440	TBC	1.6	RAI 090 80 10	Glazing 41 dB Rw overall and an R125Hz value of 25 dB (sound reduction at a frequency of 125 Hz)	PAS24



Key Plan

Revision	Date	Revised by	Description
C05	30/11/21	CR	Construction Issue - full set for Completeness
C04	09/08/21	CR	Curian Walling Co-ordination with Supplier
C03	16/08/21	CR	Curian Walling Revisions
C02	05/08/21	CR	Windows Construction Issue
C01	16/06/21	CR	Revised as per RCKa Comments
P2	04/08/21	CR	First Issue
P1	21/05/21	CR	First Issue

Revision History

hunters
Space One Beadon Road
London W8 0EA
T 020 8237 8200
mail@hunters.co.uk
www.hunters.co.uk

FARRANS
Camden
Doran CONSULTING
Camlins
semple mckillop
Harvey

HNCC

25 Bertram Street,
Highgate,
London,
N19 5DQ

BLOCK B - CURTAIN WALL TYPES

Sheet 2 of 2

Status: **S4 - CONSTRUCTION**

hunters project number: M9920	client project number: HNCC	scale: 1:20 @ A1	drawn by: CR	checked by: PG
----------------------------------	--------------------------------	---------------------	-----------------	-------------------

drawing title:
HNCC HUN-04-ZZ-DR-A-52-40002

revision: C05	date: 30/11/21	revised by: CR
-------------------------	-------------------	-------------------

Construction Issue - full set for Completeness



All drawings are to be printed in colour.

model ref: C:\Revit Local\HNCC\HUN-29-ZZ-05-A-XX-0001_r_0001\ALW13X.rvt

Use figured dimensions only. All levels and dimensions to be checked on site. This drawing is to be read in conjunction with all other relevant drawings and specifications. Hunters is a trading name of Hunter & Partners Limited. © Hunter & Partners Limited. All rights reserved.