

Tree Work Specifications
For
The Vicarage, 52 Courthope Road,
London,
NW3 2LD

Front of Property

- | | | |
|--------------|---|--|
| T1: Lime | - | Crown reduce to previous pollard points
Remove all epicormic / basal / trunk growth |
| T2: Lime | - | Crown reduce to previous pollard points
Remove all epicormic / basal / trunk growth |
| T3: Lime | - | Crown reduce to previous pollard points
Remove all epicormic / basal / trunk growth |
| T4: Lime | - | Crown reduce to previous pollard points
Remove all epicormic / basal / trunk growth |
| T5: Lime | - | Crown reduce to previous pollard points
Remove all epicormic / basal / trunk growth |
| T6: Laburnum | - | Prune to give 1.0m clearance from property |

Side of Property

- | | | |
|-------------|---|---|
| T7-T9: Lime | - | Crown reduce to previous pollard points
Remove all epicormic / basal / trunk growth to 5m height |
| T10: Cherry | - | Crown reduce height and spread 25% (2.5m branch lengths)
Crown thin 15% |

Rear of Property

- | | | |
|---------------|---|---|
| T11: Sycamore | - | Crown reduce height and spread 25% (3.0m branch lengths)
Crown thin 15%
Remove all deadwood |
| T13: Ash | - | Crown reduce height and spread 25% (2.5m branch lengths)
Crown thin 15%
Remove all deadwood |
| T15: Ash | - | Crown reduce height and spread 25% (2.5m branch lengths)
Crown thin 15%
Remove all deadwood |