

Tree Work Specifications
For
10, Templewood Avenue,
London,
NW3 7XA

Rear garden - Trees and shrubs were viewed in an anti-clockwise direction starting with the 2 Limes trees (T1&T2) by the right side gate

- T1 & T2: Limes - Crown reduce back to the most recent reduction points leaving small furnishing growth where possible
Remove the trunk growth to a height of 6m
- T6: Lime - Crown reduce the height by 3m
Reduce the crown spread to balance and shape
- T7: Sycamore - This tree has a heavy lean to the west and over the neighbouring garden
Thin throughout the crown by 20%
Remove 2-3 low branches to elevate some of the weight
- T8: Small Sycamore - Crown reduce the height and spread back to the previous reduction points leaving small furnishing growth where possible
- T9: Large Sycamore - Crown reduce the height and spread back to the previous reduction points leaving small furnishing growth where possible
- T10 & T11: Small Sycamores
Crown reduce the height and spread back to the previous reduction points leaving small furnishing growth where possible
- T12: Large Sycamore - This tree forks at 2.2-2.4m from ground level thereafter forming two main stems
Crown reduce the height and spread back to the previous reduction points leaving small furnishing growth where possible
Replace the bracing
- T15: Sycamore - Thin throughout the crown by 15%
- T16: Birch - Thin throughout the crown by 20%
- T17: Willow - Crown reduce the height and spread back to the previous pollard points
Supply and install 2 new props