



Walls:

- 53 mm Gyproc ThermoLine PIR board with integral vapour control layer
- Rockwool insulation within treated timber studframework, studwork restrained to existing walls using ss angle fixings plug/screw fixed into brickwork joints
- 50mm ventilated space
- existing brickwork walls

Floor:

- floor finish (carpet / vinyl / lioleum)
- 18mm WBP plywood floor
- VCL membrane
- 75 mm PIR insulation within treated timber joists @400 mm centers supported on adjustable height plastic cradled supports (Mesa support or equal)
- 100 x 50 C24 treated sw joists
- 50mm ventilated space
- existing floor (various finish)

- D 09/03/2022 Existing UPVC windows replaced with painted hardwood similar appearance sets
- C 19/01/2022 Amendments following comments from Conservation Officer - Glazed canopy to lightwell omitted
- B 10/12/2021 Lighting schematic plan added

<div><div><div>RYAN BUNCE & CO</div><div>Chartered Building Surveyors Project Managers Land Agents</div></div><div><div>LONDON</div><div>181 Union Street, Southwark , SE1 0LN</div></div><div><div>HAMPSHIRE</div><div>Rose Cottage, The Bury Odiham, RG29 1NB</div></div><div><div>T 01256 701176</div><div>www.ryanbunce.co.uk</div><div>email: info@ryanbunce.co.uk</div></div></div>	PROJECT Rosslyn Hill Chapel 3 Pilgrim's Pl, London NW3 1NG		CLIENT Rosslyn Hill Chapel	
	DRAWING TITLE CRYPT PLAN AS PROPOSED		DATE 05/10/2021	SCALE 1:50
	File name: Rosslyn Hill Chapel Crypt REV A v2022.vwx		Printed on: 05/10/2021	DRAWN BY REV D