

CS1.01
Chimney Piece Schedule
1 Crestfield Street

File Name					
CS101-SH-6002-4T-0-ChimneypieceSchedule					
Date	Prepared by	Approved by	Status Code	Version Number	Purpose of issue
28.01.2022	HZC	JXT	4T	0	For RIBA Stage 4 Costing

Contact information

Jessica Lydiate

jessica.lydiate@insall-architects.co.uk

Tel: 020 7245 9888




London Office

Donald Insall Associates

12 Devonshire St, London W1G 7AB

www.insall-architects.co.uk

This report and all intellectual property rights in it and arising from it are the property of or are under licence to Donald Insall Associates or the RDA. Neither the whole nor any part of this report, nor any drawing, plan, other document or any information contained within it may be reproduced in any form without the prior written consent of Donald Insall Associates or the RDA as appropriate. All material in which the intellectual property rights have been licensed to Donald Insall Associates or the RDA and such rights belong to third parties may not be published or reproduced at all in any form, and any request for consent to the use of such material for publication or reproduction should be made directly to the owner of the intellectual property rights therein.

Job:	1 Crestfield Street						28.01.2022
					Rev - 0		
GENERAL NOTE:	1. To be read in conjunction with Specification Sections Z10 Purpose made Joinery; Drawings - GA Proposed Plans and Sections - Dwgs 2000, 2001, 2002, 2003, 2100, 2101.						
	2. To be read in conjunction with Finishes schedule 6003 for redecoration						
	3. Notify Architect in writing of any discrepancies or omissions. All existing windows to be retained unless otherwise noted, and all to be checked and overhauled so that they operate properly.						
Room.	DESCRIPTION						
	Chimney no.	Existing	Defect	Proposed Works	Image	Supplier	Additional Notes:
Basement							
Kitchen		n/a	n/a	New self-supported timber studwork chimney surround to level of kitchen units. Allow for redecoration as per Finishes schedule 6003		Contractor	Refer to Insall drawing 3008 and Kitchen Designers, Herringbone, drawings
Sitting Room	CH01	n/a	n/a	New timber studwork, floor to ceiling, chimney surround. Allow for redecoration as per Finishes schedule 6003		Contractor	Refer to Insall drawing 3009
Ground Floor							
Drawing Room	CH02		n/a	Allow for redecoration as per Finishes schedule 6003		n/a	
Drawing Room	CH03	n/a	n/a	New oak fire surround Supplier: Victorian Fireplaces Model: The Derry Wooden Mantel; Oak; waxed Code: SMC119 Allow for redecoration as per Finishes schedule 6003		Contractor	Or similar
				New Insert Supplier: Victorian Fireplaces Model: Celtic Arch; Cast Iron; Black Code: RX204		Contractor	Or similar
First Floor							
Bedroom 1	CH04		n/a	Allow for redecoration as per Finishes schedule 6003		n/a	