



Freemasons' Hall, 60 Great Queen Street, London

Schedule of work to ground floor kitchen and dumb waiter lift shaft

- Remove and strip out existing kitchen.
- Remove partition, dumb waiter, lift shaft and any accessories.
- Shutter the floor to complete floor slab on ground floor.
- Block up existing doorway.
- Install new lintel to form new doorway.
- Install timber partitioning to square of room ready for ne WC installation.
- Adapt existing supply and waste to pick up sink and toilets.
- Install new copper supply and waste pipes to serve new toilet and sink.
- Install surface finishes, including of vinyl flooring and tiling.
- Install mechanical extract – this may involve locating and making access to the closest location externally, may be a bit of builder's work involved with this.
- Adapting electrical supplies to automate doors leading into the lobby and installing new lighting.
- Install Doc M pack.
- Finish and completion.