

189 HIGH STREET CAMDEN REMEDIATION STRATEGY
2021/3329/P

WINDOWS

Remove temporary timber over cladding panels;

Remove whole window above as transom bars are out of line with the adjacent unaltered original window elevations

Provide a complete new timber window to match the existing framing, transom, mullion, sill and head detailing as the original windows; transom bars to line through; re-glaze with clear glass

STONE WORK

Trim edges of where the original stone has been removed ready for a neat infill with matching stonework (sample stone to be sources to match the existing stone type and colour)

Rebuild the moulded mid panel stall riser, again to match the profile, shape and mouldings of the original stonework; seal butt joints;

Clean off adjacent areas to leave the stone infills blended into the general building appearance;

Clean off and replace any cast iron metal grilles in the stall risers (some are missing in the façade)