NOTE: ALL EXISTING ARCHITECTURAL FACING BRICKWORK, STONEWORK AND WINDOWS ARE TO BE RETAINED, CLEANED AND MADE GOOD.

EXISTING GRILLE REPLACED WITH GREASE COLLECTION HATCH TO FILL EXISTING OPENING IN STONE. (SEE IMAGE ABOVE FOR REFERENCE) COLOUR TO MATCH EXISTING GRILLE

RAL 7024

EXISTING DOOR TO BE RETAINED, MADE GOOD AND PAINTED IN MUTED COLOUR. SUGGESTED FINISH RAL: 7024

TRIM EDGES OF WHERE ORGINAL STONE HAS BEEN OMITTED FOR PREVIOUSLY INSTALLED ATM'S

PREPARE FOR NEW NEAT INFILL WITH MATCHING STON WORK(SAMPLE STONE TO MATCH THE EXISTING STONE TYPE AND COLOUR.

REBUILD MOULDED MID PANEL STALL RISER TO MATCH EXISTING PROFILE, SHAPE AND MOULDINGS OF ORIGINAL STONEWORK. SEAL BUTT JOINTS CLEAN OFF ADJACENT AREAS TO LEAVE THE STONE INFILLS BLENDED INTO THE GENERAL BUILDING APPEARANCE.

CLEAN OFF AND REPLACE CAST IRON METAL GRILLS IN STALL RISERS FOR LIKE FOT LIKE REPLACEMENT

1 HIGH STREET ELEVATION - PROPOSED

SCALE: 1 : 50

0m 1m 2m 3m 4m 5m

SCALE 1:50 (METERS) @ A1

notes:
Do not scale from drawings. All discrepancies to be reported to Gensler architect immediately.
All dimensions to be verified by contractor on site prior to any works

rev	date	revision note	drawn	checked
B	21.12.2021	PLANNING UPDATES	JC	MM
A	14.06.2021	PLANNING SUBMISSION		SC

lead consultant

Gensler

Studio 405-409
4th Floor Custard Factory
Gibb Street, Digbeth
Birmingham, WMD
B9 4AA
England

Tel +44 (0) 12 1260 1600

client

Client Name

key plan



category

family

title

PROPOSED ELEVATIONS - HIGH STREET ELEVATION

project

13485, CAMDEN IN-LINE

189 CAMDEN HIGH STREET, LONDON NW1 7BP

project number	drawn	checked
026.41042.011	SC	RB

scale	date	rev
1 : 50@A1	21.12.2021	B

role	number
	A0.350

© Gensler 2021
All rights reserved, including but not limited to The Copyright, Design and Patents Act 1988