DEVISE ENGINEERS

53-54 Doughty Street, London WC1N 2PL

Structural engineer's report and feasibility

Contents

| Introduction | 2 |
|-------------------------------------|----|
| Construction | 2 |
| Structural Inspection | 3 |
| Feasibility of proposed alterations | |
| Conclusions | |
| Terms and limitations: | |
| | |
| Structural Calculations: | Α2 |

One

Introduction

Devise Structural Engineers were appointed by Doughty Street Chambers to visit the above property to carry out a structural inspection and confirm the feasibility of the proposed photovoltaic panels. We were specifically asked to review the following items from a nonintrusive inspection:

- General structural condition of the roof
- Feasibility to:
 - o Install photovoltaic panels on areas of the existing flat and pitched roofs

During the inspection, a general review of the structural integrity of the property was carried out as far as practicable without the removal of finishes.



Figure 1: Birdseye View of property (Google Earth)

Construction

The property is a 5-storey masonry constructed town house of solid masonry (c.330thk) external walls and masonry and timber internal walls. The property is currently being used as offices.

The main volume of the property has a double gable roof which has an area of flat roof behind the front parapet and above a plant space between the gables on no. 54.

Beyond the main volume of the property is a single storey extension with hip roof which is of more recent construction.



Figure 2: View of rear extension

Two

Structural Inspection

External observations

The front elevation appears to be in reasonable condition and comprises of rendered up to ground floor with exposed brickwork above.



Figure 3: Front Elevation

Some slight staining to the brickwork below was observed and some spalling to the brickwork seen but no significant structural defects were observed.

No significant structural defects were observed to the single-storey rear extension.

The chimney stacks show signs of historic movement, however they have been relatively recently repointed and are generally in reasonable condition for the age of the property.

Internal observations

The internal finishes have been well maintained with the occasional hair line crack visible.

No significant structural defects were observed though it should be noted that not all areas were accessed.

Loft & Roof observations

The rear gable roof was accessed, and the existing roof structure inspected.

The main roof rafters are 95x60 timbers at c.380mm centres with central ridge board.

There are signs of historic water ingress, and some local areas of damp however no significant structural defects were observed in the areas that were accessible.



Figure 4: Existing Roof Construction

Strengthening works have been carried out to support the water tanks within the roof space. These works include the addition of a new steel beam and doubled up timber joists positioned above the existing loft floor construction.



Figure 5: Strengthening Works

The existing gable roofs have a slate tile finish with lead work to the areas of flat roof. The finishes seem to be in reasonable condition with no significant defects observed.



Figure 6: Existing Roof Construction

3 | Page

Three

Feasibility of proposed alterations

Installation of Photovoltaic Panels

The existing roof structure has been assessed for the increased loading of the panels.

The loads assumed are:

- Panels installed on gable roofs,15 kg/m²
- Ballasted panels installed on flat roofs, 60 kg/m²

Calculations carried out in critical areas (see Appendix II) confirm that the existing roof construction is capable of supporting the proposed panel layout without additional strengthening works.




Figure 7: Proposed Roof Plan

Four

Conclusions

The property is in good condition for its age and constructed of good quality materials.

The photovoltaic panels proposed generally seem achievable as long as they are installed by a suitable contractor to the manufacturers specifications.

DEVISE ENGINEERS

Appendix 1

Terms and limitations:

- The appointment for the inspection and report is in accordance with ACE Agreement II
- This report was carried out without receipt of any further information from the Client unless specifically stated
- Access was available to those areas stated only
- No intrusive investigation was carried out nor was it possible to view behind furniture and fittings
- This report written in relation to the structural aspects of the building only
- This report is strictly for the use of the Client stated and submission to the local authority and should not be relied upon by any other third party
- Copying of this report for third parties is prohibited without express consent.

Appendix 2

Structural Calculations:

Loading Schedule

| | | | | | - | Permanent, Gk | Variable, Qk |
|-----------------------|------------------------------|----------------|------|-----------|-------|----------------------|------------------|
| Existing Pitched Roof | 35 ⁰ | | | | | | |
| | | thickness widt | h ce | ntres der | nsity | | |
| Gk | Joists 95x65 @ 440 | 95 | 65 | 440 | 6 | 0.08 | |
| | Sarking board | 20 | 1 | 1 | 6 | 0.12 | |
| | Slate Tiles | 3 | 1 | 1 | 25 | 0.08 | |
| | Insulation | 100 | 1 | 1 | 1 | 0.10 | |
| Gk, total | | | | | | 0.46 kN/m2 | |
| Qk | Access | | | | | L | 0.6 |
| Qk,total | | | | | | | 0.6 kN/m2 |
| Proposed Pitched Roo | f 35 ⁰ | | | | | | |
| , | | thickness widt | h ce | ntres der | nsity | | |
| Gk | Joists 95x65 @ 440 | 95 | 65 | 440 | 6 | 0.08 | |
| | Sarking board | 20 | 1 | 1 | 6 | 0.12 | |
| | Slate Tiles | 3 | 1 | 1 | 25 | 0.08 | |
| | PV | | | 2 | | 0.15 | |
| | Insulation | 100 | 1 | 1 | 1 | 0.10 | |
| Gk, total | | | | | - | 0.65 kN/m2 | |
| Qk | Access | | | | | L | 0.6 |
| Qk,total | | | | | | | 0.6 kN/m2 |
| | | | | | | | |
| Proposed Flat Roof | | thickness widt | h ce | ntres der | nsity | | |
| Gk | Joists 95x60 @ 380 | 95 | 60 | 400 | 6 | 0.09 | |
| | Sarking board | 20 | 1 | 1 | 6 | 0.12 | |
| | | | | | | 0.10 | |
| | | 5 | 1 | 1 | 20 | 0.10 | |
| | Finishes | 5 | 1 | 1 - | 20 | | |
| | Finishes PV | | | - | | 0.60 | |
| | Finishes PV Insulation | | - | | 1 9 | 0.60 0.10 | |
| Gk, total | Finishes PV | 100 | 1 | 1 | 1 | 0.60 | |
| Gk, total Qk | Finishes PV Insulation | 100 | 1 | 1 | 1 | 0.60 0.10 0.22 | 0.6 |

Gable Rafter Check

| Load | ing | Data |
|------|--------|------|
| LUGU | III IS | Date |

| Gk | 0.65 kN/m² | lyy | 4286875 mm ² |
|------|-----------------------|----------------|-------------------------|
| Qk | 0.6 kN/m ² | Wyy | 90250 mm ³ |
| b | 60 mm | kmod | 0.8 |
| h | 95 mm | kdef | 0.8 |
| c/c | 380 mm | γm | 1.25 |
| Span | 2500 mm | Timber Stre | ngth C24 |
| UDL | 0.475 SLS | 1.0Gk + 1.0 Qk | |
| | 0.68 ULS | 1.35Gk + 1.5Qk | |

1.0Gk + 0.7Qk

0.41 FIRE

Bending Strength

| f_{cmk} | 24 N/mm ² |
|-----------|-------------------------|
| f_{cmd} | 15.36 N/mm ² |

Design Moment 0.53 kNm

5.85 N/mm² 0.38 % utalisation

Shear Strength

 $\begin{array}{ccc} f_{vk} & & 2.5 \text{ N/mm}^2 \\ f_{vd} & & 1.6 \text{ N/mm}^2 \end{array}$

Design Shear 1.62 kN

0.43 N/mm² 0.27 % utalisation

Deflection Check

| E _{omean} | 11000 N/mm² |
|--------------------|----------------------------|
| E _{ofin} | 6111.111 N/mm ² |
| | _ |

2 0

 $\begin{array}{c} u_{\text{inst,total}} & 5.12 \text{ mm} \\ u_{\text{creep}} & 3.84 \text{ mm} \\ u_{\text{inst,imposed}} & 2.46 \text{ mm} \\ \text{Total Limit} & 10.0 \text{ mm} \\ \text{Post Construction Limit} & 6.9 \text{ mm} \end{array}$

Total Deflection 8.96 mm 0.90 % utalisation Post Construction Deflection 6.30 mm 0.91 % utalisation

Flat Roof Check

| Loading Data | | | | |
|------------------|-------------------------|----------------|-----------------|-------------------------|
| Gk | 1.22 kN/m ² | | lyy | 4286875 mm ⁴ |
| Qk | 0.6 kN/m ² | | Wyy | 90250 mm ³ |
| b | 60 mm | | kmod | 0.8 |
| h | 95 mm | | kdef | 0.8 |
| c/c | 380 mm | | γm | 1.25 |
| Span | 1800 mm | | Timber Strength | C24 |
| UDL | 0.6916 SLS | 1.0Gk + 1.0 Qk | | |
| | 0.97 ULS | 1.35Gk + 1.5Qk | | |
| | 0.62 FIRE | 1.0Gk + 0.7Qk | | |
| Bending Strength | | | | |
| f_{cmk} | 24 N/mm ² | | | |
| $f_{\rm cmd}$ | 15.36 N/mm ² | | | |
| Design Moment | 0.39 kNm | | | |
| σ_{myd} | 4.34 N/mm ² | | | |
| | 0.28 % utalisat | ion | | |
| Shear Strength | | | | |
| f_{vk} | 2.5 N/mm ² | | | |
| f_{vd} | 1.6 N/mm ² | | | |
| Design Shear | 1.62 kN | | | |
| $	au_{d}$ | 0.43 N/mm ² | | | |

Deflection Check

 $\mathsf{E}_{\mathsf{omean}}$

| E _{ofin} | 6111.111 | N/mm ² |
|---------------------------|----------|-------------------|
| ψ_2 | 0 | |
| | | |
| U _{inst,total} | 2.00 | mm |
| U _{creep} | 1.94 | mm |
| U _{inst,imposed} | 0.66 | mm |
| Total Limit | 7.2 | mm |
| Post Construction Limit | 5.0 | mm |
| | | |

Total Deflection3.94 mm0.55 % utalisationPost Construction Deflection2.60 mm0.52 % utalisation

0.27 % utalisation

11000 N/mm²