

# Mr Banks Church Row

Smiths Technical Systems  
365-369 Bexley Road Erith Kent DA8 3EZ  
Tel: 020 8303 2280  
Email: enquiries@smithstechnical.co.uk  
www.smithstechnical.co.uk



Integrated Security & Fire Installations

Client Mr David Banks  
C/O Mr Martin Liechti  
12 Church Row  
London  
NW3 6UT

Project	12 Church Row CCTV
Our Reference	PF/SF/KB2281
Date	8.04.22

Dear Mr Liechti,

Following your email dated 8.04.22 regarding the recent correspondence from Camden Council Development Management and application ref2021/13081/1 and with reference to item 4 I can confirm the below will be carried out.

- Cameras will be installed in positions as indicated on the supplied drawings
- Each of the camera cables into the actual cameras will have an access hole of approximately 20mm drilled from the outside in, the holes will be covered up by the cameras and therefore not seen
- The cameras will be screwed into the face brick work using raw plugs and screws
- The cables will be surface fixed within the house as agreed
- There are now power requirements to the external cameras as they are POE.

I hope this meets with your requirements and look forward to hearing from you.

Kind Regards

A handwritten signature in black ink, appearing to read "Paul Farrer", written over a white background.

Paul Farrer  
Fire & Security Contracts Manager

