

Mr Banks Church Row

Smiths Technical Systems
365-369 Bexley Road Erith Kent DA8 3EZ
Tel: 020 8303 2280
Email: enquiries@smithstechnical.co.uk
www.smithstechnical.co.uk



Integrated Security & Fire Installations

Client	Mr David Banks C/O Mr Martin Liechti 12 Church Row London NW3 6UT
Project	12 Church Row CCTV
Our Reference	PF/SF/KB2281
Date	8.04.22/Revised 27.04.22

Dear Mr Liechti,

Following your email dated 8.04.22 regarding the recent correspondence from Camden Council Development Management and application ref2021/13081/I and with reference to item 4 I can confirm the below will be carried out.

- Cameras will be installed in positions as indicated on the supplied drawings
- Each of the camera cables into the actual cameras will have an access hole of under 20mm drilled from the outside in, the holes will be covered up by the cameras and therefore not seen, and will be drilled through mortar of the brickwork
- The cameras will be screwed into the face brick work using raw plugs and screws
- The cables will be surface fixed within the house as agreed
- There are no power requirements to the external cameras as they are POE.

I hope this meets with your requirements and look forward to hearing from you.

Kind Regards

Paul Farrer
Fire & Security Contracts Manager



Fire and Security Gold



Fire Industry Association

