

**Ground and Project**  
CONSULTANTS LTD



**40 Leighton Road**

**Ground Movement and Building  
Damage Assessment Report**

**May 2022**




Mat Jones and Louise Willocks  
40 Leighton Rd  
Kentish Town  
London  
NW5 2QE

**Final Report**

**Report No. 70572-2 Rev 2**

## Document Verification

Prepared for	Prepared by
Mat Jones and Louise Willocks 40 Leighton Rd Kentish Town London NW5 2QE	Ground and Project Consultants Ltd, The Hub First Floor 19-23 Stamford New Road Altrincham Greater Manchester WA14 1BN

Signatures and Approvals				
Reviewer	G Manning BSc (Hons) MSc FGS		Date	16/05/2022
Author	J Smithson BSc (Hons) MSc FGS CGeol		Date	16/05/2022
Approver	Phil Henry MEng CEng MICE Croft Structural Engineers		Date	16/05/22

Report Number	Revision	Date	Comments
70572	0	29/07/2022	Draft
	1	14/04/2022	Update to address Campbell Reith Comments
	2	16/05/2022	Update to address Campbell Reith Comments

---

## Disclaimer

Copyright of this Report is vested in Ground and Project Consultants Ltd and no part of it may be copied or reproduced by any means without prior written permission from Ground and Project Consultants Ltd. If you have received this Report in error, please destroy all copies in your possession and control and notify Ground and Project Consultants Ltd.

This report has been prepared by Ground and Project Consultants Ltd, with reasonable skill, care and diligence within the agreed scope and terms of contract and taking account of the manpower and resources devoted to it by agreement with its client, and is provided by Ground and Project Consultants Ltd solely for the use of its client, Mat Jones and Louise Willocks.

The advice and opinions in this report should be read and relied on only in the context of the report as a whole, taking account of the terms of reference agreed with the client. The findings are based on the information made available to Ground and Project Consultants Ltd at the date of the report (and will have been assumed to be correct) and on current UK standards, codes, technology and practices as at that time. They do not purport to include any manner of legal advice or opinion. New information or changes in conditions and regulatory requirements may occur in future, which will change the conclusions presented here.

This report is confidential to the client. Unless otherwise agreed in writing by Ground and Project Consultants Ltd, no other party may use, make use of or rely on the contents of the report. No liability is accepted by Ground and Project Consultants Ltd for any use of this report, other than for the purposes for which it was originally prepared and provided.

---

## Non-Technical Summary

The Land Stability BIA and GMA reports were carried out by Jon Smithson, Director of Ground and Project Consultants Ltd, Chartered Geologist (CGeol), with over 35 years' experience.

The BIA (Report Ref 70572-1) concluded that the construction of a basement at the site should not have any significant impacts on land stability. However, geotechnical testing of the London Clay Formation determined it to have very high plasticity and volume change potential. This increases the risk of movement and damage to medium due to this development. There is risk to trees on site that are within a conservation zone. Foundations should be placed at appropriate depths to avoid the effects of water content changes and root damage.

Detailed GMA and Building Damage Assessment found the potential risk to neighbouring properties to be in the Very Slight category. This is understood to be an acceptable level of risk. Most ground movement will occur during excavation of the basement and construction so the adequacy of the temporary support will be critical in limiting ground movements. Monitoring should be carried out to make sure the movements are within acceptable limits.

---

## Table of Contents

<b>1</b>	<b>Introduction.....</b>	<b>1</b>
<b>2</b>	<b>Background Information.....</b>	<b>2</b>
2.1	Site Description .....	2
2.2	Proposals.....	2
2.3	Geology .....	3
2.4	Hydrogeology .....	3
<b>3</b>	<b>Assessment of Ground Movement.....</b>	<b>4</b>
<b>4</b>	<b>Assessment of Building Damage .....</b>	<b>7</b>
4.1	Movement due to wall installation and excavation following C760.....	7
4.2	Geo5 Sheeting Check Analysis.....	8
4.3	Geo5 FEM Analysis.....	9
<b>5</b>	<b>Monitoring.....</b>	<b>10</b>
<b>6</b>	<b>Conclusions.....</b>	<b>11</b>

## Figures & Tables

Table 1: Property Dimensions and Proximity.....	5
Table 2: Ground Model .....	6
Table 3: Damage Assessment using the Burland Scale .....	7
Table 4: Geo 5 Sheeting Check Results .....	8
Table 5: Geo 5 FEM Results.....	9
Table 6: Monitoring Alerts and Actions .....	10

## Appendices

Appendix A: Drawings

Appendix B: Calculations

Appendix C: Geo5 Outputs

## 1 Introduction

Ground and Project Consultants Ltd (GPCL) have been instructed by Mat Jones and Louise Willocks to carry out a Ground Movement Assessment for the proposed basement at 40 Leighton Road. A Basement Impact Assessment has been previously carried out (Reference 70572-1), dated April 2021.

The objectives of this report are to ascertain the expected ground movements and degree of any building damage at the structures adjacent to the site.

The scope of this report and approach are as follows:

- Summarise the expected ground conditions at the site;
- Develop an understanding of the proposals and their relationship to adjacent structures;
- Carry out an assessment of ground movement following the principles and procedures set out in C760 "Guidance on Embedded Retaining Wall Design";
- Carry out a parallel check using Geo5 'Sheeting Check' software and GEO5 'FEM'.

This report has been prepared and approved by Jon Smithson, BSc, MSc, FGS, CGeol who is a chartered geologist with over 35 years' experience.

---

## 2 Background Information

### 2.1 Site Description

The site is located at 40 Leighton Road, Kentish Town, London, NW5 2QE. The site is in the London Borough of Camden. The National Grid Reference for the site is 529199, 185173.

The site is currently a two-storey terraced property with basement. It is understood the basement is approximately 2.5m in height. A small area of hardstanding is present to the front of the property and a garden with semi-mature trees to the rear of the property approximately 14m in length. The garden is accessed from the basement via steps which has a level higher than the basement but lower than the ground floor.

The site is bound and adjoined by Leighton Road to the north, 38 Leighton Road to the west, 42 Leighton Road to the east. Peckwater Health Centre is to the south. The terraces to the east of the property (No. 42) appear to have partial basements from Google Earth with stairs leading up to the front door. It is understood that the basement of No. 42 extends beneath the footprint of the main building. The property to the west (No. 38) has a basement extension visible on photos from the Existing Drawings and Photos in Appendix A. It is understood that the basement at No. 38 starts approximately 5m or 6m back from the front of the property and extending below a rear extension and external patio.

It is believed that the walls of the existing structure are underpinned by adjacent basement walls of the neighbouring properties or the original footings where no basement extensions have taken place.

There is a mature tree on the pavement to the front of the property.

No underground railways are anticipated beneath the site.

The site is in a Conservation Area.

The site is at approximately 40.2m AOD. The wider area slopes gently to the southeast at less than 2 degrees.

### 2.2 Proposals

The proposals for the site comprise the redevelopment of an existing residential property including the deepening of the existing basement to approximately 3.5m bgl (***excavating approximately 1m deeper than existing***), the addition of a basement light well to the front of the property, an extension with skylight to the rear of the property, removal of internal walls (including in the basement), extension of the first floor to the rear and the addition of a loft floor with new roof plan. A new garden room is also proposed to the rear of the garden to the very south of the site.

The construction method proposed includes casting new retaining walls in segments, installing lateral props at high and low level as the excavations progress. The floor slab is proposed to be partially suspended.

### 2.3 Geology

The ground investigation revealed that the geology comprises Made Ground to depths of up to 1.4m bgl, overlying firm to stiff London Clay Formation proven to 10.45m bgl. Roots were recorded to 1.5m bgl.

### 2.4 Hydrogeology

The London Clay Formation is an unproductive aquifer. Groundwater was not encountered during drilling or monitoring (>5.3m bgl), well below basement depth. However, groundwater levels may vary seasonally.



---

### 3 Assessment of Ground Movement

Movements have been assessed for the neighbouring properties and structures as follows:

- 38 Leighton Road
- 42 Leighton Road

Drawings which have been used in assessing basement and distances to adjoining and nearby structures are included in Appendix A. It is understood that the existing basement is to be deepened from approximately 2.5m bgl to 3.5m bgl, level with the proposed basement extension.

This assessment has taken into account that the underpinning will be in a hit and miss sequence and that shoring and horizontal propping will be used. Whilst it is acknowledged that the basement depth and excavation will be shallow relative to existing foundations ***the construction method should not leave existing foundations unsupported or vulnerable to ground movement from unsupported excavations or steeply battered excavation slopes.***

It is important to note that CIRIA report C760 is written for embedded retaining walls. Whereas the basement wall is constructed in short panels and each is cast against the exposed soil. Therefore, movement calculations for the excavation of soil and installation of underpins does not strictly apply to C760. There is no recognised method for calculating ground movements due to underpinned basements. C760 is used as a convenient and recognised approach. Calculations have been carried out using Geo5 Sheeting Check software for the basement retaining walls. For comparison we have allowed for wall installation.

It is recognised that settlements are generally minor where care in construction and appropriate precautionary measures are taken in this type of basement construction.

It is recommended that where the understanding of movements is significant, appropriate instrumentation should be installed to monitor ground movement before and during construction.

Design drawings developed by the engineer have been reviewed and used to inform this assessment.

The following key assumptions have been made:

- The detailed design of the basement (and associated temporary works) has been carried out by an appropriately qualified and experienced structural engineer, to current professional standards and best practice.
- The maximum excavation depth is approximately 3.5m below existing ground level.

- The method of basement construction will be as per the drawings, see note above, and will be carried out with due skill and care by an appropriately experienced contractor.
- A high wall stiffness has been assumed.
- The wall will be propped promptly using closely spaced props in the temporary case.
- In the permanent case the wall will be permanently propped at floor level and ceiling level.

For the purposes of the calculations, the parameters of the subject properties have been estimated as included in Table 1.

**Table 1: Property Dimensions and Proximity**

Property	Distance from basement (m)	Height (m)	Length (m)	Width (m)	Differential Basement depth (m) <sup>*3</sup>
38 Leighton Road	0	9	16.5	5	3.5 <sup>*1</sup>
42 Leighton Road	0	9.5	10	5	2 <sup>*2</sup>

<sup>\*1</sup>Front part of house only, rear has existing 2.5m basement

<sup>\*2</sup> Maximum anticipated differential depth.

<sup>\*3</sup> Note that the basement is largely being deepening by 1m.

It is assumed that the soils are competent soils as encountered in the ground investigation. Made Ground was encountered to approximately 1.4m bgl, overlying firm to stiff clay of the London Clay Formation. Groundwater was not encountered.

The ground model used during the analyses is shown in Table 2 below. Characteristic values have been assigned to the weathered London Clay obtained from SPT correlations and published research. Values of Young's modulus have been derived using the empirical formula  $E_u=400C_u$  outlined in CIRIA C580.

Table 2: Ground Model

Strata	Unit Weight (kN/m <sup>2</sup> )	Effective angle of friction (deg)	Effective cohesion (kPa)	Drained Youngs Modulus, E' (MPa) <sup>1</sup>	Poisson Ratio
Made Ground	17	20	0	8	0.3
London Clay	19	22	0	14	0.2

<sup>1</sup>Based on  $E' = 0.6E_u$  for stiff clays. Look, B., 2007. *Handbook of geotechnical investigation and design tables*.

## 4 Assessment of Building Damage

### 4.1 Movement due to wall installation and excavation following C760

The following ground movements have been calculated in relation to ground movements, using Figure 6.16 in C760.

**Table 3: Damage Assessment using the Burland Scale**

Property	Maximum Vertical Deflection $\Delta$ (mm)	Maximum Horizontal Movement dh (mm)	Building Damage Assessment
38 Leighton Road	3	2	1 Very Slight
42 Leighton Road	3	2	1 Very Slight

Ground movement contour plots are included in Appendix A.

\*In addition to assessing ground movement, some consideration should be given whether to include an allowance for the shrinkage of the dry pack at the wall. It is considered (and the experience of past project reports) that the dry pack may shrink nominally at the wall only.

Burland Scale categories 0, 1, and 2 refer to aesthetic damage, category 3 and 4 relate to serviceability and function, and 5 represents damage which relates to stability. The main objective of design and construction is to maintain a level of risk to buildings no higher than category 2 where only aesthetic damage is considered acceptable.

Note that the figures above do not necessarily represent the total ground movement but the maximum differential movements which are predicted to be experienced by the building. The ground movement and building damage calculations are appended.

The calculations assume that the wall is propped and that the wall and excavation are adequately supported in the temporary case.

There are a number of key points to note in using this assessment:

- Most ground movement will occur during excavation of the basement and construction so the adequacy of temporary support will be critical in limiting ground movements.
- The speed of propping and support is key to limiting ground movements and limiting unpropped wall heights.
- Good workmanship will contribute to minimising ground movements.

- The calculation assumes the wall is in competent soil as per the findings of the ground investigation.

Ground movement can be minimised by adopting a number of measures, including:

- Ensuring that adequate propping and support is in place at all times during construction.
- Installation of the first (stiff) support quickly and early in the construction sequence.
- Avoid leaving ground unsupported.
- Minimise deterioration of the unexcavated soil mass by the use of blinding/covering with a waterproof membrane.
- Avoid overbreak.
- The control and appropriate design of any dewatering process must ensure that fines removal and drawdown are minimised.

It must be noted that the movements are calculated values based on the findings and methods of CIRIA C760. Larger movements may be generated if anyone or any combination of the above recommendations and/or assumptions are not heeded or if ground conditions are different from those anticipated by the investigation.

The actual magnitude of these movements will depend upon a number of factors described above and the nature of the ground expected may give rise to larger movements.

#### 4.2 Geo5 Sheeting Check Analysis

Further assessment of the basement construction on the adjacent properties has been carried out using “Sheeting Check” developed by GEO5 for 1m of basement deepening. The results are included in Table 4 below.

**Table 4: Geo 5 Sheeting Check Results**

Property	Maximum Vertical Movement (mm)	Distance from the wall (m)	Maximum Horizontal Movement (mm)	Building Damage Assessment
38 Leighton Road	1	~0.7	0	0 Negligible
42 Leighton Road	1	~0.7	0	0 Negligible

The results are broadly in line with the CIRIA C760 method results. The output sheets are provided in Appendix D. Note that since a basement already exists the maximum movement is taken for the last stage only.

---

Computer analysis demonstrates that ground movements are highly sensitive to prop and wall stiffness, so the use of stiff props both in the temporary and permanent cases is essential.

#### 4.3 Geo5 FEM Analysis

Analysis of ground movement has been carried out using GEO5 FEM software to provide a check and generate a visualisation of ground movement.

The location of the services modelled in our analysis are shown in Appendix C. An electricity service has been modelled at a depth of 0.5m bgl and at a distance of 0.5m from the excavation, a water utility has been modelled 1.2m bgl and at a distance of 2.5m from the excavation and a sewage utility has been modelled 2m bgl and at a distance of 4.5m from the excavation beneath the road.

**Table 5: Geo 5 FEM Results**

<b>Structure</b>	<b>Maximum Vertical Movement (mm)</b>	<b>Maximum Horizontal Movement (mm)</b>
38 Leighton Road	1	0
42 Leighton Road	1	0
Utilities	1	0

The calculated settlements are similar to those calculated using the C760 method. The output is included within Appendix C.

## 5 Monitoring

Expected movements are such that they may not manifest themselves in monitoring through survey work. The GMA has predicted that building damage will fall into the “very slight” category. We suggest the system of alerts and actions in table 3 below. These should be developed and finalised by the Structural Engineer.

**Table 6: Monitoring Alerts and Actions**

<b>Amount of horizontal/vertical movement recorded</b>	<b>Action</b>	<b>Comments</b>
0 to 3mm	None, continue monitoring	Damage likely to be negligible
3 to 8 mm	Inform engineer, engineer to visit site	Damage likely to be negligible or very slight
>8 mm	Cease work. Inform engineer, engineer to visit site and advise on changes to working practice etc	Damage likely to be slight or worse

## 6 Conclusions

The results of the Ground Movement Assessment and Building Damage Assessment have found that the potential risk to the neighbouring properties is in the Very Slight category. This is understood to be an acceptable level of risk. The results of the FEM analysis indicate <1mm of ground movement to surrounding utilities.

The basement will be constructed mainly in the London Clay Formation with some Made Ground near the surface. Uncontrolled groundwater seepages may cause fines to washout in the short term. Most ground movement will occur during excavation of the basement and construction so the adequacy of the temporary support will be critical in limiting ground movements.

Monitoring should be carried out to make sure the movements are within acceptable limits.




---


# Appendix A


## Drawings

**EXISTING PLANS**


**KEY LABEL**

 - Boundary line


 - Existing walls




**BASEMENT PLAN** SCALE 1:100 @A3



**GROUND FLOOR PLAN** SCALE 1:100 @A3



**FIRST FLOOR PLAN** SCALE 1:100 @A3



**ROOF PLAN** SCALE 1:100 @A3





# Proficiency

Design & Build

663 FINCHLEY ROAD, HAMPSTEAD  
LONDON  
NW2 2HN

TEL. 02074356231  
PROFICIENCYARCHITECT@GMAIL.COM  
WWW.PROFICIENCYLTD.CO.UK

RIBA  

Royal Institute of  
British Architects

Architects Registration Board

**PLEASE NOTE**

- All dimensions to be verified on site.
- All dimensions are in millimeters.
- No work shall commence until all approvals and agreements have been obtained. These include, Planning, Building Regulations, Thames Water and party Wall.
- The Copyright of this drawing belongs to Proficiency Design & Build.

CLIENT:  
**MAT & LOUISE**

PROJECT:  
**BASEMENT EXTENSION +  
ONE STOREY REAR  
EXTENSION +  
MANSARD**

ADDRESS:  
**40 LEIGHTON RD, LONDON  
NW5 2QE**

TITLE:  
**EXISTING  
PLANS**

DATE:  
**08/01/2021**

PROJECT NUM:  
**P-019**




SCALE:  
**1/100 (@ A3)**

DRAWING NUM:  
**EX-01**

REV:  
**A**

STATUS:

**EXISTING ELEVATIONS**



# Proficiency

## Design & Build

663 FINCHLEY ROAD, HAMPSTEAD  
 LONDON  
 NW2 2HN

TEL. 02074356231  
 PROFICIENCYARCHITECT@GMAIL.COM  
 WWW.PROFICIENCYLTD.CO.UK

RIBA   
 Royal Institute of  
 British Architects



- PLEASE NOTE
1. All dimensions to be verified on site.
  2. All dimensions are in millimeters.
  3. No work shall commence until all approvals and agreements have been obtained. These include, Planning, Building Regulations, Thames Water and party Wall.
  4. The Copyright of this drawing belongs to Proficiency Design & Build.

CLIENT:  
**MAT & LOUISE**

PROJECT:  
**BASEMENT EXTENSION +  
 ONE STOREY REAR  
 EXTENSION +  
 MANSARD**

ADDRESS:  
**40 LEIGHTON RD, LONDON  
 NW5 2QE**

TITLE:  
**EXISTING  
 ELEVATIONS**

DATE: <b>08/01/2021</b>	PROJECT NUM: <b>P-019</b>
----------------------------	------------------------------

SCALE: <b>1/100 (@ A3)</b>	DRAWING NUM: <b>EX-02</b>
-------------------------------	------------------------------

REV: <b>A</b>	STATUS:
------------------	---------



- No.40 Front Elevation



- No.40 Front Elevation context




- No.40 Rear Elevation



- No.42 (Left Hand Side Neighbour) rear elevation context



- No.38 (Right Hand Side Neighbour) rear elevation context



- No.40 Rear Garden



**Proficiency**  
Design & Build

663 FINCHLEY ROAD, HAMPSTEAD  
LONDON  
NW2 2HN

TEL. 02074356231  
PROFICIENCYARCHITECT@GMAIL.COM  
WWW.PROFICIENCYLTD.CO.UK

RIBA  
Royal Institute of  
British Architects



PLEASE NOTE

1. All dimensions to be verified on site.
2. All dimensions are in millimeters.
3. No work shall commence until all approvals and agreements have been obtained. These include, Planning, Building Regulations, Thames Water and party Wall.
4. The Copyright of this drawing belongs to Proficiency Design & Build.

CLIENT:

**MAT & LOUISE**

PROJECT:

**BASEMENT EXTENSION +  
ONE STOREY REAR  
EXTENSION +  
MANSARD**

ADDRESS:

**40 LEIGHTON RD, LONDON  
NW5 2QE**

TITLE:

**PHOTOGRAPHS**

DATE:

**08/01/2021**

PROJECT NUM:

**P-019**

SCALE:

**1/100 (@ A3)**

DRAWING NUM:

**EX-03**

REV:

**A**

STATUS:

**PROPOSED PLANS**

**NOTE:**

- DEMOLITIONS OMITTED FOR CLARITY  
- DESIGN SUBJECT TO INVESTIGATION


- Boundary line  
- Existing walls

- Proposed Stud wall  
- Proposed External wall


**KEY LABEL**

- Proposed new floor  
- Proposed new roof


- Demolished wall




**BASEMENT PLAN** SCALE 1:100 @A3




**GROUND FLOOR PLAN** SCALE 1:100 @A3



**FIRST FLOOR PLAN** SCALE 1:100 @A3



**LOFT PLAN** SCALE 1:100 @A3



**ROOF PLAN** SCALE 1:100 @A3



# Proficiency

## Design & Build

663 FINCHLEY ROAD, HAMPSTEAD  
LONDON  
NW2 2HN

TEL. 02074356231  
PROFICIENCYARCHITECT@GMAIL.COM  
WWW.PROFICIENCYLTD.CO.UK

RIBA

Royal Institute of  
British Architects



**PLEASE NOTE**

1. All dimensions to be verified on site.
2. All dimensions are in millimeters.
3. No work shall commence until all approvals and agreements have been obtained. These include, Planning, Building Regulations, Thames Water and party Wall.
4. The Copyright of this drawing belongs to Proficiency Design & Build.

**CLIENT:**

**MAT & LOUISE**

**PROJECT:**

**BASEMENT EXTENSION +  
ONE STOREY REAR  
EXTENSION + MANSARD**

**ADDRESS:**

**40 LEIGHTON RD, LONDON  
NW5 2QE**

**TITLE:**

**PROPOSED  
PLANS**

**DATE:**

**19/01/2021**

**PROJECT NUM:**

**P-019**

**SCALE:**

**1/100 (@ A3)**

**DRAWING NUM:**

**PR-01**

**REV:**

**A**

**STATUS:**


**PROPOSED ELEVATIONS**

**NOTE:**

- DEMOLITIONS OMITTED FOR CLARITY
- DESIGN SUBJECT TO INVESTIGATION

**KEY LABEL**

— — — — — - Boundary line




**LEFT HAND SIDE ELEVATION**

**SCALE 1:100 @A3**




**FRONT ELEVATION**

**SCALE 1:100 @A3**



**RIGHT HAND SIDE ELEVATION**

**SCALE 1:100 @A3**



**REAR ELEVATION**

**SCALE 1:100 @A3**



**Proficiency**  
Design & Build

663 FINCHLEY ROAD, HAMPSTEAD  
LONDON  
NW2 2HN

TEL.02074356231  
PROFICIENCYARCHITECT@GMAIL.COM  
WWW.PROFICIENCYLTD.CO.UK

**RIBA**   
Royal Institute of  
British Architects



**PLEASE NOTE**

1. All dimensions to be verified on site.
2. All dimensions are in millimeters.
3. No work shall commence until all approvals and agreements have been obtained. These include, Planning, Building Regulations, Thames Water and party Wall.
4. The Copyright of this drawing belongs to Proficiency Design & Build.

**CLIENT:**

**MAT & LOUISE**

**PROJECT:**

**BASEMENT EXTENSION +  
ONE STOREY REAR  
EXTENSION + MANSARD**

**ADDRESS:**

**40 LEIGHTON RD, LONDON  
NW5 2QE**

**TITLE:**

**PROPOSED  
ELEVATIONS**

**DATE:**

**19/01/2021**

**PROJECT NUM:**

**P-019**

**SCALE:**

**1/100 (@ A3)**

**DRAWING NUM:**


**PR-02**

**REV:**

**A**

**STATUS:**

**PROPOSED SECTIONS: AA & BB**



**Proficiency**  
Design & Build

663 FINCHLEY ROAD, HAMPSTEAD  
LONDON  
NW2 2HN

TEL. 02074356231  
PROFICIENCYARCHITECT@GMAIL.COM  
WWW.PROFICIENCYLTD.CO.UK

RIBA  
Royal Institute of  
British Architects



**PLEASE NOTE**

1. All dimensions to be verified on site.
2. All dimensions are in millimeters.
3. No work shall commence until all approvals and agreements have been obtained. These include, Planning, Building Regulations, Thames Water and party Wall.
4. The Copyright of this drawing belongs to Proficiency Design & Build.

CLIENT:  
**MAT & LOUISE**

PROJECT:  
**BASEMENT EXTENSION +  
ONE STOREY REAR  
EXTENSION + MANSARD**


ADDRESS:  
**40 LEIGHTON RD, LONDON  
NW5 2QE**

TITLE:  
**PROPOSED  
SECTIONS: AA & BB**

DATE: <b>19/01/2021</b>	PROJECT NUM: <b>P-019</b>
----------------------------	------------------------------


SCALE: <b>1/100 (@ A3)</b>	DRAWING NUM: <b>PR-02</b>
-------------------------------	------------------------------

REV: <b>A</b>	STATUS:
------------------	---------



**Basement Existing**

Scale 1:100



**Basement Proposed**

Scale 1:100

Rev	Date	By	Amendments
-	09.03.2021	SC	First Issue

Job Number <b>210221</b>	Dwg Number <b>SL-101</b>
Scale <b>As shown @A1</b>	Rev <b>-</b>
By <b>SC</b>	Approved by <b>GW</b>


Client <b>Matthew Jones &amp; Louise Willcocks</b>
Property <b>40 Leighton Road, Kentish Town, Camden, NW5 2QE</b>
Drawing Title <b>Foundation Loading</b>

**Croft Structural Engineers**

Clockshop Mews,  
r/o 60 Saxon Rd,  
London, SE25 5EH.  
020 8684 4744  
www.croftse.co.uk


Issued for **INFORMATION ONLY**





**Basement Existing**

Scale 1:100



**Basement Proposed**

Scale 1:100

Rev	Date	By	Amendments
-	09.03.2021	SC	First Issue

Job Number <b>210221</b>	Dwg Number <b>SL-101</b>
Scale As shown @A1	Rev -
By <b>SC</b>	Approved by <b>GW</b>

Client <b>Matthew Jones &amp; Louise Willcocks</b>
Property <b>40 Leighton Road, Kentish Town, Camden, NW5 2QE</b>
Drawing Title <b>Foundation Loading</b>

**Croft Structural Engineers**

Clockshop Mews,  
r/o 60 Saxon Rd,  
London, SE25 5EH.  
020 8684 4744  
www.croftse.co.uk

Issued for **INFORMATION ONLY**

---

# Appendix B

## Calculation Spreadsheets

<b>Project</b>	40 Leighton Rd		
<b>Project No.</b>	70572		
<b>Calc Title</b>	Ground Movement Assessment adjoining properties		
<b>Date</b>	13 April 2022	<b>Rev</b>	1

**House Details, Background Data and Assumptions**

Calculations based on C760 Pg155,

<b>Building</b>	<b>38/42 Leighton Rd</b>
Ground Level (m AOD)	
Basement Depth (m)	1.0
Basement Floor level (m AOD)	
Effective Basement Depth (m)	1.0
Wall Depth (m)	1.0
Length (m)	5.0
Height (m)	9.5
Distance (m)	0.0
Far Side (m)	5.0

**Movement Calculations for Wall Installation**

<b>Horizontal</b>					<b>Relevance to Adjacent Properties</b>
<b>Distance from wall/wall depth (m)</b>	<b>Distance (m)</b>	<b>Movement/ Wall Depth (%)</b>	<b>Horizontal Movement (mm)</b>		
0.0	0.0	0.080	0.80	NS	
0.1	0.1	0.070	0.70		
0.2	0.2	0.075	0.75		
0.3	0.3	0.060	0.60		
0.4	0.4	0.050	0.50		
0.5	0.5	0.044	0.44		
0.6	0.6	0.040	0.40		
0.7	0.7	0.035	0.35		
0.8	0.8	0.030	0.30		
0.9	0.9	0.020	0.20		
1.0	1.0	0.018	0.18		
1.1	1.1	0.015	0.15		
1.2	1.2	0.012	0.12		
1.3	1.3	0.010	0.10		
1.4	1.4	0.005	0.05		
1.5	1.5	0.000	0.00	FS	
<b>Vertical</b>					<b>Relevance to Adjacent Properties</b>
<b>Distance from wall/wall depth (m)</b>	<b>Distance (m)</b>	<b>Movement/ Wall Depth (%)</b>	<b>Vertical Movement (mm)</b>		
0.0	0.0	0.050	0.5	NS	
0.1	0.1	0.048	0.5		
0.2	0.2	0.046	0.5		
0.3	0.3	0.042	0.4		
0.4	0.4	0.040	0.4		
0.5	0.5	0.037	0.4		
0.6	0.6	0.035	0.4		
0.7	0.7	0.032	0.3		
0.8	0.8	0.029	0.3		
0.9	0.9	0.027	0.3		
1.0	1.0	0.025	0.3		
1.1	1.1	0.023	0.2		
1.2	1.2	0.020	0.2		
1.3	1.3	0.018	0.2		
1.4	1.4	0.016	0.2		
1.5	1.5	0.014	0.1		
1.6	1.6	0.011	0.1		
1.7	1.7	0.009	0.1		
1.8	1.8	0.007	0.1		
1.9	1.9	0.004	0.0		
2.0	2.0	0.000	0.0	FS	

**Deflection Ratio**

	<b>38/42 Leighton Rd</b>
<b>dh</b>	0.8
<b>Delta</b>	0.5

Project:	40 Leighton Rd		
Project No.	70572		
Calc Title	Ground Movement Assessment adjoining properties		
Date:	13 April 2022	Rev	1

**Assumptions**

Calculations based on C760 Fig. 6.15 assume system stiffness =1000, FOS against base heave >3. zero at 3 x excavation depth as Fig. 6.11 a) and b)

High Stiffness	0.0075
----------------	--------

**Movement Calculations for Excavation**

Horizontal				
Distance from wall/excavation depth (m)	Distance (m)	Horizontal Movement/ Wall Depth (%)	Horizontal Movement (mm)	Relevance to Adjacent Properties
0.0	0.0	0.15	1.5	NS
0.2	0.2	0.1425	1.4	
0.4	0.4	0.135	1.4	
0.6	0.6	0.1275	1.3	
0.8	0.8	0.12	1.2	
1.0	1.0	0.1125	1.1	
1.2	1.2	0.105	1.1	
1.4	1.4	0.0975	1.0	
1.6	1.6	0.09	0.9	
1.8	1.8	0.0825	0.8	
2.0	2.0	0.075	0.7	
2.2	2.2	0.0675	0.7	
2.4	2.4	0.06	0.6	
2.6	2.6	0.0525	0.5	
2.8	2.8	0.045	0.4	
3.0	3.0	0.0375	0.4	
3.2	3.2	0.03	0.3	
3.4	3.4	0.0225	0.2	
3.6	3.6	0.015	0.1	
3.8	3.8	0.0075	0.1	
4.0	4.0	0	0.0	
				FS

Vertical				
Distance from wall/excavation depth (m)	Distance (m)	Settlement/ Excavation Depth (%)	Settlement (mm)	Relevance to Adjacent Properties
0.0	0	0.040	0.40	NS
0.2	0.2	0.050	0.50	
0.4	0.4	0.070	0.70	
0.6	0.6	0.080	0.80	
0.8	0.8	0.075	0.75	
1.0	1	0.070	0.70	
1.2	1.2	0.060	0.60	
1.4	1.4	0.060	0.60	
1.6	1.6	0.050	0.50	
1.8	1.8	0.040	0.40	
2.0	2	0.035	0.35	
2.2	2.2	0.030	0.30	
2.4	2.4	0.025	0.25	
2.6	2.6	0.020	0.20	
2.8	2.8	0.015	0.15	
3.0	3	0.010	0.10	
3.2	3.2	0.005	0.05	
3.4	3.4	0.000	0.00	
				FS

**Deflection Ratio**

	38/42 Leighton Rd
dh	0.98
Delta	0.20

<b>Project:</b>	40 Leighton Rd		
<b>Project No.</b>	70572		
<b>Calc Title</b>	Ground Movement Assessment adjoining properties		
<b>Date:</b>	13 April 2022	<b>Rev</b>	1

**Combined for Wall Installation and Excavation**

	<b>38/42 Leighton Rd</b>
<b>dh</b>	1.8
<b>Delta</b>	3.4

**Movement Assessment**

<b>38/42 Leighton Rd</b>			
Horiz Strain (%)	dh/L	0.04	
Deflection Ratio (%)	Delta/L	0.07	
From Graph Fig 6.27 c	Damage Category	1 Very Slight	
From Graph Fig 6.27 b	Try elim	0.075	upper limit of damage category Table 6.4
L/H	0.53	Therefore eh/elim	0.5
Reading off Fig 6.27 b for closest L/H curve this gives		0.9	
Delta/L/ elim			
L	5000		
Therefore Delta = L x Reading x elim			
Delta (mm)	3.4		
Delta for combined wall installation and excavation is less :Damage category is confirmed as		1 Very Slight	

---

# Appendix C


## Geo5 Outputs

# 40 Leighton Road – Horizontal Movement Contours

0mm

1mm

2mm




# 40 Leighton Road – Vertical Movement Contours

0mm

1mm

1mm






---

# Appendix C

## Geo5 Outputs

Name :

Stage : 3



Results : comp. to prev. stage; variable : Displacement d<sub>x</sub>; range : <-0.097; 0.080> mm


**Stress analysis was successfully completed.**

Analysis settings : **standard**

Attained loading = 100.00 %

Name :

Stage : 3



Results : comp. to prev. stage; variable : Displacement d<sub>z</sub>; range : <-0.005; 0.555> mm


**Stress analysis was successfully completed.**

Analysis settings : **standard**

Attained loading = 100.00 %

Name :

Stage : 3




**Stress analysis was successfully completed.**

Analysis settings : **standard**

Attained loading = 100.00 %

Name :

Stage : 3




**Stress analysis was successfully completed.**

Analysis settings : **standard**

Attained loading = 100.00 %

Results : comp. to prev. stage; variable : Displacement  $d_z$ ; range : <-0.0087; 0.5960> mm




**Stress analysis was successfully completed.**

Analysis settings : **user-defined**

Attained loading = 100.00 %

Results : comp. to prev. stage; variable : Displacement  $d_x$ ; range : <-0.140; 0.139> mm



Stress analysis was successfully completed.

Analysis settings : **user-defined**

Attained loading = 100.00 %